



Public Water System Chlorination and Pre-treatment Project

## **Environmental Assessment**

**September 2022**

**PRUDENCE ISLAND WATER DISTRICT**

PO Box 93  
Prudence Island, RI 02872  
(401) 683-0011

## Table of Contents

<b>1. INTRODUCTION .....</b>	<b>3</b>
<b>2. PROPOSED ACTIONS AND ALTERNATIVES .....</b>	<b>6</b>
<b>3. ENVIRONMENTAL IMPACTS, CONSEQUENCES, AND MITIGATION .....</b>	<b>8</b>
3.1 SOILS .....	8
3.2 LAND USE AND PLANNING .....	10
3.2.1 ZONING.....	10
3.2.2 FARMLANDS AND AGRICULTURAL USES.....	11
3.2.3 FLOODPLAIN.....	11
3.3 BIOLOGICAL RESOURCES .....	12
3.3.1 WETLANDS .....	12
3.3.2 VEGETATION AND WILDLIFE.....	13
3.4 COASTAL ZONES/COASTAL BARRIER RESOURCES .....	15
3.5 CULTURAL RESOURCES.....	16
3.5.1 HISTORIC PROPERTIES.....	16
3.5.2 ARCHAEOLOGICAL RESOURCES .....	17
3.6 WATER QUALITY .....	18
3.7 AIR QUALITY .....	18
3.8 NOISE.....	19
3.9 TRAFFIC CIRCULATION AND PARKING ACCESS.....	20
3.10 PUBLIC SERVICES AND UTILITIES .....	20
3.10.1 WATER SUPPLY/USE .....	20
3.10.2 SANITATION.....	21
3.10.3 SOLID WASTE DISPOSAL.....	21
3.10.4 STORMWATER DRAINAGE .....	22
3.10.5 ELECTRIC POWER.....	23
3.10.6 LAW ENFORCEMENT .....	23
3.10.7 FIRE PROTECTION .....	23
3.11 AESTHETICS .....	24
3.12 CLIMATE CHANGE.....	24

3.13	SOCIOECONOMIC ISSUES AND ENVIRONMENTAL JUSTICE .....	25
<b>4.</b>	<b>SUMMARY OF MITIGATION.....</b>	<b>27</b>
<b>5.</b>	<b>PUBLIC PARTICIPATION.....</b>	<b>29</b>
5.1	PUBLIC MEETING .....	29
5.2	PUBLIC HEARING .....	29
<b>6.</b>	<b>AGENCY COORDINATION AND REVIEW .....</b>	<b>30</b>

Tables

Table 1	Test Pit Findings .....	9
Table 2	RI Natural Heritage records located within 2,500 feet of the Indian Springs site .....	14

Attachments

- Attachment A – RIDOH Administrative Consent Order
- Attachment B – Design Drawings
- Attachment C – Treatment Design Technical Memorandum
- Attachment D – NRCS Web Soil Surveys
- Attachment E – Zoning Map
- Attachment F – FEMA FIRM Maps
- Attachment G – National Wetlands Inventory Map
- Attachment H – Natural Heritage Areas Map
- Attachment I – Species Profiles
- Attachment J – Agency Correspondence

# 1. Introduction

---

## 1.1 Background and Overview

The Prudence Island Water District (PIWD) is located on the southeastern side of Prudence Island, Rhode Island, and generally serves the residents between Warnerville and Bristol Colony. Prudence Island is a 3,444-acre island located in Narragansett Bay and is located within the political boundaries of the Town of Portsmouth, Rhode Island. The Town of Portsmouth is approximately 2.3 miles from Prudence Island and access to Prudence Island can only be achieved by seacraft. Historically, the water system was operated as a private water company, by an entity known as the Prudence Island Utility Corporation (PIUC). In 2004, the water system and all the assets were transferred to the PIWD, and the PIWD assumed all the responsibilities of the PIUC, including full operational control of the water system.

The PIWD water system was designed to only provide domestic water service to its customers and does not provide water for fire protection. The PIWD water system includes three supply wells, a 100,000-gallon storage tank, and distribution system piping. The piping consists of approximately 9 miles of pipe, varying in size from 1-inch to 6-inch in diameter. Two of the active wells are located at the Indian Springs site and were installed in 1994. The other active well is located at the Army Camp site, which has been in service since the 1940's, on land owned by the Prudence Conservancy. The PIWD Water System serves a year-round population of approximately 150 people and a seasonal population in excess of 1,800 people. There are approximately 350 customer service accounts within the distribution system.

## 1.2 Purpose and Need

The Prudence Island Water District (PIWD) is under an Administrative Consent Order (ACO) with the Rhode Island Department of Health (RIDOH) to install permanent disinfection facilities at their two water supply sites, including pre-treatment for the removal of iron and manganese at the Indian Springs well site (see Attachment A). PIWD retained the services of H2Olson Engineering, Inc. (H2Olson) to complete the design and permitting of these facilities in accordance the RIDOH ACO requirements.

Two treatment systems are being proposed:

1. Disinfection and iron and manganese facilities at the Indian Springs well site.
2. Disinfection facilities at the Army Camp well site.

The design drawings for the proposed facilities are included as Attachment B. The design technical memorandum is included as Attachment C.

### Indian Springs Well Site

The Indian Springs well site consists of two supply wells and two wood-framed sheds. One shed contains the well flow meter and emergency chlorine injection, and the other contains the electrical equipment. A backup generator is located outside for use in the case of electric power failure.

The primary need of the PIWD is to improve the water quality supplied from the Indian Springs wells. This will be accomplished through the installation of a treatment facility for the removal of source water iron and manganese and disinfection to achieve 4-log inactivation of viruses. The Indian Springs wells have demonstrated elevated levels of iron and manganese, beyond the regulatory water quality limits. A viable treatment system would be one in which the iron and manganese is removed to acceptable levels without utilizing a significant amount of potable water to maintain the system or generate a significant amount of treatment residuals that would be costly to dispose of and could potentially have an adverse impact on the environment of the island. The treatment system will have to be purchased, installed, and operated at a cost that would not be an undue burden upon the relatively small number of service customers of the PIWD.

The proposed treatment system includes converting the existing pump station to a chlorine addition facility which will be used for storing and dosing chlorine. The use of commercial strength sodium hypochlorite (12.5% strength) is proposed. This product can be purchased in 5-gallon pails. The proposed chlorination facilities consist of two (2) chlorine pumps, a 1-gallon day tank, and a containment pallet suitable to store up to six (6) 5-gallon pails. The chlorine will be injected downstream of the existing flow meter. Several hundred feet of the existing 4-inch water main will need to be replaced with 8-inch diameter ductile iron water main in order to provide enough contact time (CT) for 4-log inactivation of viruses.

A 2-filter greensand filtration system is proposed for iron and manganese treatment. The system is completely pre-engineered and assembled on a skid. A previously completed hydraulic evaluation indicated that the existing well pumps have sufficient head to pump through the filters with sufficient head to pump into the 100,000-gallon storage tank. The system will operate with 1 filter online, with an anticipated run-time between 24 and 72 hours. When the on-line filter requires cleaning, it will be taken offline, and the 2nd filter that is on stand-by will be placed in service. The offline filter will then be backwashed and placed on stand-by until needed. A dedicated 1,500-gallon wash water supply tank and backwash pump will provide the means for backwashing each filter. Residuals from backwashing the filters will be directed to a 2,000-gallon holding tank and infiltration system. Settled solids from filter

backwashing will be removed via a vacuum pump every 6 to 12 months, or as needed, to remove the accumulated solids in the holding tank.

Army Camp Well Site

The Army Camp well will be equipped with a new chlorination disinfection system to meet the requirements of the ACO with RIDOH. There are no other viable alternatives for this action. The proposed disinfection treatment system includes converting the existing pump station to a chlorine addition facility which will be used for storing and dosing chlorine. The use of commercial strength sodium hypochlorite (12.5% strength) is proposed. The proposed chlorination facilities consist of two chlorine pumps, a carboy scale, and a containment pallet suitable to store up to six 5-gallon pails. The chlorine will be injected downstream of the existing flow meter. Seventy feet of the existing 2-inch water main will be replaced with 16-inch diameter ductile iron water main to provide enough contact time (CT) for 4-log inactivation of viruses. The finished water will then be discharged to the high service zone and Broadway Booster station. A sample line of the treated water will run through a chlorine analyzer and then discharge the sample water into a dry well system for disposal. See Attachment B for further design details and calculations.

## 2. Proposed Actions and Alternatives

---

### **2.1 Alternative 1 - Do Nothing**

Based on the ACO with RIDOH, doing nothing is not a viable option. The two Indian Springs wells have elevated levels of iron and manganese above the Secondary Drinking Water Guidelines (0.3 mg/L for iron and 0.05 mg/L for manganese). Iron levels in these two wells generally range from 0.17 to 1.0 mg/L with spikes as high as 4.0 mg/L and manganese levels ranging from 0.12 to 0.23 mg/L. In addition, disinfection is required at both the Indian Springs and Army Camp well sites for microbiological safety.

### **2.2 Alternative 2 – Connect to another Public Water System**

The closest public water supply is the Portsmouth Water and Fire District. Connection to this system would require over 1.3 miles of transmission water main across (under) Narragansett Bay, which is economically not feasible for a system the size of the PIWD.

### **2.3 Alternative 3 – Installation of Point of Use (POU) Devices at All Customer Services**

RIDOH regulations do not allow for the use of POU devices to achieve compliance with a Maximum Contaminant Limit (MCL).

### **2.4 Alternative 4 – Installation of Individual Private Wells for All District Customers**

This alternative is not technologically viable in that many of these homes are on small lots with on-site septic disposal systems that would preclude the proper separation between wells and individual sewage disposal systems. In addition, most of these service customers are along the eastern shoreline and well installation would be very difficult due to the potential for saltwater intrusion.

### **2.5 Alternative 5 – Provide Treatment for the Wells**

This alternative consists of addressing the problem directly through treatment of the affected raw water supply before it enters the distribution system. Treatment includes disinfection at both well sites (Army Camp and Indian Springs), and removal of source water iron and manganese at the Indian Springs site.

### **2.6 Recommended Alternative**

The only feasible alternative that will address the concerns of the aforementioned ACO (included in Attachment A) is Alternative 5 – providing treatment at the existing well sites. The proposed method of treatment includes greensand filtration for the removal of source water iron and manganese at the Indian

Springs wells, and disinfection by chlorination at both the Indian Springs wells and Army Camp well. This Environmental Assessment (EA) will discuss the potential for environmental impacts resulting from this proposed action.

DRAFT



### 3. Environmental Impacts, Consequences, and Mitigation

---

The sections below provide a discussion of the environmental conditions at the project site, the potential for environmental impacts, and any mitigation measures that are determined to be necessary. Environmental impacts assessed include both short-term and long-term impacts. The direct impacts for this project are primarily short-term construction impacts and can be successfully mitigated during the construction period. No substantive environmental impacts are anticipated as a result of this project. The benefits of these water treatment updates greatly outweigh any negative impact of project implementation, providing necessary improvements in water quality for the residents of Prudence Island.

#### 3.1 Soils

##### a) Affected Environment

##### *Indian Springs Well Site*

The area surrounding the Indian Springs well site consists of three soil units, as determined via the NRCS Web Soil Survey: Quonset gravelly sandy loam, rolling (QoC); Scarboro mucky fine sandy loam (Sb), 0 to 3 percent slopes; and Windsor loamy sand, 0 to 3 percent slopes (WgA). QoC makes up 24.8% of the area of interest (AOI) and has a hydrologic rating of A, Sb makes up 26.5% of the AOI and has a hydrologic rating of A/D, and WgA makes up 48.7% of the area of interest and has a hydrologic rating of A. Hydrologic group A soils have a high infiltration rate and consist mainly of deep, well drained to excessively drained sands or gravelly sands. Soils in a dual hydrologic group match the first letter for drained areas and the second letter for undrained areas. Group D soils have a very slow infiltration rate. The soil survey results can be seen in Attachment D.

Subsurface exploration of the site was performed on November 11, 2021 by means of test pitting, performed west of the proposed building. A summary of soil conditions encountered are as follows:

**TABLE 1 TEST PIT FINDINGS**

<u>Depth</u>	<u>Soil Description</u>
0.0'-1.0'	Moist, black topsoil with root matter from vegetated (grassed) ground surface  During excavation from 1.0' to 9.5' depth soil density was observed to be firm. Estimate range of soil bearing capacity in this zone is between 2.5 to 3.0 ton/sf. Soil density observed below 9.5' is estimated to range between 3.0 & 4.0 tons/sf.
1.0'-7.0'	Dry, tan, fine sand, trace silt
7.0'-9.5'	Dry, gray, fine sand, trace silt
9.5'-10.5'	Dry, gray, fine sand, trace silt, and occasional cobble
10.5'	Bottom of excavation. No groundwater was observed.

***Army Camp Well Site***

The area surrounding the Army Camp well site consists of two soil units, as determined via the NRCS Web Soil Survey: Newport silt loam, 0 to 3 percent slopes (NeA) and Newport silt loam, 3 to 8 percent slopes (NeB). NeA makes up 36.5% of the AOI and NeB makes up 63.5% of the AOI. Both soil units are in hydrologic group C, classified as having a slow infiltration rate when thoroughly wet and consisting chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. The soil survey results can be seen in Attachment D.

b) Environmental Consequences

There are no indications of any conditions that would adversely impact soil conditions permanently. Increased erosion is a possible consequence of soil disturbance during construction, so appropriate controls will be implemented to prevent a negative impact. Any disturbed areas will be restored after construction is complete.

c) Mitigation

The contractor shall loam, seed, and fertilize all disturbed vegetative areas within the limit of work. All new and disturbed vegetative surface areas called out within the limits of work and as shown on the plans shall be comprised of 4-inch loam, seed, and fertilizer.

## **3.2 Land Use and Planning**

### ***Indian Springs Well Site***

The proposed site is identified as Portsmouth Assessor's Plat 76 Lot 5A, which is a 5.14-acre parcel which was transferred from the PIUC to the PIWD as part of the transfer of the capital assets of the water system, with the address 024 Homestead Ave. The latitude and longitude coordinates of the specific site location within the parcel are 41° 37' 13" N and 71° 18' 40" W. The treatment building and related infrastructure will comprise approximately a ½ acre portion of this existing parcel and will be situated so that it is upland and out of the protective well head radius of the existing Indian Springs wells.

### ***Army Camp Well Site***

The Army Camp well site is located on the Town of Portsmouth Assessors Plat 80, Lot 4, which is a 166-acre parcel, with the address 0 Broadway. The latitude and longitude coordinates of the specific site location within the parcel are 41° 36' 30" N and 71° 18' 45" W.

#### **3.2.1 Zoning**

##### **a) Affected Environment**

The project sites and surrounding areas are located within a residential zoning area (R-60). An R-60 district is a residential zone with minimum lot size of sixty thousand square feet (60,000 ft.<sup>2</sup>). The zoning map of Prudence Island is included in Attachment E. The proposed project will be contained entirely within the existing well sites.

##### **b) Environmental Consequences**

The zoning of the site is not a concern since the wells are already located in this area and serve the island's residential water needs. To confirm that there are no zoning conflicts, a request for review comments was made to the Rhode Island Division of Statewide Planning and the Portsmouth Town Planner. The Portsmouth Town Planner, Lea Hitchen, has confirmed that the proposed project is in compliance with the Portsmouth Zoning Ordinance and has found the project to be consistent with the Comprehensive Community Plan. The Division of Statewide Planning has reviewed the proposed project and had no comments. Copies of all correspondence can be found in Attachment J.

##### **c) Mitigation**

There are no mitigation needs related to zoning for this project.

### **3.2.2 *Farmlands and Agricultural Uses***

a) Affected Environment

Based upon observation of the project site, there are no farmlands or agricultural uses in the project site or surrounding area and therefore will not be impacted by the project. To confirm these findings, information requests have been sent to the Rhode Island Division of Statewide Planning describing the project and requesting information on potential land use impacts of the proposed project. The Division of Statewide Planning has reviewed the proposed project and has no comments. Copies of all correspondence are included in Attachment J.

b) Environmental Consequences

Based upon the findings above, there are no perceived environmental consequences associated with the project and farmlands or agricultural uses.

c) Mitigation

Based upon the lack of environmental consequences, no mitigation associated with farmlands and agricultural uses is recommended.

### **3.2.3 *Floodplain***

a) Affected Environment

In review of the National Flood Insurance Program Flood Insurance Rate Maps (FIRM) for the site locations, numbered 44005C0081J, effective September 4, 2013, the project sites are located in Zone X (unshaded), which is the Area of Minimal Flood Hazard and has less than 0.2% annual chance of flood hazard. These maps can be seen in Attachment F.

b) Environmental Consequences

Based upon the findings above, there are no perceived environmental consequences associated with the project and floodplain.

c) Mitigation

Based upon the lack of environmental consequences, no mitigation associated with the floodplain is recommended.

### **3.3 Biological Resources**

#### **3.3.1 Wetlands**

##### a) Affected Environment

The RIDEM Rules and Regulations Governing the Administration and Enforcement of The Freshwater Wetlands Act define a freshwater wetland as:

- A. A bog, flood plain, pond, marsh, riverbank, swamp, river, area of land within fifty feet (50'), area(s) subject to flooding, area(s) subject to storm flowage, floodway, flowing body of water, stream, intermittent stream, perimeter wetland, submergent and emergent plant communities, special aquatic sites, shrub and forested wetland or any combination thereof;
- B. Those areas that are inundated or saturated by surface or groundwater at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions; or
- C. Any or all wetlands created as part of, or the result of, any activity permitted or directed by the Department after July 16, 1971 including, but not limited to: restored wetlands; value replacement wetlands created to compensate for wetland loss such as flood plain excavations; biofiltration areas; and any wetlands created, altered or modified after July 16, 1971.

##### ***Indian Springs Well Site***

Based upon the review of RIGIS mapping of the project area, showing National Wetlands Inventory sites, and a preliminary review of the identified project site, there are no RIDEM regulated wetlands within or surrounding the proposed project area.

##### ***Army Camp Well Site***

Based upon the review of RIGIS mapping of the project area, showing National Wetlands Inventory sites, and a preliminary review of the identified project site, there are no RIDEM regulated wetlands within or surrounding the proposed project area.

There is a wetland area surrounding Schoolhouse Swamp, but this is approximately 1,300 feet away from the project site, therefore no impact is anticipated.

A map of the wetland areas delineated by the National Wetlands Inventory is attached as Attachment G. Communication with RIDOH has confirmed that there are no regulated wetlands within or impacted by the project area.

b) Environmental Consequences

Based upon the findings above, there are no perceived environmental consequences associated with the project and wetlands.

c) Mitigation

Based upon the lack of environmental consequences, no mitigation associated with wetlands is recommended.

### **3.3.2 Vegetation and Wildlife**

a) Affected Environment

Based upon review of the RIGIS database, the Indian Springs site is located within a RI Natural Heritage Area. Natural Heritage Areas are locations where rare species carry out important life-cycle activities. A map of these areas and the site locations is attached in Attachment H. Through contact with Paul Jordan, a data analyst and GIS specialist at RIDEM, RI Natural Heritage records were obtained showing no rare species observations near the Army Camp site and three rare species observations within 2,500 feet of the parcel containing the Indian Springs proposed facility. These records are all state-listed threatened species and include the Pine Barrens Tiger Beetle (*Cicindela formosa generosa*), the Oblique-lined Tiger Beetle (*Cicindela tranquebarica*), and Arrow-feather Three-awn Grass (*Aristida purpurascens var. purpurascens*) as listed in Table 2. The two beetle species observations were located about 1,200 feet west of the parcel boundary that contains the Indian Springs proposed facility. The parcel covers a land area of 5.14 acres, of which the Indian Springs project site occupies an approximately ½ acre portion on the eastern side of the parcel. The habitat is similar across the surrounding area, so the presence of these threatened species at the site is possible. *Cicindela formosa generosa* occurs exclusively in inland sand flats and barrens. The proposed project will not disturb or modify any existing sand patches.

**TABLE 2**  
**RI NATURAL HERITAGE RECORDS LOCATED WITHIN 2,500 FEET OF THE INDIAN SPRINGS SITE**

<u>#</u>	<u>Family</u>	<u>Genus</u>	<u>Species</u>	<u>Common Name</u>	<u>Survey Year</u>	<u>Last Seen</u>	<u>Status</u>	<u>Count</u>
1	Insect	<i>Cicindela</i>	<i>formosa generosa</i>	Pine Barrens Tiger Beetle	1996	1996	State Threatened	1
2	Insect	<i>Cicindela</i>	<i>tranquebarica</i>	Oblique-lined Tiger Beetle	1995	1995	State Threatened	1
3	Poaceae	<i>Aristida</i>	<i>purpurascens</i> var. <i>purpurascens</i>	Arrow-feather Three-awn Grass	2021	2021	State Threatened	1

Project review comments from the RIDEM Office of Customer & Technical Assistance have drawn attention to the likely presence of wildlife in roads and within the Limit of Work – particularly eastern box turtles and spotted turtles. These turtles are active and can be found crossing roads from approximately April 1 through November 1. Additionally, the island is sensitive to the introduction of wildlife pathogens and invasive species.

The proposed project will be located downhill and adjacent from the existing well house, on land that is already cleared, regularly mowed, and used for vehicle parking and storage. The project is not anticipated to significantly alter the suitability of this small, already disturbed area as habitat for these threatened species or remove any additional habitat area. Species profiles for the identified threatened animal species are included in Attachment I. Requests for review of the proposed project and identification of any potential issues related to vegetation and wildlife have been sent to the RIDEM Division of Fish and Wildlife and the NOAA Fisheries Greater Atlantic Regional Fisheries Office. The RIDEM Division of Fish and Wildlife directed our request to the Office of Customer & Technical Assistance for review. Copies of these letters are included in Attachment J.

b) Environmental Consequences

Any impact of this project to the surrounding habitat is anticipated to be minimal. With proper precautions, it is not expected that the project will have significant consequences to vegetation and wildlife in the area. Review comments from the NOAA Fisheries Office indicate that construction related to the project has the possibility to impact Essential Fish Habitat, but the minimization procedures outlined in the project, such as sedimentation controls, are adequate to minimize adverse effects. This response is included in Attachment J.

c) Mitigation

To prevent harm to animals that may be present on island roads, project vehicles will exercise caution and follow local speed limits at all times. In the event that a turtle is found in the road, the vehicle will be stopped, and the turtle carefully moved to safety. Before beginning construction each day, a visual sweep of the Limit of Work will be performed to identify the presence of box turtles. If a turtle is found in the Limit of Work, it will be moved to a forested, upland area at least 200 feet away before construction begins. Further information on Best Management Practices to limit impacts to box turtles can be found with RIDEM correspondence in Attachment J.

To prevent the introduction of wildlife pathogens to the island, all equipment will be cleaned and decontaminated before loading onto the ferry to Prudence Island. Complete disinfection protocols can be found with RIDEM correspondence in Attachment J. To prevent the introduction of invasive species, loaming and seeding within construction areas will not involve imported soil from off-island and will only use native species seed mixes.

If any of the listed species are observed in the project area during construction, appropriate measures will be taken to protect the species and its habitat. Any vegetation disturbed during construction will be restored to the greatest extent possible.

### **3.4 Coastal Zones/Coastal Barrier Resources**

a) Affected Environment

The Coastal Zone Management Act (CZMA) of 1972, as amended, applies to all lands on the boundary of any ocean or arm thereof, and the Great Lakes. The Coastal Barrier Resources Act (CBRA) and the Coastal Barrier Improvement Act only apply to selected geographic areas designated as "Coastal Barrier Resources System (CBRS) Units." These units have been established along the coasts of the Atlantic Ocean, Gulf of Mexico, and the Great Lakes. Based upon its upland location, this project does not impact any of the areas defined by CZMA or CBRA. The project site is not located in areas under the jurisdiction of the Rhode Island Coastal Resources Management Council – tidal and coastal pond waters, shoreline features, and areas of historic and archaeological significance in the coastal zone – and the project does not present a reasonable potential to damage the coastal environment.

b) Environmental Consequences



Based upon the findings above, there are no perceived environmental consequences associated with the project and coastal resource issues.

c) Mitigation

Based upon the lack of environmental consequences, no mitigation associated with coastal resource issues is recommended.

## **3.5 Cultural Resources**

### ***3.5.1 Historic Properties***

a) Affected Environment

The National Historic Preservation Act (NHPA) of 1966, as amended (16 U.S.C. § 470 et seq.), and the Advisory Council on Historic Preservation's (ACHP) implementing regulations, 36 CFR Part 800 (Section 106 regulations), requires the identification of historic properties that are within the proposed project area to determine potential effects. Historic property means any prehistoric or historic district, site, building, structure, or object included in or eligible for inclusion in the National Register of Historic Places. This term includes, for the purposes of the Section 106 regulations, artifacts, records, and remains that are related to and located within such properties. The term "eligible for inclusion in the National Register" includes both properties formally determined as such by the Secretary of the Interior and all other properties that meet National Register of Historic Properties listing criteria. Under the Rhode Island Historic Preservation Act (R.I. Gen. Laws § 42-45-5), the Rhode Island Historic Preservation and Heritage Commission (RIHPHC) shall advise on any activity that will encroach upon, damage, or destroy any site, building, place, landmark, or area included in the state register. Based upon the review of the project site and the national and state registers, there appears to be no historic properties within the project area or affected by the project activities. However, the project may still require review by RIHPHC since it will be seeking other state permits. The NHPA also requires consultation with federally recognized tribes when a project might affect a historic site. Upon review of the project area, it does not appear to impact any tribal sites or cultural resources. To confirm these findings, a request for review comments has been sent to the RIHPHC and the Narragansett Tribal Historic Preservation Office. Upon review of the project information, RIHPHC has confirmed that no historic properties will be affected by the project. No response has yet been received from the Narragansett Tribal Historic Preservation Office. Copies of all correspondence can be found in Attachment J.

b) Environmental Consequences

Based upon the findings above, there are no perceived environmental consequences associated with the project and historical properties.

c) Mitigation

Based upon the lack of environmental consequences, no mitigation associated with historical properties is recommended. In the event that any historical artifacts are unearthed during project construction, RIHPHC will be notified, and construction will be delayed or modified to ensure that these resources are properly managed.

### ***3.5.2 Archaeological Resources***

a) Affected Environment

The Archaeological Resources Protection Act of 1979 (ARPA) focuses on regulation of legitimate archaeological investigation on public lands and the enforcement of penalties against those who loot or vandalize archaeological resources, as well as providing authority to Federal officials to better manage archaeological sites on public land. Section 9 of ARPA requires that information about the location and nature of these archaeological resources is held confidential unless providing the information would further the purpose of ARPA and not create harm for the resources. There are no known archaeological resources on or affected by the project sites. To confirm the absence of archaeological resources in the project site area, a request for further review has been sent to the RIHPHC. Upon review of the project information, the RIHPHC has concluded that no historic properties will be affected by the project. A copy of this correspondence can be found in Attachment J.

b) Environmental Consequences

There are no expected environmental consequences related to archaeological resources based on the above information.

c) Mitigation

Based on the above information, no mitigation is recommended.

### 3.6 Water Quality

a) Affected Environment

The proposed greensand filtration system will generate filter backwash waste from the periodic backwash to flush accumulated solids from the media bed. The filter will be backwashed from a 1,500-gallon wash water supply tank every 1 to 3 days. The backwash water supernatant will be discharged through a settling tank and infiltration galley system to filter out the insoluble ferric and manganic oxides and return the spent backwash water to the watershed. There will also be a minor discharge at the Army Camp site from an analyzer discharge line that will pull treated water for sampling, with a flow of approximately 0.5-1 gpm, and direct it to a dry well system. An application for approval of the groundwater discharge systems - including settling tank, infiltration galley, and dry well – has been submitted to RIDEM. This course of approval, and other potential design options, has been discussed with Neal Personeus, Senior Environmental Scientist/Project Manager for the Office of Water Resources at RIDEM. This correspondence is included in Attachment J.

b) Environmental Consequences

The groundwater discharge systems related to this project are not anticipated to have any negative impact on water quality but will be monitored to detect any changes that could possibly occur. Based upon the findings above, there are no perceived environmental consequences associated with water quality issues and the project.

c) Mitigation

Based upon the lack of environmental consequences, no mitigation associated with water quality issues is recommended. If any issues are detected during the use of the proposed groundwater discharge system, the system operators will follow the protocol laid out in the groundwater discharge approval application.

### 3.7 Air Quality

a) Affected Environment

One possible air quality impact associated with the project is exhaust from the propane-driven portable emergency generator that will be used during electric power failure. The generator will be relatively small and only run for short periods of time when needed.

Construction activities may involve short-term air quality impacts such as dust generation and emissions from vehicles. With proper controls and the small scale of this project, these impacts are anticipated to be negligible.

b) Environmental Consequences

There are negligible environmental consequences associated with the project and air quality.

c) Mitigation

Precautions shall be taken in accordance with good industrial practice to limit airborne particulate matter from construction activities and material transport. Construction vehicles will be in compliance with the most recent Rhode Island Department of Transportation (RIDOT) emissions standards.

### 3.8 Noise

a) Affected Environment

The facilities proposed for this project are not expected to generate adverse noise impacts. There will inevitably be some noise associated with construction, but this will be confined to normal weekday work hours. During normal operation, all mechanical equipment will be housed in an enclosed structure and their sound of operation will not be heard outside the confines of the treatment building. The only potential noise resulting from the operation of these facilities will be the use of a propane-driven portable emergency generator in the case of electric power failure.

b) Environmental Consequences

The environmental consequences related to noise will be minimal. Those temporary impacts associated with construction will be of a short duration. Any noise associated with long-term operation of the facility would be well below residential threshold levels and is not expected to have any environmental consequences.

c) Mitigation

Short-term noise impacts will be mitigated by provisions in the construction contract documents to control noise to the extent possible during construction. This will also require that activities that have the potential to generate noise issues be carried out on weekdays, during daytime hours, when noise will be less disruptive.

No long-term noise mitigation is necessary for this project.

### **3.9 Traffic Circulation and Parking Access**

#### a) Affected Environment

Short-term transportation issues may arise during project construction due to limited access to the island by ferry. The transportation of construction materials to the island may take up vehicle space on the ferry that is generally used by residents and visitors to the island. Operation will only generate, at most, a few additional trips per day over island roads leading to the facility. There will be some minor disruptions of local traffic during the construction of utilities within existing roadways, but this will be limited and minimized with good traffic control practices. Traffic on Prudence Island is extremely minimal, and the project is of a small scale, so no significant disruptions are expected. The project will not impact any public parking access.

#### b) Environmental Consequences

Based upon the findings above, there are minor consequences associated with the project and transportation issues related to the use of limited ferry space and disrupting roadways during construction.

#### c) Mitigation

To mitigate the minor consequences associated with the project and transportation issues related to the use of limited ferry space, transportation of equipment and building materials will be avoided during peak ferry usage times. Construction personnel will be instructed to carpool to the jobsite to limit the number of vehicles on the ferry and on island roads. Good traffic control practices will be used to minimize the impact of disrupted roadways during construction.

### **3.10 Public Services and Utilities**

#### ***3.10.1 Water Supply/Use***

#### a) Affected Environment

This project will improve the quality of the water supply by removing iron and manganese to within regulatory standards and provide disinfection. The greensand filtration system at the Indian Springs site will be backwashed from a 1,500-gallon wash water supply tank every 1 to 3 days. This system is not anticipated to have any adverse effect on water supply.

Water required during construction is expected to be minimal to none and is not a concern to the water supply.

b) Environmental Consequences

Based on the information above, there are no perceived environmental consequences associated with water supply from this project.

c) Mitigation

Based upon the lack of perceived environmental consequences, no mitigation efforts related to water supply are recommended.

### ***3.10.2 Sanitation***

a) Affected Environment

There are no sanitation changes or additions associated with the implementation of this project.

b) Environmental Consequences

Since there are no sanitation aspects of this project, no environmental consequences related to sanitation are anticipated.

c) Mitigation

Based on the above information, there is no mitigation recommended for sanitation.

### ***3.10.3 Solid Waste Disposal***

a) Affected Environment

Some solid waste generation is to be expected during the construction of this project, mainly consisting of construction debris. All construction debris and other solid waste generated will be properly contained and disposed of in compliance with Federal, State, and local regulations.

The Indian Springs site includes a backwash settling tank that will generate sludge resulting from backwash of the greensand filter. The sludge in the settling tank will be monitored and measured monthly by operating staff. When the sludge depth reaches 18 inches, the sludge

will be vacuumed out of the settling tank. Once removed, the sludge will be disposed of through a sludge hauler.

b) Environmental Consequences

There are no expected environmental consequences related to solid waste disposal for this project.

c) Mitigation

To ensure there are no consequences related to solid waste disposal, any waste generated will be properly contained and disposed of.

### ***3.10.4 Stormwater Drainage***

a) Affected Environment

This project will not create significant long-term changes to stormwater drainage in the surrounding environment. There are no storm drains in the project vicinity.

b) Environmental Consequences

During the construction phase of the project, soil erosion has the potential to enter stormwater flows and impact local water bodies if proper control methods are not put in place.

No long-term environmental consequences related to stormwater drainage are anticipated for this project.

c) Mitigation

To mitigate the effects of land disturbance during construction on stormwater quality, standard soil erosion and sedimentation control measures will be implemented. As small sites of less than 1 acre, the project construction will comply with Minimum Standard 10 of the *RI Stormwater Design and Installation Standards Manual (RISDISM)*. The construction operator will develop a Soil Erosion and Sediment Control Plan, in accordance with the measures laid out in Section 3.3.7 of the RISDISM, prior to beginning construction.

Communication with RIDEM confirmed that the project does not fall under any stormwater regulations. No long-term mitigation for stormwater drainage is recommended.

### ***3.10.5 Electric Power***

a) Affected Environment

The project is expected to require only minimal amounts of electric power that will not be a burden on the power provided to Prudence Island. The site will have a propane-driven portable emergency generator that will be used during electric power failure.

b) Environmental Consequences

There are no anticipated environmental consequences associated with electric power for this project.

c) Mitigation

Based on the above information, no mitigation related to electric power is recommended.

### ***3.10.6 Law Enforcement***

a) Affected Environment

Prudence Island is part of the municipality of Portsmouth, RI and all law enforcement service calls are taken by the Portsmouth Police Dispatch Center. Any law enforcement emergencies during project implementation will be directed there.

b) Environmental Consequences

There is no anticipated interference with law enforcement associated with this project.

c) Mitigation

Based on the above information, no mitigation is recommended regarding law enforcement.

### ***3.10.7 Fire Protection***

a) Affected Environment

The PIWD water system is designed only to provide domestic water service and does not provide fire protection. The wells and hydrants impacted by this project are not involved in fire protection. Fire emergencies are responded to by the Prudence Island Volunteer Fire Department. Prudence Island has a separate water storage tank, known as Greer tank, and a number of underground cisterns, which are used to supply water for fire trucks in



emergencies. These supplemental fire water storage tanks are filled manually as water supply resources permit, and will not be affected by this project.

b) Environmental Consequences

Based upon the above findings, there are no perceived environmental consequences associated with fire protection on Prudence Island.

c) Mitigation

Based upon the lack of consequences associated with fire protection, no mitigation is recommended.

### 3.11 Aesthetics

a) Affected Environment

Aesthetics are not anticipated to be a concern for this project. The proposed treatment building will be a single low-profile structure and the building and related infrastructure will be occupying only a small area of the parcel. The design will complement and blend into the surrounding area. Observation of the sites show that they are positioned away from other developments and hidden by the tree cover in the area.

b) Environmental Consequences

Based upon the findings above, there are no perceived environmental consequences associated with the project and local aesthetics.

c) Mitigation

Based upon the lack of consequences associated with aesthetics, no mitigation is recommended.

### 3.12 Climate Change

a) Affected Environment

Climate change has serious potential impacts, especially for coastal areas like Rhode Island. This project will not contribute significantly to greenhouse gas emissions that advance climate change. The project site is in an upland location that is not imminently threatened by potential sea level rise.

b) Environmental Consequences

There are no significant anticipated environmental consequences associated with the advancement of climate change due to the implementation of this project.

c) Mitigation

Based on the above information, no mitigation due to climate change impacts is recommended.

### **3.13 Socioeconomic Issues and Environmental Justice**

a) Affected Environment

RIDEM defines Environmental Justice (EJ) as “the fair treatment and meaningful involvement of all people regardless of race, color, national origin, English language proficiency, or income with respect to access to the state’s natural resources and the development, implementation, and enforcement of environmental laws, regulations, and policies.” EJ efforts seek to prevent disproportionate impacts of environmental and public health risks on any particular communities.

A substantial portion of the PIWD service area is comprised of low-income residents. According to EPA’s EJScreen tool, there is a high elderly population on Prudence Island as well. Overall, Prudence Island is sparsely populated, and the project sites are fairly isolated. Prudence Island is not located within any of RIDEM’s identified EJ Focus Areas.

There will be some noise associated with construction of the project for a temporary period during working hours. This will most affect those living closest to the project sites, but the impact is expected to be minimal and short-term. Traffic impacts will be extremely minimal. There will be no displacement due to this project. There are no expected economic losses to the residents of Prudence Island due to implementation of this project.

The water treatment updates in this project are necessary for the residents of Prudence Island and no significant adverse human health or environmental effects are anticipated for any group or community. This project would be benefiting the residents of Prudence Island through much-needed water quality improvements at a reasonable cost.

b) Environmental Consequences

Based upon the findings above, there are no perceived environmental consequences associated with the project and socioeconomic issues or EJ.

c) Mitigation

Based upon the lack of environmental consequences, no mitigation associated with socioeconomic issues or EJ is recommended.

DRAFT

## 4. Summary of Mitigation

---

The mitigation measures proposed for this project are as follows:

- **Soils:** All new and disturbed vegetative surface areas called out within the limits of work and on the plans shall be comprised of 4-inch loam, seed, fertilizer.

**Vegetation and Wildlife:** To prevent harm to animals that may be present on island roads, project vehicles will exercise caution and follow local speed limits at all times. In the event that a turtle is found in the road, the vehicle will be stopped, and the turtle carefully moved to safety. Before beginning construction each day, a visual sweep of the Limit of Work will be performed to identify the presence of box turtles. If a turtle is found in the Limit of Work, it will be moved to a forested, upland area at least 200 feet away before construction begins. Further information on Best Management Practices to limit impacts to box turtles can be found with RIDEM correspondence in Attachment J.

To prevent the introduction of wildlife pathogens to the island, all equipment will be cleaned and decontaminated before loading onto the ferry to Prudence Island. Complete disinfection protocols can be found with RIDEM correspondence in Attachment J. To prevent the introduction of invasive species, loaming and seeding within construction areas will not involve imported soil from off-island and will only use native species seed mixes.

If any of the listed species are observed in the project area during construction, appropriate measures will be taken to protect the species and its habitat. Any vegetation disturbed during construction will be restored to the greatest extent possible.

- **Historic Properties:** The project is not anticipated to have any adverse impact on historic properties or items. In the event that any historical artifacts are unearthed during project construction, RIHPHC will be notified and construction will be delayed or modified to ensure that these resources are properly managed.
- **Water Quality:** No adverse impact on water quality is expected as a result of this project. If any issues are detected during the use of the proposed groundwater discharge system, the system operators will follow the protocol laid out in the groundwater discharge approval application.

- **Air Quality:** Precautions shall be taken in accordance with good industrial practice to limit airborne particulate matter from construction activities and material transport. Construction vehicles will be in compliance with the most recent RIDOT emissions standards.
- **Noise:** Short-term noise impacts will be mitigated by provisions in the construction contract documents to control noise to the extent possible during construction. This will also require that activities that have the potential to generate noise issues be carried out on weekdays, during daytime hours, when noise will be less disruptive.
- **Traffic Circulation:** To mitigate the minor consequences associated with the project and transportation issues related to the use of limited ferry space, transportation of equipment and building materials will be avoided during peak ferry usage times. Construction personnel will be instructed to carpool to the jobsite to limit the number of vehicles on the ferry and on island roads. Good traffic control practices will be used to minimize the impact of disrupted roadways during construction.
- **Solid Waste Disposal:** To ensure there are no consequences related to solid waste disposal, any waste generated will be properly contained and disposed of.
- **Stormwater Drainage:** To mitigate the effects of land disturbance during construction on stormwater quality, standard soil erosion and sedimentation control measures will be implemented. As small sites of less than 1 acre, the project construction will comply with Minimum Standard 10 of the *RI Stormwater Design and Installation Standards Manual* (RISDISM). The construction operator will develop a Soil Erosion and Sediment Control Plan, in accordance with the measures laid out in Section 3.3.7 of the RISDISM, prior to beginning construction.

## 5. Public Participation

---

### 5.1 Public Meeting

A public meeting or workshop to discuss the project and the environmental impacts of the project shall be coordinated by the Prudence Island Water District in accordance with 216-RICR-50-05-6.11. The meeting is required to discuss with the public the project scope, alternatives, and the preferred additions of disinfection and iron and manganese treatment, and to solicit public opinions and concerns. This meeting is required to be documented including the preparation of meeting notes, sign-in sheet, presentation materials, and methods of advertisement (including media). The meeting documentation will be included as an Attachment of the final EA.

### 5.2 Regulatory Review and Public Hearing

RIDOH and RIDEM will review the final EA and make a determination. Following the decision, RIDOH will invite public comments for thirty (30) days, or as required by R.I. Gen. Laws Chapter 42-35, by publishing a notice of the determination made in a paper of statewide circulation, on RIDOH's website and/or any other acceptable means in accordance with R.I. Gen. Laws Chapter 42-35. In addition, notification of such determination will be sent to all persons and associations who have advised RIDOH that they wish to be notified. During the public comment period, any interested party may submit written comments. Requests for a public hearing shall be made in accordance with R.I. Gen. Laws § 42-35-2.8. Following the public notice or public hearing, the final determination will be made by the Director of RIDOH.

## 6. Agency Coordination and Review

---

Several agencies were contacted in the development of this EA. Each agency was provided a proposed scope of work generally describing the project components, a copy of the project overview plan showing the project limits, and the proposed site location. The following agencies were contacted:

- RIDEM Office of Technical and Customer Assistance
- RIDEM Division of Fish and Wildlife
- RIDEM Office of Water Resources
- RIDEM Supervising GIS Specialist
- Rhode Island Division of Statewide Planning
- Portsmouth Town Planner
- Rhode Island Historic Preservation and Heritage Commission (RIHPHC)
- Narragansett Tribal Historic Preservation Office (NTHPO)
- NOAA Fisheries Greater Atlantic Regional Fisheries Office

Letters requesting project review were sent out on July 20, 2022 by mail and email. The NTHPO was only contacted by mail. The RIDEM Supervising GIS Specialist was contacted by email on July 21, 2022 after direction from the RI Natural History Survey. Discussion with the RIDEM Office of Water Resources regarding the groundwater discharge approval application began on June 27, 2022. Any review comments that were received have been incorporated into the EA. No response has yet been received from the NTHPO. Copies of all correspondence are included in Attachment J.

## **Attachment A**

### **RIDOH Administrative Consent Order**

DRAFT







Department of Health  
Room 209  
Three Capitol Hill  
Providence, RI 02908-5097

TTY: 711  
[www.health.ri.gov](http://www.health.ri.gov)

September 2, 2021

**CERTIFIED MAIL**

7020 2450 0001 5704 5167

PWS #RI1592023  
Robin Weber, Moderator, Administrative Contact  
Prudence Island Water District  
PO Box 100  
Prudence Island, RI 02872

Dear Ms. Weber:

Enclosed is the Second Amended Consent Order signed by both Rhode Island Department of Health and Prudence Island Water District.

Sincerely,

A handwritten signature in black ink, appearing to read "Seema Dixit".


Seema Dixit  
Director  
Environmental Health Division

Enclosures

Cc: William Capron, Designated Operator (by email)  
Prudence Island Water District, Owner (0412 Narragansett Ave, Prudence Island, RI 02872)  
Ralph Kinder, Prudence Island Water District Legal Counsel (Gilstein, Kinder & Levin, LLP, 300 Metro Center Blvd., Suite 150A, Warwick, RI 02886)  
Anita Flax, RIDOH  
Carlene Newman, RIDOH  
Colin Millar, RIDOH  
Hui Chen, RIDOH  
Garth Hoxsie-Quinn, RIDOH  
Christina Millar, RIDOH  
Zhengkai Li, RIDOH



State of Rhode Island



**IN THE MATTER OF:  
PRUDENCE ISLAND WATER DISTRICT PUBLIC  
WATER SYSTEM # RI 1592023**

**SECOND AMENDED CONSENT ORDER**

The Prudence Island Water District (PIWD) is licensed as a Public Water System pursuant to R.I. Gen. Laws § 46-13-1 *et seq.* (Public Drinking Water Supply) and 216-RICR-50-05-1 (Public Drinking Water). The Rhode Island Department of Health, Division of Environmental Health, Center for Drinking Water Quality, in connection with the matter described below, herein makes the following:

**FINDINGS OF FACT AND CONCLUSIONS OF LAW**

1. PIWD is licensed by RIDOH as Public Water System #RI 1592023.
2. During the period July 1, 2018 to July 31, 2018, PIWD violated Section 17.1 of R4613-DWQ<sup>1</sup> in that it exceeded the microbiological Maximum Contaminant Level for the Total Coliform Rule.
3. During the period September 1, 2018 to September 30, 2018, PIWD violated Section 16.4(c)(6)(B) of R46-13-DWQ in that it exceeded the microbiological Maximum Contaminant Level for the Total Coliform Rule.
4. During the period September 1, 2018 to September 30, 2018, PIWD violated Section 16.4(c) of R46-13-DWQ and 40 CFR § 141.860(a) of the National Primary Drinking Water Regulations in that it exceeded the microbiological Maximum Contaminant Level for the Total Coliform Rule and the Revised Total Coliform Rule.
5. By email dated October 4, 2018 RIDOH notified PIWD that PIWD was required to provide public notice of a boil water advisory because *E. coli* bacteria was found in the water supply.
6. From June, 2017 to June, 2021, PIWD had 49 sample results out of 210 samples that were present for total coliform, triggering ten Level 1 or Level 2 Assessments.

---

<sup>1</sup> R46-13-DWQ was superseded by 216-RICR-50-05-1 on 10/31/2018.

7. By letter dated October 19, 2018, RIDOH notified PIWD that RIDOH had concluded that despite the implementation of several corrective actions to attempt to remedy recurring coliform presence in the distribution system, the coliform issue still remained, had been assessed as a sanitary defect and significant deficiency that was expected to continue, and required PIWD to install permanent chlorination at all wells in order to maintain a disinfect residual of at least 0.2 mg/L throughout the distribution system pursuant to Sections 13.4, 16.4 (c) and 10.1 of R46-13-DWQ. RIDOH stated that this permanent chlorination system must reliably achieve 4-log (99.99%) inactivation of viruses before the first customer for each groundwater source in accordance with Section 13.4. RIDOH stated that the permanent chlorination system must be installed and approved by May 17, 2019.
8. By letter dated October 29, 2018, PIWD filed a timely request for a hearing on the issue of whether RIDOH was justified in ordering plans for permanent chlorination at all PIWD wells.
9. During the period October 1, 2018 to October 31, 2018, the PIWD violated Section 16.4(c) of R46-13-DWQ in that it exceeded the microbiological Maximum Contaminant Level for the Total Coliform Rule.
10. On or about February 28, 2019, RIDOH and PIWD entered into a Consent Order under which PIWD agreed to attain compliance through the implementation of a cross-connection plan by August 1, 2020. PIWD also agreed to apply for approval of a permanent chlorination system by September 13, 2020 and to install a permanent chlorination system by July 1, 2021 if compliance through the implementation of a cross-connection plan was not attained by August 1, 2020.
11. On or about June 15, 2020, RIDOH and PIWD entered into a First Amendment and Restatement of the Consent Order under which PIWD agreed to attain compliance through the implementation of a cross-connection plan by December 1, 2020. PIWD also agreed to apply for approval of a permanent chlorination system by January 13, 2021 and install the permanent chlorination system by November 1, 2021 if compliance through the implementation of a cross-connection plan was not attained by December 1, 2020.
12. PIWD did not attain compliance through the implementation of a cross-connection plan by December 1, 2020.
13. PIWD did not apply for approval of a permanent chlorination system by January 13, 2021. PIWD requested an extension by email on January 13, 2021 and RIDOH approved the extension by email on January 14, 2021.
14. Upon information and belief, the permanent chlorination system will not be installed by November 1, 2021.

15. PIWD admits to the jurisdiction of RIDOH.

16. PIWD hereby acknowledges and waives:

- a. The right to an administrative hearing on whether RIDOH was justified in ordering plans for permanent chlorination at all PIWD wells;
- b. The right to legal representation at said hearing;
- c. The right to produce testimony, witnesses, and evidence on its behalf at said hearing; and
- d. Any and all rights of appeal.

**ACCORDINGLY, AND BASED ON THE FOREGOING,**

RIDOH and PIWD hereby agree:

1. PIWD must have all cross-connection control surveys performed by an individual holding a current certification from a cross-connection control program recognized by RIDOH (216-RICR-50-05-1.9.4(E)(1)).
2. PIWD has until May 31, 2025 to attain compliance through implementation of a cross connection control plan, including the inspection of existing backflow preventers and installation and inspection of backflow preventers at locations where a proper backflow preventer is not present, at each service connection.
3. On or before October 31, 2021, PIWD shall submit an application to the Rhode Island Infrastructure Bank for a loan from the State Revolving Fund for the purpose of obtaining funding, or otherwise apply for funding by October 31, 2021 from a different financial institution, for a permanent chlorination system at all wells (and an iron-manganese pre-treatment system at the Indian Spring wells) in order to maintain a disinfect residual of at least 0.2 mg/L throughout the distribution system pursuant to 216-RICR-50-05-1.13.4, 216-RICR-50-05-1.16.4(A)(6)(j) and 216RICR-50-05-1.10(A) of R46-13-DWQ. This permanent chlorination system must reliably achieve 4-log (99.99%) inactivation of viruses before the first customer for each groundwater source in accordance with 216-RICR-50-05-1.13.4. PIWD shall comply with all state and federal statutes and regulations in submitting this application (see <https://www.riib.org/sites/default/files/Drinking-Water.pdf>). PIWD shall provide to RIIB or another financial institution all information necessary to ensure financing is secured in order to meet the requirements of Items 4 through 7 below.
4. PIWD shall submit an application to RIDOH for approval of a permanent chlorination system as described in the RIDOH letters dated October 19, 2018 and June 10, 2021, attached hereto as Exhibit A, by December 31, 2021. The application must include:

- a. Plans, specifications, and calculations for iron and manganese pre-treatment of the Indian Spring wells. These plans, specifications, and calculations shall be signed and stamped by a Rhode Island-registered Professional Engineer and include manufacturer cut sheets and NSF 60 and 61 certifications for all components that come into contact with the water. PIWD shall comply with all state and federal statutes and regulations in submitting this application (see <https://health.ri.gov/publications/specifications/Relevant-Federal-and-StateLaws.pdf>).
  - b. A corrosion control study performed, stamped, and signed by a Rhode Island registered Professional Engineer to ensure any alteration of water chemistry due to the addition of chlorine will not cause a destabilization to the existing pipe scale. This study is required under 216-RICR-50-05-1.7.2(B)(3)(c) and shall include results of:
    - i. A materials survey or re-evaluate the most recent survey completed for the Lead and Copper Rule. The objective is to determine the existing structure of the water distribution system and the potential sources/tiers of lead and copper (216-RICR-50-05-1.7.7(A)).
    - ii. A water characteristics evaluation or re-evaluate the most recent studies that measures for lead, copper, pH, alkalinity, calcium hardness, conductivity, water temperature, dissolved oxygen, chlorides, sulfates, the oxidation-reduction potential and corrosion inhibitor, if used. Depending on the model of evaluation that is utilized, there are other analytes that should be considered. These include but are not limited to natural organic matter, total dissolved solids, ammonia, and buffer intensity.
    - iii. A desktop study, which includes evaluations of literature, pre-engineering work, prior PIWD system investigations, water quality data and information, theory, and similar system information in order to demonstrate if an alteration in the water chemistry can cause a destabilization of existing scale. All references must be cited.
  - c. A plan created, stamped, and signed by a Rhode Island-registered Professional Engineer for reducing the potential for Disinfection Byproducts formation. This plan must include test results of the wells for total organic carbon and other water quality parameters the Professional Engineer deems necessary to make this determination.
5. Within 90 days of preliminary approval by RIDOH of the permanent chlorination system engineering design, PIWD shall submit to RIDOH its final Environmental Assessment as required by Section 6.11 of the *Rhode Island Drinking Water State Revolving Fund* regulations, 216-RICR-50-05-6.

6. PIWD shall respond to comments and questions in RIDOH's engineering plan review letter(s) related to the treatment system within 31 days or by the date included in the letter(s), whichever is later.
7. Within 120 days of receiving financing or the final RIDOH engineering approval letter, whichever is later, PIWD shall install the permanent chlorination system treatment system and notify the RIDOH project engineer of the completion of the installation so that a conformance inspection can be performed by RIDOH.
8. PIWD will submit progress reports to RIDOH, which will be due January 15, 2022, January 15, 2023, January 15, 2024 and October 31, 2024 in accordance with 216-RICR50-05-1.9.4. These reports shall include progress on Items 4(a) through 4(c) above.
9. PIWD customers will remain on a boil water advisory until the treatment system is installed and approved by RIDOH, 4-log chlorination is shown to be maintained in two consecutive months of Groundwater Rule Compliance Monitoring monthly operating reports, and a minimum concentration of 0.2 mg/L chlorine residual is maintained throughout the distribution system as shown in two consecutive months of chlorine monitoring with Revised Total Coliform Rule coliform samples. PIWD will provide boil water advisory Public Notice Distribution and Posting to consumers, a copy to RIDOH, and Public Notice Certification to RIDOH on or before September 3, 2021 and every three months thereafter until the boil water advisory is lifted by RIDOH.
10. All previous Notices of Violation issued to date, including without limitation those dated October 19 and October 31, 2018, and any and all appeals thereof, are hereby dismissed/null and void with no assessments.
11. Should PIWD remain out of compliance with 216-RICR-50-05-1 following the expiration of all deadlines stated herein, PIWD will be subject to all fines and administrative penalties allowable by law, including, but not limited to, R.I. Gen. Laws § 46-13-16 and 216-RICR50-05-1.20.
12. This Second Amended Consent Order supersedes the First Amendment and Restatement of the Consent Order dated June 15, 2020 and is binding on the PIWD, its successors, and assigns, and cannot be terminated or modified unless a written agreement is executed between the parties.

Signed this 23 day of August, 2021.

  
\_\_\_\_\_

ROBIN WEBER  
PWS # RI1592023

PRUDENCE ISLAND WATER DISTRICT

Ratified by the RI Department of Health on the 1st day of September 2021.

*Seema Dixit*

\_\_\_\_\_  
AMY B. PARMENTER, CHIEF  
CENTER FOR DRINKING WATER QUALITY  
RHODE ISLAND DEPARTMENT OF HEALTH





## **Attachment B**

### **Design Drawings**

DRAFT

# WATER SYSTEM CHLORINATION & PRETREATMENT


Prepared For:

PRUDENCE ISLAND WATER DISTRICT  
024 HOMESTEAD AVE  
PRUDENCE ISLAND, RHODE ISLAND



## Index of Drawings

Sheet No.	Dwg. No.	Description
1	G-1	COVER SHEET PROCESS FLOW DIAGRAM CIVIL SHEETS
2	C-1	LEGEND AND GENERAL NOTES
3	G-2	INDIAN SPRINGS EXISTING CONDITIONS PLAN
4	C-3	ARMY CAMP EXISTING CONDITIONS PLAN
5	C-4	INDIAN SPRINGS PROPOSED CONDITIONS PLAN
6	C-5	INDIAN SPRINGS PROPOSED GRADING PLAN
7	C-6	ARMY CAMP PROPOSED CONDITIONS
8	C-7	CIVIL CONSTRUCTION DETAILS
9	C-8	CIVIL CONSTRUCTION DETAILS BUILDING SHEETS
10	B-1	INDIAN SPRINGS PRECAST CONCRETE BUILDING ELEVATIONS
11	B-2	INDIAN SPRINGS BUILDING FLOOR PLANS STRUCTURAL SHEETS
12	S-1	GENERAL NOTES AND TYPICAL DETAILS
13	S-2	FOUNDATION PLAN, SECTIONS AND DETAILS






*Locus Plan*  
SCALE: 1" = 6,000'

PROJECT No. 19.21.01  
FOR PERMITTING  
DECEMBER 2021

## Index of Drawings

Sheet No.	Dwg. No.	Description
14	M-1	MECHANICAL SHEETS PLANT MECHANICAL NOTES AND LEGEND
15	M-2	MECHANICAL SCHEDULES
16	M-3	MECHANICAL PROCESS PIPING PLAN
17	M-4	MECHANICAL PROCESS PIPING SECTIONS
18	M-5	WELL HOUSE CHEMICAL FEED SYSTEMS
19	M-6	MECHANICAL DETAILS HVAC SHEETS
20	H-1	MECHANICAL HVAC NOTES, SYMBOLS, AND ABBREVIATIONS ELECTRICAL SHEETS
21	E-1	ELECTRICAL NOTES, SYMBOLS, AND ABBREVIATIONS
22	E-2	ELECTRICAL POWER DETAILS AND SCHEDULE INSTRUMENTATION SHEETS
23	I-1	SCADA SYSTEM SCHEMATIC
24	I-2	INDIAN SPRINGS CHLORINATION
25	I-3	FILTER SKID INSTRUMENTATION
26	I-4	ARMY CAMP CHLORINATION



- LEGEND**
- BALL VALVE
  - BUTTERFLY VALVE
  - ELECTRIC ACTUATED VALVE
  - GATE VALVE
  - REDUCER
  - COUPLING
  - AIR RELIEF VALVE
  - CHEMICAL INJECTION POINT
  - CENTRAL PUMP
  - DRAIN
  - MAGNETIC FLOW METER
  - SAMPLE TAP
  - FLOW ELEMENT
  - PRESSURE INDICATOR
  - DIFFERENTIAL PRESSURE INDICATOR/TRANSMITTER
  - PRESSURE INDICATING TRANSMITTER
  - ARV - AIR RELIEF VALVE
  - CV - CONTROL VALVE
  - FT - FLOW TRANSMITTER
  - MV - MANUAL VALVE
  - SMV - SAMPLE VALVE



SCALE ADJUSTMENT GUIDE  
 BARS IS ONE INCH ON ORIGINAL DRAWING

NO.	DATE	REVISIONS	DESCRIPTION



PROJECT NO.:	119.21.01
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	SCC
CHECKED BY:	SCC
DRAWN BY:	RAI
APPROVED BY:	LMG

# WATER SYSTEM CHLORINATION & PRETREATMENT

## PRUDENCE ISLAND WATER DISTRICT PRUDENCE ISLAND, RHODE ISLAND

DRAWING TITLE:  
**PROCESS FLOW  
 DIAGRAM**

DRAWING NO.:  
**G-1**

SHEET NO. 1 OF 28

FOR PERMITTING

A. GENERAL NOTES

- 1. CONTRACTOR'S WORK SHALL NOT INTERFERE WITH NORMAL ON-GOING OPERATIONS OF THE EXISTING WATER TREATMENT PLANT...
2. THE CONTRACTOR IS ADVISED THAT IF ANY BE NECESSARY TO WORK DURING PERIODS OUTSIDE NORMAL WORKING HOURS...
3. NOTICE TO CONTRACTOR: THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AND STRUCTURES AS SHOWN ON THESE PLANS...
4. DATUM: THE PROJECT VERTICAL DATUM IS A LOCAL DATUM, SEE PROJECT BENCHMARKS SHOWN ON THE PLANS.
5. CONSTRUCTION STAKING CONTROL: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ESTABLISHING AND MAINTAINING ALL CONTROL POINTS AND BENCH MARKS NECESSARY TO PERFORM THE WORK.
6. IT SHOULD BE NOTED THAT ADDITIONAL UTILITY STRUCTURES MAY EXIST: THE LOCATION AND SIZES OF EXISTING PIPES, DUCTS, CONDUITS AND ANOTHER UNDERGROUND STRUCTURES SHOWN ON THE DRAWINGS ARE NOT WARRANTED TO BE EXACT NOR IS IT WARRANTED THAT ALL UNDERGROUND STRUCTURES BEFORE BEGINNING CONSTRUCTION...
7. IT IS THE GENERAL CONTRACTOR'S RESPONSIBILITY TO REVIEW THE SITE CONDITIONS BEFORE THE PREPARATION AND SUBMITTAL OF HIS BID...
8. DO NOT SCALE DRAWINGS UNLESS OTHERWISE NOTED. WRITTEN DIMENSIONING AND STATIONING SHALL PREVAIL. REPORT ANY DISCREPANCIES TO THE ENGINEER IMMEDIATELY.
9. THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE REGULATIONS OF THE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA)
10. THE CONTRACTOR SHALL OBTAIN AND PAY THE FEES FOR ANY AND ALL ADDITIONAL PERMITS REQUIRED FOR THE PROPER EXECUTION OF ALL PHASES OF THE PROJECT.
11. REFER TO EARTHWORK SPECIFICATION SECTION AND/OR CONSTRUCTION DETAIL SHEETS FOR BEDDING AND BACKFILL REQUIREMENTS.
12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER EXECUTION OF ALL PHASES OF THE PROJECT.
13. THE CONTRACTOR HAS REACHED SUBSTANTIAL COMPLETION.
14. THE LOCATION AND LIMITS OF ALL ON-SITE WORK AREAS SHALL BE REVIEWED/COORDINATED WITH, AND ACCEPTABLE TO PRUDENCE ISLAND WATER DISTRICT AND THE ENGINEER. THE CONTRACTOR SHALL LIMIT HIS ACTIVITIES TO THESE AREAS.
15. ALL UTILITY SIZES, LOCATIONS, AND APPEARANCES ARE SUBJECT TO THE APPROVAL AND/OR REVISION OF THE RESPECTIVE UTILITY HAVING JURISDICTION.
16. ALL MATERIALS TO BE REMOVED MUST BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
17. ALL TEMPORARY SEDIMENTATION BASINS AND DEMATERING EQUIPMENT TO BE INSTALLED PRIOR TO ANY DEMETERING ACTIVITIES ON THE SITE AS REQUIRED.
18. ANY ALTERATIONS REQUIRED ON THESE DRAWINGS DURING CONSTRUCTION SHALL BE APPROVED BY THE ENGINEER PRIOR TO CONSTRUCTION AND RECORDED BY THE CONTRACTOR ON THE AS-BUILT DRAWINGS.
19. CONTRACTOR SHALL BE RESPONSIBLE FOR THE PREPARATION, SUBMITTAL AND APPROVAL OF ALL REQUIRED STORMWATER DRAINAGE AND GROUNDWATER DISCHARGE OR CONSTRUCTION PERMITS AND PLANS, SUCH AS NPDES CONSTRUCTION PERMIT AND THE DEVELOPMENT OF SITE SPECIFIC SWPPP. SUGGESTED SWPPP NOTES ARE INCLUDED IN SECTION D OF THIS SHEET FOR CONTRACTOR'S USE.
20. THE CONTRACTOR SHALL NOT OPEN OR CLOSE ANY VALVES WHICH HOLD WATER IN THE SYSTEM, UNLESS GRANTED APPROVAL TO DO SO BY THE PRUDENCE ISLAND WATER DISTRICT.
21. ALL EQUIPMENT SHALL BE DE-ENERGIZED AND MADE SAFE BEFORE DEMOLITION.
22. THE CONTRACTOR IS ADVISED THAT HAZARDOUS CHEMICALS MAY BE PRESENT IN PROPOSED AREAS OF WORK. CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO ENSURE THE SAFETY OF PERSONNEL WORKING IN AND AROUND THE AREAS.

B. DIMENSIONS AND QUANTITIES

- 1. ALL DIMENSIONS AND QUANTITIES SHALL BE DETERMINED OR VERIFIED BY THE CONTRACTOR.
2. THE CONTRACTOR IS ADVISED TO TAKE ALL PRECAUTIONS AND MAKE ALL INVESTIGATIONS NECESSARY TO PERFORM THE WORK. THE OWNER WILL NOT CONSIDER CONTRACTOR'S UNFAMILIARITY WITH THE PROJECT OR SITE CONDITIONS AT THE TIME OF BID AS A BASIS FOR ADDITIONAL COMPENSATION.

C. PROTECTION NOTES

- 1. ABSOLUTE PROTECTION OF PERSONS AND PROPERTY SHALL BE PROVIDED AT ALL TIMES. THE WORK SHALL BE EXECUTED IN SUCH A WAY AS TO AVOID HAZARD TO PERSONS AND PROPERTY. WORK SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THE REQUIREMENTS OF LOCAL, STATE AND FEDERAL AGENCIES HAVING JURISDICTION OVER THE WORK.
2. PROVIDE ALL NECESSARY TEMPORARY PROTECTION AND BARRIERS TO SEGREGATE THE WORK AREA AND TO PREVENT DAMAGE TO ADJACENT AREAS, AS REQUIRED BY ALL JURISDICTION REGULATIONS.
3. PROVIDE PROPER PROTECTION AND BARRIERS BETWEEN THE WORK OF THIS CONTRACT AND EXISTING STRUCTURES TO REMAIN.
4. THE CONTRACTOR SHALL RESTORE ALL DAMAGED PRIVATE AND PUBLIC PROPERTY DURING CONSTRUCTION TO ITS PRE-CONSTRUCTION CONDITION, AT NO COST TO THE OWNER.
5. THE CONTRACTOR IS TO TAKE SPECIAL CARE NOT TO DAMAGE TREES, BUSHES, PLANTS, FLOWERS, STONEWALLS, FENCES, BUILDING ETC. WITHIN THE CONSTRUCTION AREA UNLESS THEY ARE NOTED TO BE REMOVED.
6. CONTRACTOR SHALL REMOVE AND REPLACE OR REPAIR ALL CURBS, SIDEWALKS, STONE WALLS, PAVEMENT, CANALS, ACCESS ROADS, LANDSCAPING, TREES AND OTHER ITEMS INTENDED TO REMAIN IN PLACE UNTIL AFTER CONSTRUCTION ACTIVITIES TO AT LEAST THEIR ORIGINAL CONDITION, AND TO THE SATISFACTION OF THE PRUDENCE ISLAND WATER DISTRICT AND THE ENGINEER AT NO ADDITIONAL COST TO THE OWNER.
7. THE CONTRACTOR, AT NO ADDITIONAL COST TO THE OWNER, SHALL REPAIR ANY EXISTING UTILITIES TO REMAIN, WHICH ARE DAMAGED DURING CONSTRUCTION.
8. IN THOSE INSTANCES WHERE POWER OR TELEPHONE POLE SUPPORT IS REQUIRED, THE CONTRACTOR SHALL PROVIDE A MINIMUM 48-HOUR NOTIFICATION TO THE RESPECTIVE UTILITY COMPANY; NO ADDITIONAL PAYMENT WILL BE PROVIDED FOR TEMPORARY BRACING OF UTILITIES.
9. ALL STRUCTURES AND BUILDINGS LOCATED ADJACENT TO THE TRENCH EXCAVATION SHALL BE PROTECTED AND FIRMLY SUPPORTED BY THE CONTRACTOR UNTIL THE TRENCH IS BACKFILLED. INJURY TO ANY SUCH STRUCTURE CAUSED BY OR RESULTING FROM THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE. ALL UTILITIES REQUIRING REPAIR, RELOCATION OR ADJUSTMENT AS A RESULT OF THE PROJECT SHALL BE COORDINATED THROUGH THE RESPECTIVE UTILITY AND THE TOWN.
10. OPEN TRENCHES MUST BE BACKFILLED AT THE END OF THE WORKDAY OR COVERED WITH STEEL PLATES.

D. STORMWATER POLLUTION PREVENTION PLAN

- 1. DEMOLITION, SEDIMENTATION, AND EROSION CONTROL (STORMWATER POLLUTION PREVENTION PLAN);
2. THE FIRST STAGE INVOLVES ACTIVITIES NEEDED TO ADDRESS STORMWATER MANAGEMENT: EXCAVATING MATERIAL DESIGNATED FOR OFF-SITE DISPOSAL OR ON-SITE RELOCATION AND FENCING SELECTED AREAS. STAGE ONE WILL PREPARE SITE FOR CONSTRUCTION.

D. STORMWATER POLLUTION PREVENTION PLAN (CONT.)

- 4. TYPICAL PRACTICES TO BE APPLIED TO THE SITE INCLUDE THE FOLLOWING:
A. PRIOR TO EARTH DISTURBANCE IN ANY WORK AREA, CHECK PREVIOUSLY INSTALLED SITUATION BARRIERS (STRIP MATTE) BETWEEN THE WORK AREA AND ANY WETLAND AREAS OR OTHER RECOGNIZED SENSITIVE AREA WHERE CONSTRUCTION AREA RUNOFF MAY DRAIN TOO, AND IN FULL ACCORD WITH THE DEMOLITION AND EROSION CONTROL PLANS. EROSION CONTROL MEASURES WILL BE INSPECTED AND REPAIRED AS NEEDED WEEKLY OR FOLLOWING EACH MAJOR RAINFALL EVENT (GREATER THAN 0.5") WHICHEVER IS SOONER.
B. DISCHARGE WATER FROM DEMATERING SUPERORDERS TO A TEMPORARY SITUATION TRAP OR SEDIMENTATION BASIN. ALL EXISTING STOCKPILES OF MATERIAL AS SHOWN ON THE DRAWINGS SHALL BE STABILIZED AND SURROUNDED BY EROSION CONTROLS.
C. PROVIDE TEMPORARY BERRMS AND SWALES TO DIVERT SURFACE WATER AWAY FROM THE AREAS THAT WILL BE EXPOSED BY CONSTRUCTION ACTIVITY TO MINIMIZE THE AMOUNT OF STABILIZED MATERIAL CONTACT WITH EXPOSED SOILS. PROVIDE STABLE OUTLETS FOR THESE DRENCHES, AND LINE OR VEGETATE THESE DIMENSIONS TO PROVIDE FOR THEIR STABILITY DURING CONSTRUCTION.
D. LIMIT THE EXTENT OF EXPOSED SOILS TO AREAS THAT CAN BE WORKED AND RESTABILIZED WITHIN THE CONSTRUCTION SEASON AND DURING THE SPECIFIC CONSTRUCTION PHASE. WHEN EARTHWORK CONSTRUCTION ACTIVITY IN AN AREA IS COMPLETE, STABILIZE THE AREA WITH A SUITABLE SURFACE AS DESCRIBED BELOW.
E. ALL CONSTRUCTION VEHICLES EXITING THE SITE WILL BE HOSED DOWN (AS NEEDED) TO REMOVE ALL SOIL. REFER TO CIVIL CONSTRUCTION DETAILS FOR ENTRANCE PAD CONSTRUCTION DETAIL, WHICH SHALL BE MAINTAINED DURING CONSTRUCTION.
F. THE CONTRACTOR WILL BE RESPONSIBLE FOR THE CONTROL OF DUST AND IMPLEMENT CONSTRUCTION MEASURES WITH THE INTENT TO PRECLUDE THE GENERATION OF EXCESS DUST, AND AS DIRECTED BY THE OWNER'S REPRESENTATIVE.
G. EXISTING PAUL ROADS AND PARKING LOTS AND ROADWAYS ADJACENT TO THE SITE WILL BE GUERD BY A UNPROTECTED STREET. STREETER WEEKLY OR AS NEEDED TO REMOVE LOSE SOIL MATERIALS ACCUMULATED FROM SUPERORDERS PAID SUPERORDERS. THE CONTRACTOR SHALL FOLLOW THE SPEED PRACTICES DESCRIBED BELOW WITH THE DIRECTIONS OF THE APPLICANT'S REPRESENTATIVE TO ADDRESS EROSION AND SEDIMENTATION CONDITIONS THAT MAY ARISE ON A CASE BY CASE BASIS DURING CONSTRUCTION.
H. THE FOLLOWING IS A DESCRIPTION OF MINIMUM CONSTRUCTION REQUIREMENTS AND DOES NOT RELIEVE THE CONTRACTOR OF HIS RESPONSIBILITIES WITH REGARD TO DETERMINING THE ADEQUACY OF MEANS AND METHODS OF CONSTRUCTION.
5. THE ANTICIPATED CONSTRUCTION SEQUENCING IS DESCRIBED IN SECTION 01010 OF THE SPECIFICATIONS. THE CONTRACTOR SHALL SUBMIT A HIS SEQUENCE OF WORK FOR THE OVERALL PROJECT FOR THE ENGINEER'S REVIEW AND APPROVAL.
7. MAINTENANCE:
A. DURING THE PERIOD OF CONSTRUCTION:
A. TEMPORARY DEMATERING SEDIMENTATION BASINS, IF REQUIRED, WILL BE CHECKED AFTER EACH SIGNIFICANT RAINFALL AND CLEANED AS NEEDED TO REMAIN STORAGE CAPACITY.
B. TEMPORARY DRAINAGE SWALES WILL BE CHECKED WEEKLY AND REPAIRED WHEN NECESSARY.
C. THE HAYBALE AND SITUATION FENCING BARRIERS AND OTHER EROSION AND SEDIMENT CONTROL MEASURES/DEVICES SHALL BE INSPECTED, CLEANED, REPLACED AND/OR REPAIRED AS NECESSARY, WEEKLY AND AFTER EACH SIGNIFICANT RAINFALL.





Table with 2 columns: NO., DATE. Rows for REVISIONS.






Table with 2 columns: PROJECT NO., DATE. Rows for project metadata.


Water System Chlorination & Pretreatment Prudence Island Water District. Includes drawing title, legend notes, and sheet number C-1.

EXISTING LEGEND



PROPOSED LEGEND





**GENERAL NOTES**

1. HORIZONTAL AND VERTICAL DATUM IS BASED ON LOCAL DATUM.
2. PROJECT BENCH MARK ESTABLISH IN THE MIDDLE OF THE CONCRETE STEP TO THE PUMP HOUSE. BENCH MARK ELEVATION IS 102.96.
3. CONSTRUCTION BASELINE HUB & TACK ESTABLISHED AT STA.0+60.00 AND STA.2+86.86.



FOR PERMITTING

**H2Olson Engineering, Inc.**  
 DRINKING WATER PROFESSIONALS  
 www.h2olsonengineering.com  
 (908) 375-0077

SCALE ADJUSTMENT GUIDE  
 0" = 1"  
 PAPER IS ONE INCH IN ORIGINAL DRAWING

REVISIONS	
NO.	DATE



PROJECT NO.:	1192101
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	RLK
CHECKED BY:	SCO
DRAWN BY:	RLK
APPROVED BY:	LMG

**WATER SYSTEM CHLORINATION & PRETREATMENT**  
 PRUDENCE ISLAND WATER DISTRICT  
 PRUDENCE ISLAND, RHODE ISLAND

DRAWING TITLE:  
 INDIAN SPRING  
 EXISTING CONDITIONS  
 PLAN


DRAWING NO.:  
**C-2**  
 SHEET NO. 3 OF 26



**H2Olson Engineering, Inc.**  
DRINKING WATER PROFESSIONALS  
www.h2olsonengineering.com  
(888) 375-0807

SCALE ADJUSTMENT GUIDE  
OR  
BAR IS ONE INCH ON ORIGINAL DRAWING

REVISIONS	
NO.	DATE



PROJECT NO.:	1192101
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	RJK
CHECKED BY:	SCO
DRAWN BY:	RJK
APPROVED BY:	LMG



**WATER SYSTEM CHLORINATION & PRETREATMENT**  
PRUDENCE ISLAND WATER DISTRICT  
PRUDENCE ISLAND, RHODE ISLAND

DRAWING TITLE:  
**ARMY CAMP EXISTING CONDITIONS PLAN**


DRAWING NO.:  
**C-3**  
SHEET NO. 4 OF 26



- GENERAL NOTES**
- HORIZONTAL AND VERTICAL DATUM IS BASED ON LOCAL DATUM.
  - PROJECT BENCH MARK ESTABLISH ON THE MIDDLE EDGE OF THE CONCRETE SLAB FOR THE BACKUP GENERATOR. BENCH MARK ELEVATION IS 176.87.
  - CONSTRUCTION BASELINE HUB & TACK ESTABLISHED AT STA.0+00.00 AND STA.1+28.06.




FOR PERMITTING



**GENERAL NOTES**

1. THE STATION AND OFFSET FROM THE CONSTRUCTION BASELINE FOR THE PROPOSED BUILDING CORNERS ARE AS FOLLOWS:  
 NE CORNER - STA:2+27.14, 0.00'R  
 NW CORNER - STA:2+27.14, 0.97'R  
 SW CORNER - STA:2+50.64, 24.50'R  
 SE CORNER - STA:2+26.64, 24.00'R
2. SUBSURFACE EXPLORATION WAS PERFORMED NOVEMBER 1, 2021 BY MEANS OF TEST PITTING, AS SHOWN ON THIS SHEET. TEST PIT #1 (TP-1) WAS PERFORMED WEST OF THE PROPOSED BUILDING. A SUMMARY OF SOIL CONDITIONS ARE ENCOUNTERED ARE AS FOLLOWS:  
 DEPTH      SOIL DESCRIPTION  
 0.0'-1.0'    MOSTLY BLACK TOPSOIL WITH ROOT MATTER FROM VEGETATED (GRASSED)  
 1.0'-7.0'    DRY TAN FINE SAND TRACE SILT  
 7.0'-9.5'    DRY GRAY FINE SAND TRACE SILT  
 9.5'-10.5'    DRY GRAY FINE SAND TRACE SILT AND OCCASIONAL COBBLE  
 10.5'        BOTTOM OF EXCAVATION
3. REFER APPENDIX IN CONTRACT DOCUMENTS FOR TEST PIT LOG INFORMATION.



FOR PERMITTING

**H2Olson Engineering, Inc.**  
 DRINKING WATER PROFESSIONALS  
 www.h2olsonengineering.com  
 (908) 375-0077

SCALE ADJUSTMENT GUIDE  
 0" = 1" SCALE IN ORIGINAL DRAWING

NO.	DATE	DESCRIPTION




PROJECT NO.:	119.21.01
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	RLK
CHECKED BY:	SCO
DRAWN BY:	RLK
APPROVED BY:	LMG

**WATER SYSTEM CHLORINATION & PRETREATMENT**  
 PRUDENCE ISLAND WATER DISTRICT  
 PRUDENCE ISLAND, RHODE ISLAND

DRAWING TITLE:  
**INDIAN SPRING PROPOSED CONDITIONS PLAN**

DRAWING NO.:  
**C-4**  
 SHEET NO. 5 OF 26





PROPOSED MANHOLE COVERS TO BACKWASH SETTLING TANK  
 MH (EAST) RIM EL.69.28  
 MH (MIDDLE) RIM EL.68.24  
 MH (WEST) RIM EL.69.22

PROPOSED MANHOLE COVERS TO INFILTRATION GALLEY  
 MH RIM EL.69.18


PROPOSED CRUSHED STONE SPLASH PAD  
 (1.5x1.5x0.33) REFER TO NOTE 3, THIS SHEET.

PROPOSED 4'x8' CONCRETE LANDING

PROPOSED BLDG.  
 FF 69.60

**GENERAL NOTES**

- CONTRACTOR SHALL LOAM, SEED AND FERTILIZE ALL DISTURBED VEGETATIVE AREAS OUTSIDE THE LIMIT OF WORK, AT NO COST TO THE OWNER. LOAM THICKNESS SHALL BE 4-INCH MINIMUM.
- UNDER THE LUMP SUM BID ITEM, ALL NEW VEGETATIVE SURFACE AREAS CALLED OUT WITHIN THE LIMITS OF WORK AND ON THE PLANS SHALL BE COMPRSED OF 4-INCH LOAM, 1.5-INCH TOPSOIL, AND 1.5-INCH CRUSHED STONE. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR PREPARING AND FERTILIZING ANY AREA DISTURBED AS PART OF CONSTRUCTION ACTIVITY, AT NO ADDITIONAL COST TO THE OWNER.
- PROPOSED CRUSHED STONE SPLASH PAD, LOCATED NEAR THE NORTHWEST CORNER OF THE PROPOSED BUILDING, SHALL BE CONSTRUCTED OF 4-INCH THICK LAYER OF 3/4-INCH CRUSHED STONE IN A 1.5'-11" DEEP RADIUS TOODRINKING MIDDLE OF CRUSHED STONE PAD IS TO BE PLACED OVER 4'-4" NOMINOWN GEOTEXTILE. STONE PAD SHALL BE INSTALLED OVER 4'-4" NOMINOWN GEOTEXTILE TO BE PLACED ACROSS THE BOTTOM OF THE PAD AND EXTEND UP THE CRUSHED STONE SIDEWALL TO THE SURFACE.



FOR PERMITTING

**H2Olson Engineering, Inc.**  
 DRINKING WATER PROFESSIONALS  
 www.h2olsonengineering.com  
 (908) 375-0677

SCALE ADJUSTMENT GUIDE  
 0" = 1" ORIGINAL DRAWING

REVISIONS	
NO.	DATE



PROJECT NO.:	1192101
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	RAK
CHECKED BY:	SCO
DRAWN BY:	RAK
APPROVED BY:	LMG

**WATER SYSTEM CHLORINATION & PRETREATMENT**  
 PRUDENCE ISLAND WATER DISTRICT  
 PRUDENCE ISLAND, RHODE ISLAND

DRAWING TITLE:  
**INDIAN SPRING PROPOSED GRADING PLAN**

DRAWING NO.:  
**C-5**

SHEET NO. 6 OF 26



**H2Olson Engineering, Inc.**  
DRINKING WATER PROFESSIONALS  
www.h2olsonengineering.com  
(888) 375-0007

SCALE ADJUSTMENT GUIDE  
OR  
BAR IS ONE INCH ON ORIGINAL DRAWING

REVISIONS	
NO.	DATE

**LISA GOYER**  
No. 11536  
REGISTERED PROFESSIONAL ENGINEER  
CIVIL

PROJECT NO.:	1192101
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	RJK
CHECKED BY:	SCO
DRAWN BY:	RJK
APPROVED BY:	LMG

**WATER SYSTEM CHLORINATION & PRETREATMENT**  
PRUDENCE ISLAND WATER DISTRICT  
PRUDENCE ISLAND, RHODE ISLAND


DRAWING TITLE:  
**ARMY CAMP PROPOSED CONDITIONS PLAN**


DRAWING NO.:  
**C-6**  
SHEET NO. 7 OF 26



- GENERAL NOTES**
1. CONTRACTOR SHALL LOAM, SEED AND FERTILIZE ALL DISTURBED VEGETATIVE AREAS WITHIN THE LIMITS OF WORK, AT NO COST TO THE OWNER. LOAM THICKNESS SHALL BE 4-INCH MINIMUM.
  2. UNDER THE LUMP SUM BID ITEM, ALL NEW VEGETATIVE SURFACE AREAS CALLED OUT WITHIN THE LIMITS OF WORK AND ON THE PLANS SHALL BE COMPRISED OF 4-INCH LOAM, SEED, FERTILIZER AND WHERE APPLICABLE SHALL INCLUDE EROSION CONTROL BLANKET. IN ADDITION, THE CONTRACTOR SHALL ALSO BE PREPARED TO LOAM, SEED AND FERTILIZE ALL AREAS DESIGNATED AS PART OF CONSTRUCTION ACTIVITY, AT NO ADDITIONAL COST TO THE OWNER.

FOR PERMITTING






- ENTRANCE PAD NOTES:**
- NON-WOVEN GEOTEXTILE FABRIC SHALL BE PLACED OVER THE ENTIRE AREA OF THE CONSTRUCTION ENTRANCE PRIOR TO PLACING STONE.
  - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OF FLOWING SEDIMENT ONTO PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT WASHED OFF OR TRACKED ONTO PUBLIC RIGHT-OF-WAY MUST BE REMOVED PROMPTLY.
  - AT THE COMPLETION OF CONSTRUCTION THE CONTRACTOR SHALL REMOVE THE CONSTRUCTION ENTRANCE PAD AND RESTORE THE SURFACE TO ORIGINAL CONDITION.

**CONSTRUCTION ENTRANCE PAD**

SCALE: NOT TO SCALE




- MINIMUM SURFACE AREA OF CONCRETE THRUST BLOCK AGAINST UNDISTURBED EARTH - SF<sup>2</sup> (SQUARE FEET)
- MINIMUM RESTRAINED LENGTH OF PIPE ON EITHER SIDE OF FITTING - LF (LINEAR FEET)

PIPE SIZE	PLUG LF	TEE LF	90° BEND LF	45° BEND LF	22 1/2° BEND LF	11 1/4° BEND LF
6"	2.8	3.7	2.8	4.0	1.8	2.1
8"	4.8	4.8	5.3	6.8	2.3	3.7
10"	7.3	5.8	7.3	10.3	3.8	5.6
12"	10.3	6.9	10.3	14.5	5.3	7.9
16"	17.8	8.9	17.8	25.2	9.2	14.0
20"	27.5	10.8	27.5	38.9	13.6	21.0
24"	39.2	12.7	39.2	53.4	19.1	29.0

- NOTES:**
- THE "SF" VALUES IN THE ABOVE TABLE ARE BASED ON 3,000 P.S.F. SOIL BEARING CAPACITY, 150 P.S.I. TEST PRESSURE AND A 1.5 FACTOR OF SAFETY.
  - THE "LF" VALUES IN THE ABOVE TABLE ARE BASED ON A TYPE 3 LAYING CONDITION, A SAND SILT SOIL DESIGNATION, A 5 FOOT RUN LENGTH, 150 P.S.I. TEST PRESSURE AND A 1.5 FACTOR OF SAFETY.


**RESTRAINT AT FITTINGS**

SCALE: NOT TO SCALE



**SEDIMENTATION CONTROL BARRIER**


SCALE: NOT TO SCALE



**GATE VALVE AND VALVE BOX DETAIL**

SCALE: NOT TO SCALE


ITEM	ITEM / DESCRIPTION
1	TOP CAP
2	SLOTTED OPERATING NUT
3	2-1/2" NST OUTLET
4	2" COUPLING
5	2" STEEL PIPE
6	INLET VALVE BODY
7	LOCKING COVER
8	DRAIN HOLE
9	HYDRANT SHUT-OFF VALVE
10	CRUSHED ROCK
11	VALVE BOX
12	SOLID CONCRETE BLOCK
13	2" STREET ELBOW



**2-INCH BLOW-OFF HYDRANT**

SCALE: NOT TO SCALE


**HYDRANT NOTES:**  
 BLOW-OFF HYDRANT SHALL BE SELF-DRAINING, NON-FREEZING TYPE WITH A 4" DEPTH OF BURY. HYDRANT SHALL BE FURNISHED WITH A 2" FIP VERTICAL INLET CONNECTION, A NON-TURNING OPERATING ROD AND SHALL OPEN TO THE LEFT. OUTLET SHALL BE 2-1/2" NST OR SMALLER (MUST SPECIFY ON ORDER WITH CAP AND EXTEND A MINIMUM OF 12" ABOVE THE GROUND.  
 ALL WATER FLOW SHALL PASS THRU A 2" STEEL PIPE AND WATERWAY. THE OPERATING DRIVE MECHANISM SHALL RAISE AND LOWER A PLUNGER TO CONTROL THE FLOW OF WATER AND SHALL BE SERVICEABLE FROM ABOVE GROUND WITH NO NEED FOR SPECIAL TOOLS. OPERATING ROD SHALL BE STANDARD UNIVERSAL SHD OPERATING DRIVE SHALL OPERATE WITH A STANDARD UNIVERSAL SLOTTED VALVE WRENCH. WHEN OPEN THE FLOW OF WATER SHALL BE UNOBSTRUCTED AND THE DRAIN HOLE SHALL BE COVERED.  
 HYDRANT SHALL BE SET IN 4 CUBIC FEET OF CRUSHED STONE TO ALLOW FOR PROPER DRAINAGE OF HYDRANT. CRUSHED STONE SHALL BE WRAPPED WITH 4-0Z NON-WOVEN GEOTEXTILE. ALL GEOTEXTILE SEAMS SHALL HAVE MINIMUM 12 LAP. RECORD INDICATION OF THE A.M.V. SHOULD BE FOLLOWED WHEN INSTALLING THE HYDRANT.  
 THE MANGUARD MODEL #77 BLOW-OFF HYDRANT AS MANUFACTURED BY THE KUPFERLE FOUNDRY, ST. LOUIS MO. 63102 OR APPROXIMATELY EQUAL.



**DENSE GRADED CRUSHED STONE ACCESS ROAD DETAIL**

SCALE: NOT TO SCALE


- NOTE:**
- DENSE GRADED CRUSHED STONE SHALL MEET MASSDOT M2.017 SPECIFICATION AND GRADATION REQUIREMENTS.
  - MATERIAL SHALL BE COMPACTED TO 95% OF THE MAX. DRY DENSITY OF THE MATERIAL, AS DETERMINED BY LABORATORY TESTING.
  - CONTRACTOR SHALL PREPARE LEVEL SUBGRADE TO RECEIVE THE DENSE GRADE CRUSHED STONE AND SHALL PERFORM AT A MINIMUM PROOF ROLLS THE SUBGRADE FOUR TIMES WITH A 10-TON SMOOTH DRUM ROLLER, BEFORE PLACING DENSE GRADE CRUSHED STONE.



**GRASSED VEGETATED SURFACE**

SCALE: NOT TO SCALE

- NOTES:**
- ALL GRASSSED SURFACE SLOPES STEEPER THAN 7H:1V SLOPE SHALL INCLUDE THE INSTALLATION OF EROSION CONTROL BLANKET AFTER THE LOAM, SEED AND FERTILIZER HAVE BEEN PLACED.
  - MATERIAL SPECIFICATIONS FOR THE EROSION CONTROL BLANKET SHALL MEET CORLEX II EROSION CONTROL BLANKET AS MANUFACTURED BY AMERICAN EXCELSIOR COMPANY, OR EQUAL.



**TYPICAL TRENCH DETAIL**

SCALE: NOT TO SCALE

- TYP. TRENCH NOTES:**
- MIN. COVER 5' COVER FOR WATER MAIN
  - MIN. 3' COVER FOR STORM DRAIN

FOR PERMITTING

**H2Olson Engineering, Inc.**  
 DRINKING WATER PROFESSIONALS  
 www.h2olsonengineering.com  
 (908) 375-0307

SCALE ADJUSTMENT GUIDE  
 0" = 1"  
 BARS ONE INCH ON ORIGINAL DRAWING


NO.	DATE	REVISIONS

LISA GOYER  
 No. 11536  
 REGISTERED PROFESSIONAL ENGINEER  
 CIVIL


PROJECT NO.:	1192101
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	RLK
CHECKED BY:	SCO
DRAWN BY:	RLK
APPROVED BY:	LMG

**WATER SYSTEM CHLORINATION & PRETREATMENT**  
 PRUDENCE ISLAND WATER DISTRICT  
 PRUDENCE ISLAND, RHODE ISLAND

DRAWING TITLE: CIVIL CONSTRUCTION DETAILS  
 DRAWING NO.: C-7  
 SHEET NO. 8 OF 26




**FILTER BACKWASH INFILTRATION SYSTEM - SECTION**  
SCALE: N.T.S.




- SETTLING TANK NOTES:**
1. CONCRETE: 4,000 PSI MINIMUM AFTER 28 DAYS.
  2. DESIGN CONFORMS WITH 310 CUR, SECTION 15.00 DEP TITLE 5 REGS FOR SEPTIC TANKS
  3. ALL REINFORCEMENT PER ASTM C1227.
  4. BAFFLE WALL OPTIONAL FOR TWO COMPARTMENT TANKS.
  5. TIES AND GAS BAFFLE SOLD SEPARATELY.
  6. TONGUE & GROOVE JOINT SEALED WITH BUTYL RESIN.
  7. IF COVER EXCEEDS 4 FEET, HEAVY DUTY TANK REQUIRED. ALSO AVAILABLE IN AASHTO HS-20 LOADING.

**PLAN VIEW**




**SECTION VIEW A-A**


**BACKWASH (2,000 GALLON) SETTLING TANK DETAIL**  
SCALE: N.T.S.



**FRONT VIEW**




**PLAN VIEW**




**SIDE VIEW**


**BACKWASH INFILTRATION (4'X4') GALLEY DETAIL**  
SCALE: N.T.S.



**TYPICAL PIPE BOOT SEAL**  
SCALE: N.T.S.



**PLAN VIEW**



**SECTION VIEW A-A**

**SECTION VIEW B-B**


**6-FT DIAMETER DRY WELL**  
SCALE: N.T.S.

FOR PERMITTING



SCALE ADJUSTMENT GUIDE  
0" = 1" IN ORIGINAL DRAWING

REVISIONS	
NO.	DESCRIPTION



PROJECT NO.:	1192101
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	RJK
CHECKED BY:	SCO
DRAWN BY:	RJK
APPROVED BY:	LMG

**WATER SYSTEM CHLORINATION & PRETREATMENT**  
PRUDENCE ISLAND WATER DISTRICT  
PRUDENCE ISLAND, RHODE ISLAND

DRAWING TITLE: **CIVIL CONSTRUCTION DETAILS**  
DRAWING NO.: **C-8**  
SHEET NO. **9** OF **26**

**H2Olson Engineering, Inc.**  
 DRINKING WATER PROFESSIONALS  
 www.h2olsonengineering.com  
 (800) 375-0007

SCALE ADJUSTMENT GUIDE  
 0" = 1"  
 PARTS ONE INCH ON ORIGINAL DRAWING

REVISIONS	
NO.	DATE

PROJECT NO.:	119.21.01
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	SCO
CHECKED BY:	SCO
DRAWN BY:	LMG
APPROVED BY:	LMG


**WATER SYSTEM CHLORINATION & PRETREATMENT**  
 PRUDENCE ISLAND WATER DISTRICT  
 PRUDENCE ISLAND, RHODE ISLAND

DRAWING TITLE: **INDIAN SPRINGS PRECAST CONCRETE BUILDING ELEVATIONS**


DRAWING NO.: **B-1**

SHEET NO. **10** OF **26**


**EAST ELEVATION**  
 SCALE: 1/2" = 1'




**NORTH ELEVATION**  
 SCALE: 1/2" = 1'




**WEST ELEVATION**  
 SCALE: 1/2" = 1'




**SOUTH ELEVATION**  
 SCALE: 1/2" = 1'




**B1 - DOOR AND LOUVER HEAD DETAIL**  
 SCALE: N.T.S.



**B2 - DOOR JAMB DETAIL**  
 SCALE: N.T.S.



**B3 - DOOR SILL DETAIL**  
 SCALE: N.T.S.



FOR PERMITTING



**H2Olson Engineering, Inc.**  
DRINKING WATER PROFESSIONALS  
www.h2olsonengineering.com  
(800) 375-0007

SCALE ADJUSTMENT GUIDE  
0" = 1"  
BARS IN ONE INCH ON ORIGINAL DRAWING

NO.	DATE	DESCRIPTION




PROJECT NO.:	119 21 01
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	SCO
CHECKED BY:	SCO
DRAWN BY:	LMG
APPROVED BY:	LMG

**WATER SYSTEM CHLORINATION & PRETREATMENT**  
PRUDENCE ISLAND WATER DISTRICT  
PRUDENCE ISLAND, RHODE ISLAND

DRAWING TITLE:  
**INDIAN SPRINGS BUILDING FLOOR PLANS**

DRAWING NO.:  
**B-2**

SHEET NO. 11 OF 26



**FLOOR PLAN**  
SCALE: 1/2" = 1'

**LIGHTING AND SWITCH LEGEND**

	3-WAY SWITCH (INTERIOR LIGHTS)
	SWITCH (EXTERIOR LIGHTS)
	6"x48" LED CEILING LIGHTING FIXTURE
	A - INTERIOR LIGHT A
	B - INTERIOR LIGHT B
	COMBO EXIT SIGN EM LIGHT (EM2)
	LED EXTERIOR LIGHT (X1)


**POWER LEGEND**

	DUPLEX GFCI RECEPTACLE
	GROUND ROD
	HOMERUN
	FILTER CONTROL PANEL
	TRANSFORMER
	LIGHTING PANEL
	POWER PANEL

**HVAC LEGEND**


	THERMOSTAT
	FAN COIL
	HEAT PUMP

**HVAC, LIGHTING, AND OUTLET PLAN**  
SCALE: 1/2" = 1'



**TYPICAL MOUNTING PLAN**  
FOR PERMITTING  
SCALE: 1/2" = 1'






**FOUNDATION PLAN**  
SCALE: 1/4" = 1'-0"

- NOTES:**
1. REFER TO BUILDING AND MECHANICAL DRAWINGS FOR BUILDING LAYOUT.
  2. **CF1** INDICATES FOOTING TYPE. SEE FOOTING SCHEDULE.  
**65.50'** INDICATES BOTTOM FOOTING ELEVATION.
  3. (\*) ASTERISKS INDICATES DIMENSIONS TO BE COORDINATED WITH PRECAST CONCRETE APPROVED PRECAST CONCRETE BUILDING SHOP DRAWINGS PRIOR TO FABRICATIONS.
  4. COORDINATE PRECAST CONCRETE BUILDING PINNING LAYOUT AND REQUIREMENT BETWEEN THE FOUNDATION PLAN AND DETAIL A ON THIS SHEET AND THE PINNING REQUIREMENT ON THE APPROVED PRECAST CONCRETE BUILDING SHOP DRAWINGS PRIOR TO INSTALLATION.


**FOOTING SCHEDULE**

TYPE	SIZE	REINFORCING
CF1	2'-0" X 1'-0" DEEP X CONT.	3-#4 LONG. & #5@12" TRANS. BOT.



**SECTION 1**  
SCALE: 1/2" = 1'-0"

**SECTION 2**  
SCALE: 1/2" = 1'-0"



**TYP. BUILDING PINNING DETAIL A**  
SCALE: 1" = 1'-0"

- NOTES:**
1. BUILDING PINNING DETAIL, ITS LAYOUT AND REQUIREMENTS TO BE COORDINATED, VERIFIED AND APPROVED BY PRECAST CONCRETE BUILDING'S PROFESSIONAL ENGINEER PRIOR TO FABRICATION AND INSTALLATION. REVISE AS REQUIRED.

FOR PERMITTING

**H2Olson Engineering, Inc.**  
DRINKING WATER PROFESSIONALS  
www.h2olsonengineering.com  
(958) 375-7707

**LIN ASSOCIATES, INC.**  
CONSULTING ENGINEERS  
SCALE ADJUSTMENT GUIDE  
OR  
BASE ONE HONOR  
ORIGINAL DRAWING

**REVISIONS**

NO.	DATE	DESCRIPTION

LISA GOYER  
No. 11536  
REGISTERED PROFESSIONAL ENGINEER  
CIVIL

**PROJECT NO.:** 111921.01.01  
**DATE:** DECEMBER 2021  
**SCALE:** AS NOTED  
**DESIGNED BY:** GK  
**CHECKED BY:** GK  
**DRAWN BY:** RML  
**APPROVED BY:** GK

**WATER SYSTEM CHLORINATION & PRETREATMENT**  
PRUDENCE ISLAND WATER DISTRICT  
PRUDENCE ISLAND, RHODE ISLAND

**DRAWING TITLE:** FOUNDATION PLAN, SECTIONS AND DETAILS  
**DRAWING NO.:** S-2  
**SHEET NO.:** 13 OF 26



**NOTES**

1. THE REQUIREMENTS INCLUDED IN THESE NOTES ARE SUPPLEMENTARY TO THE CONTRACT, GENERAL CONDITIONS, TECHNICAL REQUIREMENTS, AND OTHER REQUIREMENTS SPECIFIED HEREIN.
2. MOUNTING DETAILS PROVIDED ARE GENERIC FOR EQUIPMENT AND DEVICES OF VARIOUS MANUFACTURERS. THE INSTALLING CONTRACTOR MUST STRICTLY COMPLY WITH MANUFACTURER'S INSTRUCTION IN THE INSTALLATION OF THESE DEVICES. IF THERE ARE ANY ENGINEERING ISSUES THEY MUST BE REFERRED TO THE ENGINEER PRIOR TO INSTALLATION.
3. IT IS NOT THE INTENT OF THESE DRAWINGS TO PORTRAY EVERY DETAIL OF THE REQUIRED WORK. THE CONTRACTOR SHALL PROVIDE THE EQUIPMENT AND SYSTEMS COMPLETE SO THAT WHEN ASSEMBLED AND INSTALLED IN THE WORK, THEY SHALL OPERATE AND PERFORM AS DESCRIBED HEREIN.
4. COORDINATE THE WORK REQUIRED BY THESE DRAWINGS ("W" SERIES) WITH THE WORK REQUIRED BY OTHER DRAWINGS.
5. PROVIDE FILLER FLANGES (OR OTHER ENGINEER APPROVED METHOD) TO LIMIT INTERFERENCE BETWEEN WAFER BUTTERFLY VALVES AND DUCTILE IRON PIPE LINING OR CAST IRON FITTINGS.
6. THE CONTRACTOR SHALL NOT OPEN OR CLOSE ANY VALVES WHICH HOLD WATER IN THE SYSTEM, UNLESS GRANTED APPROVAL TO DO SO BY THE PRUDENCE ISLAND WATER DISTRICT.
7. ALL WALL AND FLOOR SLEEVES SHALL BE LARGE ENOUGH TO ACCOMMODATE FLANGES AS REQUIRED. FLOOR SLEEVES SHALL PROJECT AT LEAST 4-IN ABOVE FINISH FLOOR UNLESS OTHERWISE SHOWN. IF SLEEVES ARE TO BE SEALED, PROVIDE GROOVED COUPLING PIPING CONNECTION TO FACILITATE INSTALLATION AND REMOVAL OF PIPING.
8. ALL PIPE PENETRATIONS THROUGH INTERIOR AND EXTERIOR WALLS AND FLOORS SHALL BE SEALED WATERTIGHT.
9. SMALL PIPING (SAMPLE, SERVICE WATER, ETC.) IS SHOWN DIAGRAMMATICALLY. FIELD-ROUTING SUBJECT TO APPROVAL OF THE ENGINEER. SMALL PIPE ROUTING MUST NOT INTERFERE WITH ACCESS TO OR OPERATION OF ANY OTHER PIPE, VALVE, EQUIPMENT, OR BUILDING SYSTEM.
10. ALL PROCESS EQUIPMENT, INCLUDING PUMPS, SHALL BE ISOLATED FROM PIPING LOADS AND DYNAMICS BY FLEXIBLE CONNECTORS IN ACCORDANCE WITH THE MANUFACTURER'S REQUIREMENTS AND SPECIFICATIONS.
11. ALL PIPING, VALVES, EQUIPMENT, ETC. SHALL BE LABELED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
12. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING THE LOCATION FOR ALL WALL PENETRATIONS WITH THE VARIOUS TRADES. WALL PIPES AND WALL SLEEVES SHALL BE REQUIRED FOR ALL PIPE PENETRATIONS THROUGH CONCRETE WALLS WHETHER SHOWN ON THE DRAWINGS OR NOT. ALL WALL AND FLOOR SLEEVES SHALL BE LARGE ENOUGH TO ACCOMMODATE FLANGES, IF REQUIRED.
13. WHEN MAKING NEW CONNECTIONS TO EXISTING PIPING, THE CONTRACTOR MAY, AT ITS OPTION:
  - A. REPLACE PIPING BACK TO NEAREST FITTING
  - B. USE SLEEVE COUPLING OR FLANGE ADAPTERS (RESTRAINED ON PRESSURE LINES).
14. PROVIDE EXPANSION JOINTS WITH CONTROL RODS FOR ALL EXPOSED PIPING CROSSING STRUCTURAL EXPANSION JOINTS.
15. ALL SLEEVE TYPE COUPLINGS ON PRESSURE PIPING SHALL BE HARNESSED UNLESS OTHERWISE INDICATED. WHERE COUPLINGS ARE PROVIDED TO PROVIDE AXIAL FLEXIBILITY, PIPING MUST BE SECURELY RESTRAINED.
16. MATERIALS AND WORKMANSHIP FURNISHED UNDER THIS CONTRACT SHALL BE A STANDARD, HIGH-GRADE QUALITY, AND OF THE BEST WORKMANSHIP AND DESIGN. ALL LIKE PARTS OF EQUIPMENT OF THE SAME SIZE OR CAPACITY SHALL BE INTERCHANGEABLE. SUITABLE PROVISION SHALL BE MADE FOR EASY ADJUSTMENT OR REPLACEMENT OF ALL PARTS REQUIRING ADJUSTMENT OR REPLACEMENT.
17. ALL MECHANICAL LAYOUTS ARE GENERALLY DIAGRAMMATIC AS SHOWN ON THESE DRAWINGS. THE WORK OF THE VARIOUS TRADES SHALL BE COORDINATED TO AVOID INTERFERENCE AND TO SECURE MAXIMUM HEAD ROOM. PARTICULAR ATTENTION IS DRAWN TO CONGESTED SPACES INSIDE AND OUTSIDE OF THE STRUCTURES. IF, IN THE INTEREST OF COORDINATION AND EXPEDIENCY, IT BECOMES NECESSARY TO DEVELOP "INTERFERENCE DRAWINGS" (DEFINED AS DRAWINGS EMBODYING THE WORK OF TRADES INVOLVED, ILLUSTRATING DETAILS OR CONSTRUCTION PROPOSED BY THE CONTRACTOR AND ARRANGEMENT OF ACTUAL EQUIPMENT AND APPARATUS PURCHASED), SUCH DRAWINGS SHALL BE PREPARED BY THE CONTRACTOR AND SHALL BE COORDINATED WITH OTHER TRADES AT NO ADDITIONAL EXPENSE TO THE OWNER.
18. THE INSTALLATION OF FACILITIES AND APPURTENANT WORK SHALL BE PROVIDED IN ACCORDANCE WITH THE REQUIREMENTS OF ALL FEDERAL, STATE, AND MUNICIPAL CODES AND REGULATIONS GOVERNING THE WORK. IN INSTANCES WHERE THE REQUIREMENT OF DRAWINGS AND SPECIFICATIONS ARE IN EXCESS OF THE REQUIREMENTS OF THE APPLICABLE CODES AND REGULATIONS, AND ARE PERMITTED HEREUNDER THEN, IN SUCH INSTANCES, THE REQUIREMENTS OF THE CONTRACT DOCUMENTS SHALL GOVERN, UNLESS DIRECTED OTHERWISE IN WRITING BY THE ENGINEER.
19. UNLESS OTHERWISE SPECIFIED, NEAT BRASS PLATE, OR OTHERWISE SUITABLE MATERIAL, HAVING THE SERIAL NUMBER, THE MAKE, HORSEPOWER, CAPACITY, SPEED, AND OTHER PERTINENT DATA AND ANY IMPORTANT OPERATING OR MAINTENANCE INSTRUCTIONS PERMANENTLY AND CLEARLY MARKED ON THE PLATE, SHALL BE MOUNTED ON EACH ITEM OF EQUIPMENT. ALL IMPORTANT PARTS OF EQUIPMENT, AS DIRECTED BY ENGINEER/OWNER SHALL BE STAMPED FOR IDENTIFICATION AND LOCATION.
20. ALL NECESSARY ANCHOR BOLTS, NUTS, WASHERS, SETTING TEMPLATES, AND SUCH OTHER PARTS SHALL BE PROVIDED AS REQUIRED FOR THE PROPER INSTALLATION OF THE WORK, AND WHERE PRACTICABLE, THEY SHALL BE BUILT IN AS THE WORK PROGRESSES. THE PARTS SHALL BE OF THE MATERIALS SPECIFIED, AND WHERE NOT SPECIFIED OR INDICATED, THEY SHALL BE OF APPROVED TYPES AND MATERIALS FOR EACH APPLICATION. THE SETTING OF ANCHOR BOLTS BY DRILLING AND GROUTING WILL NOT BE PERMITTED.
21. ALL EQUIPMENT SHALL BE INSTALLED IN STRICT CONFORMANCE WITH THE RECOMMENDATIONS OF THE MANUFACTURER, AS APPROVED. TRULY LEVEL AND PLUMB, AND SHALL BE PROVIDED COMPLETE WITH ALL NECESSARY PIPING, FITTINGS, CONTROLS, WIRING, AND APPURTENANCES AND ACCESSORIES SO THE EQUIPMENT WILL BE LEFT COMPLETE AND IN SATISFACTORY OPERATION. PARTICULAR CARE SHALL BE TAKEN IN THE INSTALLATION OF PUMPS IN ORDER TO PREVENT A STRAIN ON THE PIPING OR PUMP FLANGES AND THE CONTRACTOR SHALL INSURE THE CORRECT ALIGNMENT OF SHAFTS, COUPLINGS, AND BEARINGS.
22. ALL WEDGES, SHIMS, FILLING PIECES, KEYS, PACKING, GROUT, OR OTHER MATERIALS NECESSARY TO PROPERLY ALIGN, LEVEL, AND SECURE APPARATUS IN PLACE SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR. ALL PARTS INTENDED TO BE PLUMB OR LEVEL MUST BE PROVEN EXACTLY SO. ANY GRINDING NECESSARY TO BRING PARTS TO PROPER BEARING AFTER INSTALLATION SHALL BE DONE AT THE EXPENSE OF THE CONTRACTOR.
23. THE CONTRACTOR SHALL PROVIDE ALL OPENINGS, CHANNELS, CHASES, ETC. AS REQUIRED TO COMPLETE THE WORK UNDER THIS CONTRACT, TOGETHER WITH THOSE REQUIRED BY OTHER CONTRACTORS.
24. EXISTING PROCESS SYSTEMS, PIPELINES, EQUIPMENT, AND APPURTENANCES ARE SHOWN ON THESE DRAWINGS FOR REFERENCE ONLY AND WERE OBTAINED FROM THE BEST AVAILABLE SOURCES. THE EXACT LOCATION AND ELEVATION OF THESE ITEMS SHALL BE INVESTIGATED AND FIELD VERIFIED BY THE CONTRACTOR. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER.
25. CONTRACTOR SHALL PROVIDE RESTRAINT OF ALL EXPANSION JOINTS/FLEX CONNECTORS WITH TE-RODS.
26. WHERE CONNECTION OF NEW PIPING SYSTEMS TO EXISTING PIPING SYSTEMS IS REQUIRED, CONTRACTOR SHALL PROVIDE MISCELLANEOUS FITTINGS, FILLER FLANGES, COUPLINGS, ETC. AS MAY BE REQUIRED TO COMPLETE THE WORK, WHETHER SHOWN ON THE DRAWINGS OR NOT. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING PIPING DIMENSIONS.
27. CONTRACTOR SHALL SUBMIT PIPING LAYOUT DIAGRAMS TO THE ENGINEER FOR APPROVAL PRIOR TO ANY PIPING INSTALLATION. PIPING LAYOUT DIAGRAMS SHALL SHOW DIMENSIONS OF ALL VALVES, FITTINGS, PIPE RUNS, AND SUPPORTS.
28. ALL PIPING SYSTEMS AND EQUIPMENT SHALL BE ADEQUATELY AND SAFELY SUPPORTED. CONTRACTOR SHALL DESIGN, PROVIDE, AND INSTALL ALL SUPPORTS AS REQUIRED BY THE PIPING AND EQUIPMENT PROVIDED. AT A MINIMUM, ALL PIPING SYSTEMS SHALL BE SUPPORTED PER THE REQUIREMENTS OF MANUFACTURER'S STANDARDIZATION SOCIETY (MSS) SP-58 AND MSS SP-69. SUPPORT DESIGN SHALL ACCOMMODATE ALL STATIC AND OPERATIONAL CONDITIONS TO WHICH THE PIPING AND EQUIPMENT MAY BE SUBJECTED. SUPPORTS SHALL BE IN ADDITION TO THOSE SHOWN ON THE CONTRACT DRAWINGS.

**MECHANICAL PROCESS LEGEND**

**VALVES, COUPLING, & APPURTENANCES**

	BURIED GATE VALVE		REDUCER/INGREASER
	BURIED PLUG VALVE		STRAINER
	BALL VALVE		UNION
	BUTTERFLY VALVE		FLEXIBLE HOSE
	ELECTRIC ACTUATED BUTTERFLY VALVE		CENTRIFUGAL PUMP
	BALL CHECK VALVE		DIAPHRAGM METERING PUMP
	SWING CHECK VALVE		ROTAMETER
	WAFER CHECK VALVE		DIAPHRAGM ISOLATOR (GAUGE GUARD)
	GATE VALVE		CALIBRATION COLUMN
	DIAPHRAGM VALVE		VENT
	PINCH VALVE		VENT
	PLUG VALVE		4 FUNCTION VALVE
	MUD VALVE		ELECTOR
	NEEDLE VALVE		DRAIN
	SOLENOID VALVE		FLEX COUPLING (CHEMICAL SERVICE)
	SLEEVE TYPE COUPLING		FLOAT SWITCH
	SPLIT SLEEVE ADAPTER		ULTRASONIC LEVEL SENSOR
	FLANGED COUPLING ADAPTER		SUBMERSIBLE CENTRIFUGAL PUMP
	EXPANSION JOINT (METAL)		AIR FILTER/INSECT SCREEN
	EXPANSION JOINT (RUBBER)		ELECTRIC DIAPHRAGM METERING PUMP
	QUICK CONNECT		BASKET STRAINER
	MAGMETER		QUICK DISCONNECT MALE ADAPTER
	TURBINE FLOWMETER		HOSE COUPLING
	PRESSURE REDUCING VALVE		EXPANSION JOINT
	VACUUM BREAKER		CAST-IN-PLACE WALL PIPE
	BACK PRESSURE/ANTISIPHON VALVE		
	RELIEF VALVE		
	COMBINATION VALVE		
	PRESSURE INDICATOR (LIQUID SERVICE)		
	PRESSURE INDICATING TRANSMITTER (LIQUID SERVICE)		
	PRESSURE INDICATOR (AIR SERVICE)		
	FLOW SWITCH		
	PRESSURE SWITCH		
	ANTI-SIPHON VALVE		
	TEMPERATURE INDICATOR		
	SAMPLE TAP		
	PRESSURE DIFFERENTIAL SWITCH		
	QUICK DISCONNECT FEMALE COUPLER		

**PROCESS STREAM ABBREVIATIONS**

BW	BACKWASH
FE	FILTER EFFLUENT
FI	FILTER INFLUENT
NOCl	SODIUM HYPOCHLORITE


**PIPING AND TUBING MATERIALS**

CI	CAST IRON PIPE
CPVC	CHLORINATED POLYVINYL CHLORIDE PIPE
CS	CARBON STEEL
CU	COPPER
DI	DUCTILE IRON PIPE
FRP	FIBERGLASS REINFORCED PLASTIC PIPE
GALV	GALVANIZED STEEL
HDPE	HIGH DENSITY POLYETHYLENE
HOSE	FLEXIBLE HOSE
PE	POLYETHYLENE
PVC	POLYVINYL CHLORIDE
RCP	REINFORCED CONCRETE PIPE
SS	STAINLESS STEEL PIPE OR TUBING
STL	STEEL

**REVISIONS**

NO.	DATE	DESCRIPTION

SCALE ADJUSTMENT GUIDE  
 0 = FIVE INCH  
 1" = ORIGINAL DRAWING



PROJECT NO.:	1192101
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	SCO
CHECKED BY:	SCO
DRAWN BY:	LNG
APPROVED BY:	LNG

**WATER SYSTEM CHLORINATION & PRETREATMENT PRUDENCE ISLAND WATER DISTRICT PRUDENCE ISLAND, RHODE ISLAND**

DRAWING TITLE:  
**PLANT MECHANICAL NOTES AND LEGEND**

DRAWING NO.:  
**M-1**  
 SHEET NO. 14 OF 26

FOR PERMITTING

# PROCESS VALVE SCHEDULE

Mechanical Tag No.	Size	Type	Description	Location	Application	Service	Valve Position	Valve Operator
CV-201A	1-1/2"	BUTTERFLY VALVE	FILTER #1 INFLUENT	FILTER VALVE SKID	WATER	OPEN/CLOSE	OPEN FOR ONLINE, CLOSED FOR OFFLINE	MOTOR
CV-201B	1-1/2"	BUTTERFLY VALVE	FILTER #1 INFLUENT	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
CV-201C	1-1/2"	BUTTERFLY VALVE	FILTER #2 INFLUENT	FILTER VALVE SKID	WATER	OPEN/CLOSE	OPEN FOR ONLINE, CLOSED FOR OFFLINE	MOTOR
CV-201D	1-1/2"	BUTTERFLY VALVE	FILTER #2 INFLUENT	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
CV-202A	1-1/2"	BUTTERFLY VALVE	FILTER #1 EFFLUENT	FILTER VALVE SKID	WATER	OPEN/CLOSE	OPEN FOR ONLINE, CLOSED FOR OFFLINE	MOTOR
CV-202B	1-1/2"	BUTTERFLY VALVE	FILTER #1 EFFLUENT	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
CV-202C	1-1/2"	BUTTERFLY VALVE	FILTER #2 EFFLUENT	FILTER VALVE SKID	WATER	OPEN/CLOSE	OPEN FOR ONLINE, CLOSED FOR OFFLINE	MOTOR
CV-202D	1-1/2"	BUTTERFLY VALVE	FILTER #2 EFFLUENT	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
CV-203A	2-1/2"	BUTTERFLY VALVE	FILTER #1 BACKWASH INLET	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	MOTOR
CV-203B	2-1/2"	BUTTERFLY VALVE	FILTER #2 BACKWASH INLET	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	MOTOR
CV-204A	1"	BUTTERFLY VALVE	FILTER #1 BACKWASH OUTLET	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	MOTOR
CV-204B	1"	BUTTERFLY VALVE	FILTER #2 BACKWASH OUTLET	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	MOTOR
CV-205A	1"	BUTTERFLY VALVE	FILTER #1 RINSE VALVE	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	MOTOR
CV-205B	1"	BUTTERFLY VALVE	FILTER #2 RINSE VALVE	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	MOTOR
AV-207A	1"	AIR RELEASE	FILTER #1	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	-
AV-207B	1"	AIR RELEASE	FILTER #2	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	-
MV-207A	1"	BALL VALVE	ARV ISOLATION	FILTER #1	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
MV-207B	1"	BALL VALVE	ARV ISOLATION	FILTER #2	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
MV-209A	1"	BALL VALVE	WASTEWATER #1	FILTER VALVE SKID	DRAIN	OPEN/CLOSE	NORMALLY CLOSED	HANDLE
MV-209B	1"	BALL VALVE	WASTEWATER #2	FILTER VALVE SKID	DRAIN	OPEN/CLOSE	NORMALLY CLOSED	HANDLE
CV-201	2"	BUTTERFLY VALVE	BACKWASH TANK FILL	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	MOTOR
CV-202	2"	BUTTERFLY VALVE	BACKWASH TANK FILL	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	MOTOR
MV-202	2"	BALL VALVE	BACKWASH TANK FILL	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
MV-203	1-1/2"	BALL VALVE	BACKWASH PUMP SUCTION	BACKWASH SUPPLY	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
MV-204	1-1/4"	BALL VALVE	BACKWASH PUMP DISCHARGE	BACKWASH SUPPLY	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
MV-205	2"	BALL VALVE	TREATMENT SKID BYPASS	BYPASS	WATER	OPEN/CLOSE	NORMALLY CLOSED	HANDLE
MV-206	2"	BALL VALVE	TREATMENT SKID BYPASS	BYPASS	WATER	OPEN/CLOSE	NORMALLY CLOSED	HANDLE
CV-401	2"	BUTTERFLY VALVE	FILTER EFFLUENT HEADER	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	MOTOR
MV-401	2"	BALL VALVE	FILTER EFFLUENT HEADER	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
MV-201A	1/4"	BALL VALVE	FILTER #1 INFLUENT	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
MV-201B	1/4"	BALL VALVE	FILTER #2 INFLUENT	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
MV-202A	1-1/2"	BALL VALVE	FILTER #1 EFFLUENT	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	HANDLE
MV-202B	1-1/2"	BALL VALVE	FILTER #2 EFFLUENT	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	HANDLE
MV-203A	1/2"	BALL VALVE	FILTER #1	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	HANDLE
MV-203B	1/2"	BALL VALVE	FILTER #2	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	HANDLE
MV-204A	1/4"	BALL VALVE	FILTER #1	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
MV-204B	1/4"	BALL VALVE	FILTER #2	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
MV-205A	1/4"	BALL VALVE	FILTER #1	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	HANDLE
MV-205B	1/4"	BALL VALVE	FILTER #2	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	HANDLE
MV-206A	1/4"	BALL VALVE	FILTER #1	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
MV-206B	1/4"	BALL VALVE	FILTER #2	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
MV-207A	1/4"	BALL VALVE	FILTER #1	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	HANDLE
MV-207B	1/4"	BALL VALVE	FILTER #2	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY CLOSED	HANDLE
MV-208A	1/4"	BALL VALVE	FILTER #1	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
MV-208B	1/4"	BALL VALVE	FILTER #2	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
MV-209A	1/4"	BALL VALVE	FILTER #1	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE
MV-209B	1/4"	BALL VALVE	FILTER #2	FILTER VALVE SKID	WATER	OPEN/CLOSE	NORMALLY OPEN	HANDLE

# PUMP SCHEDULE

EQUIPMENT ID	PAID TAG NO.	EQUIPMENT DESCRIPTION	LOCATION	TYPE	RATING POINTS	DRIVE	MOTOR		VOLTAGE			REMARKS	
							HP	RPM	ENCL	VAC	HZ	PH	
P-301	BWP-301	BACKWASH SUPPLY PUMP	INDIAN SPRINGS TREATMENT PLANT	CENTRIFUGAL	65 GPM @ 40 FT TDH	CONSTANT	1.5	1200	ODP	460	60	3	ELECTRICAL 3-PHONG TWIST-LOCK PLUG CONNECTION
P-302	ISMP-501	METERING PUMP	INDIAN SPRINGS WELL HOUSE	PERISTALTIC	0.0002 - 33.3 GPH @ 125 PSI	VARIABLE	3.5	AMPS (MAX)		120	60	1	ELECTRICAL 3-PHONG TWIST-LOCK PLUG CONNECTION
P-303	ISMP-502	METERING PUMP	INDIAN SPRINGS WELL HOUSE	PERISTALTIC	0.0002 - 33.3 GPH @ 125 PSI	VARIABLE	3.5	AMPS (MAX)		120	60	1	ELECTRICAL 3-PHONG TWIST-LOCK PLUG CONNECTION
P-304	ACMP-503	METERING PUMP	ARMY CAMP WELL HOUSE	PERISTALTIC	0.0002 - 33.3 GPH @ 125 PSI	VARIABLE	3.5	AMPS (MAX)		120	60	1	ELECTRICAL 3-PHONG TWIST-LOCK PLUG CONNECTION
P-305	ACMP-504	METERING PUMP	ARMY CAMP WELL HOUSE	PERISTALTIC	0.0002 - 33.3 GPH @ 125 PSI	VARIABLE	3.5	AMPS (MAX)		120	60	1	ELECTRICAL 3-PHONG TWIST-LOCK PLUG CONNECTION

# FLOW ELEMENT SCHEDULE

EQUIPMENT ID	PAID TAG NO.	EQUIPMENT DESCRIPTION	LOCATION	TYPE	Size	Flow Range	VAC	VOLTAGE		PH	REMARKS
								Hz			
MAG-1	FE-101	RAW WATER FLOW METER	INDIAN SPRINGS WELL HOUSE	MAG	2"	5 - 100 GPM	110	6		1	
MAG-2	FE-201A	FILTER NO. 1 INFLUENT	INDIAN SPRINGS TREATMENT PLANT	MAG	2"	5 - 100 GPM	110	6		1	
MAG-3	FE-201B	FILTER NO. 2 INFLUENT	INDIAN SPRINGS TREATMENT PLANT	MAG	2"	5 - 100 GPM	110	6		1	

FOR PERMITTING



SCALE ADJUSTMENT GUIDE  
0 = 1/8" = 1" ORIGINAL DRAWING

NO.	DATE	DESCRIPTION



PROJECT NO.: 119.21.01  
DATE: DECEMBER 2021  
SCALE: AS NOTED  
DESIGNED BY: SCO  
CHECKED BY: SCO  
DRAWN BY: LMG  
APPROVED BY: LMG

**WATER SYSTEM CHLORINATION & PRETREATMENT**  
PRUDENCE ISLAND WATER DISTRICT  
PRUDENCE ISLAND, RHODE ISLAND

DRAWING TITLE: MECHANICAL SCHEDULES  
DRAWING NO.: M-2  
SHEET NO. 15 OF 26



**H2Olson Engineering, Inc.**  
DRINKING WATER PROFESSIONALS  
www.h2olsonengineering.com  
(800) 575-0807

SCALE ADJUSTMENT GUIDE  
0 = BAR IS ONE INCH ON ORIGINAL DRAWING  
1" = ORIGINAL DRAWING

REVISIONS		
NO.	DATE	DESCRIPTION

LISA GOYER  
No. 11536  
REGISTERED PROFESSIONAL ENGINEER  
CIVIL

PROJECT NO.:	119 21 01
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	SCO
CHECKED BY:	SCO
DRAWN BY:	LMG
APPROVED BY:	LMG


**WATER SYSTEM CHLORINATION & PRETREATMENT**  
PRUDENCE ISLAND WATER DISTRICT  
PRUDENCE ISLAND, RHODE ISLAND

DRAWING TITLE:  
**MECHANICAL PROCESS PIPING PLAN**


DRAWING NO.:  
**M-3**  
SHEET NO. 16 OF 26

FOR PERMITTING


**FLOOR PLAN**  
SCALE: 1/2" = 1'



**SECTION**  
SCALE: 1" = 1'



**SECTION**  
SCALE: 1" = 1'




5'-3\"/>



**H2Olson Engineering, Inc.**  
 DRINKING WATER PROFESSIONALS  
 www.h2olsonengineering.com  
 (800) 375-0607

SCALE ADJUSTMENT GUIDE  
 0" = 1" INCH  
 ORIGINAL DRAWING

REVISIONS	
NO.	DESCRIPTION




PROJECT NO.:	119.21.01
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	SCO
CHECKED BY:	SCO
DRAWN BY:	LMG
APPROVED BY:	LMG

**WATER SYSTEM CHLORINATION & PRETREATMENT**  
 PRUDENCE ISLAND WATER DISTRICT  
 PRUDENCE ISLAND, RHODE ISLAND





DRAWING TITLE:  
**MECHANICAL PROCESS PIPING SECTIONS**

DRAWING NO.:  
**M-4**  
 SHEET NO. 17 OF 26

FOR PERMITTING



**SECTION**  
 SCALE: 1" = 1'  
 C  
 M-3



NOTE:  
1. CHLORINE SYSTEM SCHEMATIC IS FOR BOTH INDIAN SPRINGS AND ARMY CAMP.

REVISIONS

NO.	DATE	DESCRIPTION

SCALE ADJUSTMENT GUIDE  
0 1"  
BAR IS ONE INCH ON ORIGINAL DRAWING

**H2Olson Engineering, Inc.**  
DRINKING WATER PROFESSIONALS  
www.h2olsonengineering.com  
(888) 375-0807

LISA GOYER  
No. 11596  
REGISTERED PROFESSIONAL ENGINEER  
STATE OF RHODE ISLAND

PROJECT NO.: 1192101  
DATE: DECEMBER 2021  
SCALE: AS NOTED  
DESIGNED BY: SCO  
CHECKED BY: SCO  
DRAWN BY: RAT  
APPROVED BY: LMG

**WATER SYSTEM CHLORINATION & PRETREATMENT**  
PRUDENCE ISLAND WATER DISTRICT  
PRUDENCE ISLAND, RHODE ISLAND

DRAWING TITLE:  
**WELL HOUSE CHEMICAL FEED SYSTEMS**

DRAWING NO.: **M-5**  
SHEET NO. 18 OF 26

FOR PERMITTING


NO.	DATE	DESCRIPTION	REVISIONS

PROJECT NO.:	119.21.01
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	SCO
CHECKED BY:	SCO
DRAWN BY:	RAT
APPROVED BY:	LMG

**WATER SYSTEM CHLORINATION & PRETREATMENT  
 PRUDENCE ISLAND WATER DISTRICT  
 PRUDENCE ISLAND, RHODE ISLAND**

**BACKWASH TANK ULTRASONIC LEVEL DETAIL**

SCALE: N.T.S.




NOTES:

1. ELECTRICAL CONTRACTOR TO SUPPLY AND INSTALL ALL DIVISION 16 DEVICES, EQUIPMENT, COMPONENTS, AND ANCILLARY ITEMS ASSOCIATED WITH POWER AND SIGNAL WIRING FOR I&C DEVICES.
2. THE MOUNTING DETAILS PROVIDED ARE GENERIC FOR ULTRASONIC DEVICES OF VARIOUS MANUFACTURERS. THE INSTALLING CONTRACTOR MUST STRICTLY COMPLY WITH MANUFACTURER'S INSTRUCTION IN THE INSTALLATION OF THESE DEVICES. IF THERE ARE ANY ENGINEERING ISSUES THEY MUST BE REFERRED TO THE ENGINEER PRIOR TO INSTALLATION.

**PRESSURE TRANSMITTER MOUNTING DETAIL  
 TRANSMITTER AND SAMPLE TAP**

SCALE: N.T.S.




NOTES:

1. ELECTRICAL CONTRACTOR TO SUPPLY AND INSTALL ALL DIVISION 16 DEVICES, EQUIPMENT, COMPONENTS, AND ANCILLARY ITEMS ASSOCIATED WITH POWER AND SIGNAL WIRING FOR I&C DEVICES.
2. THE MOUNTING DETAILS PROVIDED ARE GENERIC FOR LEVEL SWITCH DEVICES OF VARIOUS MANUFACTURERS. THE INSTALLING CONTRACTOR MUST STRICTLY COMPLY WITH MANUFACTURER'S INSTRUCTION IN THE INSTALLATION OF THESE DEVICES. IF THERE ARE ANY ENGINEERING ISSUES THEY MUST BE REFERRED TO THE ENGINEER PRIOR TO INSTALLATION.

**BACKWASH TANK FLOAT SWITCH DETAIL**

SCALE: N.T.S.




1. SIZES SHOWN ARE FOR DUCTILE IRON PIPE, FOR OTHER MATERIALS AND PIPE SIZES CONSULT MANUFACTURER'S SPECIFICATIONS.
2. FILL ANNULAR SPACE WITH GROUT.

CARRIER PIPE NOMINAL SIZE	CARRIER PIPE O.D.	SLEEVE DRILLED SIZE	CORE DRILLED I.D.
1 1/2"	1.625"	3"	3"
2"	2.50"	4"	4"
4"	4.80"	8"	8"
6"	6.90"	10"	10"
8"	9.05"	12"	12"
16"	17.40"	20"	20"
18"	19.50"	24"	24"
24"	25.80"	30"	29"

NOTES:


**TYPICAL PIPE SLAB PENETRATION DETAIL**

SCALE: N.T.S.



**CHEMICAL FEED TEE DETAIL**

SCALE: N.T.S.



FOR PERMITTING









Kurt Kuegler, P.E.  
198 Cullen Street  
Watertown, CT  
06795  
203-233-1583


SCALE ADJUSTMENT GUIDE  
1" = 1/8" OR 1/4" INCHES  
OR  
ORIGINAL DRAWING

Table with columns: PANELBOARD, SERVICE, PANELBOARD CONFIGURATION, MAIN, BRANCH CIRCUITS. Includes details like Class: LIGHTING, Type: GE, Type AE, and various load specifications.


Table with columns: PANELBOARD, SERVICE, PANELBOARD CONFIGURATION, MAIN, BRANCH CIRCUITS. Includes details like Class: LIGHTING, Type: GE, Type AO, and various load specifications.

Table with columns: TYPE, DESCRIPTION, MANUFACTURER/CATALOG NO, LUMENS NOMINAL, WATTS, TYPE, COLOR TEMP, CRI, OPERATING VOLTS, INSTALLATION & MOUNTING. Lists lighting fixtures like '4 FT LED ENCLOSED AND SILICON GASKETED POLYCARBONATE HOUSING'.

FOR REMITTING




STEP DOWN TRANSFORMER CONNECTION DIAGRAM



ELECTRICAL ONE-LINE


- ONE-LINE NOTES: 1) SEE POWER AND CONTROL INTERCONNECTION SCHEDULES AND WORK ITEMS... 2) NOT ALL REQUIRED JUNCTION OR PULL BOXES... 3) SEE OTHER DRAWINGS FOR LOCATIONS AND SCHEDULE INFORMATION...




WATER SYSTEM CHLORINATION & PRETREATMENT  
PRUDENCE ISLAND WATER DISTRICT  
PRUDENCE ISLAND, RHODE ISLAND

DRAWING TITLE:  
ELECTRICAL POWER SCHEDULES  
E-2  
SHEET NO. 22 OF 26


INDIAN SPRINGS WELL HOUSE



INDIAN SPRINGS WATER TREATMENT PLANT




EXISTING ARMY CAMP RTU



ALARM AND INTERLOCK SCHEDULE

DEVICE	EVENT	INTERLOCK #	ALARM	SET POINT	RANGE	DELAY	ACTION
AIT-401 & AIT-402	HH/CHLORINE	1	YES	2	0 TO 4.0	0-300 S	STOP CHLORINE FEED PUMPS; STOP WELL PUMPS
AIT-401 & AIT-402	HI CHLORINE	N/A	YES	1.5	0 TO 4.0	0-300 S	ANNUNCIATE ON APPLICABLE OIT
AIT-401 & AIT-402	LO CHLORINE	N/A	YES	0.5	0 TO 4.0	0-300 S	ANNUNCIATE ON APPLICABLE OIT
AIT-401 & AIT-402	LO-LO CHLORINE	2	YES	0.25	0 TO 4.0	0-300 S	STOP CHLORINE FEED PUMPS; STOP WELL PUMPS
PIT-101	HI PRESSURE, IS	N/A	YES	85	0 TO 150	0-300 S	ANNUNCIATE ON APPLICABLE OIT
PIT-101	LO PRESSURE, IS	N/A	YES	55	0 TO 150	0-300 S	ANNUNCIATE ON APPLICABLE OIT
PIT-401	HI PRESSURE, IS	N/A	YES	75	0 TO 150	0-300 S	ANNUNCIATE ON APPLICABLE OIT
PIT-401	LO PRESSURE, IS	N/A	YES	50	0 TO 150	0-300 S	ANNUNCIATE ON APPLICABLE OIT
FTI-101	HI FLOW, IS	N/A	YES	50	0 TO 100	0-300 S	ANNUNCIATE ON APPLICABLE OIT
IS-P1, IS-P4, AC-P1	WELL PUMP OFF/ON	3	NO	N/A	N/A	N/A	WELL PUMPS ON/OFF = POWER TO CHLORINE PUMPS ON/OFF
LIT-301	HH/HL Level	4	YES	7	0 TO 10	0-300 S	CLOSE CV-301; CLOSE CV-202
LSH-301	HI/HL Level	5	YES	7	N/A	N/A	CLOSE CV-301; CLOSE CV-202
LIT-301	HI Level	N/A	YES	6	0 TO 10	0-300 S	ANNUNCIATE ON APPLICABLE OIT
LIT-301	LO Level	N/A	YES	2	0 TO 10	0-300 S	ANNUNCIATE ON APPLICABLE OIT
LSL-301	LO-LO Level	6	YES	1	N/A	N/A	STOP BACKWASH PUMP P-301
LIT-301	LO-LO Level	7	YES	1	0 TO 10	0-300 S	STOP BACKWASH PUMP P-301
DPT-201A	HI DIFFERENTIAL PRESSURE	N/A	YES	7	0 TO 20	0-300 S	ANNUNCIATE ON APPLICABLE OIT
DPT-201B	HI DIFFERENTIAL PRESSURE	N/A	YES	7	0 TO 20	0-300 S	ANNUNCIATE ON APPLICABLE OIT
WIT-501	LO Weight	N/A	YES	20	1 TO 100	0-300 S	ANNUNCIATE ON APPLICABLE OIT
WIT-502	LO Weight	N/A	YES	20	0 TO 100	0-300 S	ANNUNCIATE ON APPLICABLE OIT

LEGEND



PROCESS STREAM REFER TO SHEET X  
REFER TO SHEET M-1 FOR ADDITIONAL SYMBOLS

ISA INSTRUMENT IDENTIFICATION TABLE

MEASURED OR INITIATING VARIABLE	FIRST LETTER MEAS. VARI.	SWITCH (HI, LO, OPEN, CLOSE)	PRIM. ELEM. (SENSOR)	INDICATOR	INDICATING CONTROLLER	CONTROL OR CONTR. (BLND)	RECORDER	INTEGRATOR (TOTALIZER)	TRANSMITTER (INDICTING)	TRANSMITTER	VALVE OR ACTUATOR	RELAY	SOURCE
ANALYSIS	A	ASL	AE	AI			AR		AIT	AT		AV	
BURNER, COMBUSTION	B		BE			BC						BY	
CONDUCTIVITY	C	GSH	CE	CI	CC	CC	CR		CIT	CT		CY	DX
DENSITY	D	DSH	DE	DI	DC	DC	DR		DIT	DT		DY	DX
VOLTAGE	E		EE	EI					EIT	ET		EY	
FLOW RATE	F	FSHL	FE	FI	FC	FC	FR	FQ	FIT	FT	FV	FV	
USER'S CHOICE	G												
HAND	H	HS											
CURRENT (ELECTRICAL)	I	IS	IE	II	IIC	IC			IT			IV	
POWER	J	JSH	JE	JI	JIC	JC	JR	JQ				JY	
TIME, TIME SCHEDULE	K			KI	KIC	KC		KQ				KY	KS
LEVEL	L	LSH	LE	LI	LIC	LC	LR		LIT	LT	LV	LY	
HUMIDITY	M		ME	MI	MC	MC	MIR		MIT	MT		MY	
USER'S CHOICE	N												
USER'S CHOICE	O												
PRESSURE, VACUUM	P	PSH	PE	PI	PIC	PC	PR		PIT	PT	PV	PV	
QUANTITY	Q												
RADIATION	R												
SPEED, FREQUENCY	S	SSL	SE	SI	SC	SC			SIT	ST		SY	
TEMPERATURE	T	TSL	TE	TI	TIC	TC	TR		TIT	TT	TV	TY	
MULTI-VARIABLE	U			UI			UR					UY	
MECHANICAL ANALYSIS	V												
WEIGHT, FORCE	W	WS	WE	WI	WIC		WR		WIT	WT			
VIBRATION	X		XE	XI			XR		YIT	YT		YY	
EVENT	Y	YS		YI					YIT	YT		YY	
POSITION, DIMENSION	Z	ZSO	ZE	ZI			ZR		ZIT	ZT		ZY	

PROCESS AND INSTRUMENTATION

PROCESS AND INSTRUMENTATION	PROCESS AND INSTRUMENTATION	PROCESS AND INSTRUMENTATION	PROCESS AND INSTRUMENTATION	PROCESS AND INSTRUMENTATION	PROCESS AND INSTRUMENTATION	PROCESS AND INSTRUMENTATION	PROCESS AND INSTRUMENTATION	PROCESS AND INSTRUMENTATION	PROCESS AND INSTRUMENTATION	PROCESS AND INSTRUMENTATION	PROCESS AND INSTRUMENTATION	PROCESS AND INSTRUMENTATION	PROCESS AND INSTRUMENTATION
A/L/L	AUTO/LEAD/LAG	N/A	NORMAL/ALARM	SP	SET POSITION								
DPT	DIFFERENTIAL PRESSURE INDICATOR TRANSMITTER	O/C	OPEN/CLOSE OR OPEN/CLOSED	S/S	START/STOP								
EFF	EFFLUENT	O/C/A	OPEN/CLOSE/AUTOMATIC	YL	EVENT ALARM LOW								
F	FAULT	O/O	ON/OFF	YLL	EVENT ALARM LOW LOW								
FOP	FIELD CONTROL PANEL	O/O/R	ON/OFF/RESET	YH	EVENT ALARM HIGH								
FCV	FLOW CONTROL VALVE	O/S/C	OPEN/STOP/CLOSE	YHH	EVENT ALARM HIGH HIGH								
F/R	FORWARD/REVERSE	O/S/C/A	OPEN/STOP/CLOSE/AUTOMATIC	YNF	EVENT NO FLOW								
FS	FLOW SWITCH	PIC	PANEL INTERFACE CONNECTOR	YF	EVENT FAIL								
H/A	HAND/AUTOMATIC	PLC	PROGRAMMABLE LOGIC CONTROLLER	YM	EVENT IN MANUAL								
H/O/A	HAND/OFF/AUTOMATIC	POS	POSITION	YS	EVENT STATUS								
INF	INFLUENT	RS	RUN STATUS										
L/R	LOCAL/REMOTE	RSL	REMOTE/STOP/LOCAL										
L/R/O	LOCAL/REMOTE/OFF	SA	SAMPLE PORT										
MCP	MAIN CONTROL PANEL	SA	SPEED ADJUST										

FOR PERMITTING

SCALE ADJUSTMENT GUIDE  
BARS IS ONE INCH ON ORIGINAL DRAWING

NO.	DATE	DESCRIPTION

PROJECT NO.:	119 21 01
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	SCD
CHECKED BY:	SCD
DRAWN BY:	RAJ
APPROVED BY:	LMG

WATER SYSTEM CHLORINATION & PRETREATMENT  
PRUDENCE ISLAND WATER DISTRICT  
PRUDENCE ISLAND, RHODE ISLAND


DRAWING TITLE: SCADA SYSTEM SCHEMATIC

DRAWING NO.: I-1


SHEET NO. 23 OF 26

INDIAN SPRINGS WELL HOUSE

EXISTING INDIAN SPRINGS WELL HOUSE




INDIAN SPRINGS RTU



NOTES:

- POWER SUPPLY FOR THE CHEMICAL FEED PUMPS SHALL BE NEW DUPLEX OUTLET. OUTLET IS TO BE ELECTRICALLY INTERLOCKED WITH THE WELL PUMPS. REFER TO ELECTRICAL SHEETS FOR DETAILS AND SHEET I-1 FOR OTHER INTERLOCKS.



FOR PERMITTING

REVISIONS	
NO.	DATE



PROJECT NO.:	1192101
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	SCO
CHECKED BY:	SCO
DRAWN BY:	RAT
APPROVED BY:	LMG

**WATER SYSTEM CHLORINATION & PRETREATMENT**  
PRUDENCE ISLAND WATER DISTRICT  
PRUDENCE ISLAND, RHODE ISLAND


DRAWING TITLE:  
INDIAN SPRINGS  
CHLORINATION

DRAWING NO.:  
I-2  
SHEET NO. 24 OF 26



SCALE ADJUSTMENT GUIDE  
0  
1  
ORIGINAL DRAWING

# INDIAN SPRINGS WATER TREATMENT PLANT INDIAN SPRINGS FILTER CONTROL PANEL



FOR PERMITTING

**H2Olson Engineering, Inc.**  
DRINKING WATER PROFESSIONALS  
www.h2olsonengineering.com  
(308) 375-7007

SCALE ADJUSTMENT GUIDE  
OR  
BAR IS ONE INCH  
ORIGINAL DRAWING

NO.	DATE	DESCRIPTION



PROJECT NO.:	119 21 01
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	SCO
CHECKED BY:	SCO
DRAWN BY:	RAJ
APPROVED BY:	LMG


**WATER SYSTEM CHLORINATION  
& PRETREATMENT**  
PRUDENCE ISLAND WATER DISTRICT  
PRUDENCE ISLAND, RHODE ISLAND

DRAWING TITLE:  
**TREATMENT PLANT  
INSTRUMENTATION**

DRAWING NO.:  
**1-3**  
SHEET NO. 25 OF 28

ARMY CAMP WELL HOUSE

ARMY CAMP RTU



NOTES:

- 1) POWER SUPPLY FOR THE CHEMICAL FEED PUMPS SHALL BE NEW DUPLEX POWER PLETS TO BE ELECTRICAL INTERLOCKED WITH THE WELL PUMP. REFER TO ELECTRICAL SHEETS FOR DETAILS AND SHEET I-1 FOR OTHER INTERLOCKS

FOR PERMITTING

**H2Olson Engineering, Inc.**  
DRINKING WATER PROFESSIONALS  
www.h2olsonengineering.com  
(800) 375-0807

SCALE ADJUSTMENT GUIDE  
OR  
BAR IS ONE INCH ON ORIGINAL DRAWING

NO.	DATE	REVISIONS	DESCRIPTION



PROJECT NO.:	119 21 01
DATE:	DECEMBER 2021
SCALE:	AS NOTED
DESIGNED BY:	SCO
CHECKED BY:	SCO
DRAWN BY:	RAT
APPROVED BY:	LMG

**WATER SYSTEM CHLORINATION & PRETREATMENT**  
PRUDENCE ISLAND WATER DISTRICT  
PRUDENCE ISLAND, RHODE ISLAND

DRAWING TITLE:  
**ARMY CAMP CHLORINATION**

DRAWING NO.:  
**1-4**  
SHEET NO. 26 OF 26



## **Attachment C**

# **Treatment Design Technical Memorandum**

DRAFT






**To:** Robin Weber, Board Moderator  
Prudence Island Water District

**From:** Lisa M. Goyer, P.E.  
Stephen C. Olson, P.E.

**Cc:**

**Date:** December 30, 2021

**Subject:** Prudence Island Water District  
Public Water System Chlorination and Pre-treatment Design



---

## INTRODUCTION AND BACKGROUND

The Prudence Island Water District (PIWD) is under an Administrative Consent Order (ACO) with the Rhode Island Department of Health (RIDOH) to install permanent disinfection facilities for their two water supply sources, including pre-treatment for the removal of iron and manganese at the Indian Springs well site. PIWD retained the services of H2Olson Engineering, Inc. (H2Olson) to complete the design and permitting of these facilities in accordance the RIDOH ACO requirements. As such, H2Olson has completed the design and prepared plans and specifications suitable for bidding and construction of the proposed disinfection and pre-treatment facilities.

Presented herein are engineering design calculations and studies required by the ACO including the following:

1. Facility description and design capacity of the proposed disinfection facilities and iron and manganese treatment facilities for the Indian Springs water supply sources.
2. CT calculations for the proposed PIWD disinfection facilities to achieve 4-log inactivation of viruses under the Groundwater Rule.
3. A Disinfection By-Product formation study based on the proposed use of chlorine for disinfection at the PIWD water supply sites.
4. A Corrosion Control Study to assess the proposed use of chlorine for disinfection while maintaining simultaneous compliance with the Lead and Copper Rule (and recent revisions).

## FACILITY DESCRIPTION

The PIWD water supply system currently consists of two active groundwater well sites: Army Camp and Indian Springs. The Army Camp site consists of one groundwater supply well while the Indian Springs site consists of two groundwater supply wells: Well # 1 and Well #2.

As previously noted, two treatment systems are being proposed:

1. Disinfection and iron and manganese facilities at the Indian Springs well site.
2. Disinfection facilities at the Army Camp well site.

H2Olson has reviewed numerous existing available engineering reports including, but not limited to: Prudence Island Utility Corporation Water System Master Plan, 1998; Preliminary Engineering Report, Prudence Island Water District, Treatment Facility, 2006; Engineering Evaluation and Facility Capital Improvement Plan, Prudence Island Water District, 2012; and Draft Preliminary Engineering Report, Prudence Island Water District, Various Water System Projects, 2013. The following treatment technologies for the removal of iron and manganese at the Indian Springs well site were reviewed and discussed to varying degrees within the above noted reports: water softening (ion exchange); greensand media filtration; granular activated carbon (GAC) media filtration; membrane filtration; and, vacuum diatomaceous earth filtration. Based on a review and evaluation of the previously completed alternative treatment assessments, the use and application of greensand media filtration for the Indian Springs well site is recommended. This technology will only require the application of chlorine for oxidation and effective treatment performance. This is an efficient and effective approach since the addition of chlorine is already required for disinfection to achieve 4-log inactivation of viruses to meet the requirements of the Groundwater Rule.

A summary of proposed engineering design parameters, including target chemical dosages, for the Indian Springs treatment facilities are presented in Table 1. The proposed treatment system includes converting the existing well house to a chlorine addition facility which will be used for storing and dosing chlorine. The use of commercial strength sodium hypochlorite (12.5% strength) is proposed. This product can be purchased in 5-gallon pails (carboys). The proposed chlorination facility consists of two (2) chlorine pumps, a carboy scale, and a containment pallet suitable to store up to six (6) 5-gallon pails. Chlorine will be pumped directly out of a 5-gallon pail and injected downstream of the existing flow meter. Several hundred feet of the existing 4-inch water main will need to be replaced with 8-inch diameter ductile iron water main in order to provide sufficient contact time (CT) for 4-log inactivation of viruses.

A 2-filter greensand filtration system is proposed for iron and manganese treatment. The system is completely pre-engineered and assembled on a skid. A previously completed hydraulic evaluation indicated that the existing well pumps have sufficient head to pump through the filters with sufficient head to pump into the system's 100,000 gallon storage tank (Big Blue). The system will operate with 1 filter online (the second on stand-by), with an anticipated run-time between 24 and 72 hours. When the on-line filter requires cleaning, it will be taken off-line and the 2<sup>nd</sup> filter that is on stand-by will be placed in service. The off-line filter will then be backwashed and placed on stand-by until needed. A dedicated 1,500 gallon washwater supply tank and backwash pump

will provide the means for backwashing each filter. The backwash sequence will also include a rinsing sequence. Residuals from backwashing the filters will be directed to a 2,000 gallon holding tank and infiltration system. Settled solids from filter backwashing will be removed via a vacuum pump every 6 to 12 months, or as needed, to remove the accumulated solids in the holding tank.

**Table 1**  
**Indian Spring Treatment Facility**  
**Conceptual Design Summary**

<i>Hydraulic Design Capacity</i>	35 gpm
<b>Disinfection Facilities</b>	
<i>Chlorine Dose</i>	3.2 mg/L
	Target POE Residual: 0.5 mg/L
	Minimum Residual for CT: 0.2 mg/L
<i>Chlorine Pumps</i>	2
<i>Feed Capacity</i>	0.04 gph (2.6 mL/min)
<i>Day Use/Storage</i>	1 gallon
<i>Bulk Storage</i>	Five (5) 5-gallon pails
<i>Pipe for 4-log CT</i>	170 ft of 16-inch DI (@ 60 gpm)
<b>Iron and Manganese Pretreatment</b>	
<i>Building Size</i>	24 ft x 24 ft
<i>Number of Filters</i>	2
<i>Filter Size</i>	3 ft diameter, 6.5 ft height
<i>Filter Skid Dimensions (L x W x H)</i>	8.3 ft x 5 ft x 9 ft
<i>Filter Loading Rate (per filter)</i>	5 gpm/sf
<i>Filter Run Time</i>	24 – 72 hours
<i>Backwash Loading Rate</i>	12 gpm/sf
<i>Backwash Flow Rate</i>	85 gpm
<i>Washwater Supply Tank Volume</i>	1,500 gallons
<i>Rinse to Waste Flow Rate</i>	35 gpm
<i>Rinse to Waste Volume</i>	500 gallons
<i>Backwash Waste Tank Volume</i>	2,000 gallons

A summary of proposed engineering design parameters, including target chemical dosages, for the proposed Army Camp disinfection facilities are presented in Table 2. The proposed disinfection treatment system includes converting the existing well house to a chlorine addition facility which will be used for storing and dosing chlorine. The use of commercial strength sodium hypochlorite (12.5% strength) is proposed. This product can be purchased in 5-gallon pails. The proposed chlorination facilities consist of two (2) chlorine pumps, a carboy scale, and a containment pallet suitable to store up to six (6) 5-gallon pails. Chlorine will be pumped directly out of a 5-gallon pail (carboy) and injected downstream of the existing flow meter. Seventy feet of the existing 2-inch water main will need to be replaced with 16-inch diameter ductile iron water main in order to provide enough contact time (CT) for 4-log inactivation of viruses.

**Table 2**  
**Amy Camp Disinfection Facility**  
**Conceptual Design Summary**

<i>Hydraulic Design Capacity</i>	26 gpm
<b>Disinfection Facilities</b>	
<i>Chlorine Dose</i>	1.0 mg/L
	Target POE Residual: 0.5 mg/L
	Minimum Residual for CT: 0.2 mg/L
<i>Chlorine Pumps</i>	2
<i>Feed Capacity</i>	0.01 gph (0.6 mL/min)
<i>Day Use/Storage</i>	0.25 gallon
<i>Bulk Storage</i>	Two (2) 5-gallon pails
<i>Pipe for 4-log CT</i>	70 ft of 16-inch DI

#### 4-LOG INACTIVATION CT CALCULATIONS

The PIWD disinfection facilities were designed to achieve 4-log inactivation of viruses using sufficient contact time with free chlorine. The CT values required for 4-log inactivation were based on the inactivation tables found in the USEPA Guidance Manual for Disinfection Profiling and Benchmarking, source water temperature, and treated water pH. The calculated CT achieved was based on a minimum free chlorine residual of 0.2 mg/L and the contact time achieved for the various pipe sections at the site design flow. The design flow for the Army Camp well site was 26 gallons per minute (gpm), based on a review of historical pumping records. The design flow for the Indian Springs well site was 60 gpm, based on the directive to build in addition CT capacity for future growth. The CT calculations determined that 70 feet of new 16-inch diameter pipe was required to achieve 4-log inactivation at Army Camp and 170 feet of new 16-inch diameter pipe at Indian Springs. In addition to the 16-inch main, CT credits were also calculated for the existing 50 feet of 2-inch pipe, 20 feet of new 2-inch pipe, and the volume of one (1) greensand filter. The CT calculations for each site are provided in Attachment A.

#### DISINFECTION BY-PRODUCT FORMATION STUDY

In order to examine the future potential impacts of chlorine disinfection at the PIWD well sites on the future potential formation of disinfection by-products, H2Olson Engineering, Inc. completed a bench-top simulated distribution system (SDS) disinfection by-product (DBP) formation potential study. The intent of the SDS-DBP study was to chlorinate PIWD source water with chlorine and allow the samples to incubate in the dark at a constant temperature to simulate typical distribution system conditions (temperature, time, pH). Monthly PIWD production numbers were reviewed from 2017 through July 2021 and theoretical seasonal water ages were estimated based on the total water volume of the distribution system (capacity of the Big Blue Storage Tank and the total pipe length and diameter) and the average winter and summer production. Using a total distribution system volume of 129,000 gallons, an average monthly winter flow of 10,381 gallons

per day (gpd) and an average monthly summer flow of 42,072 gpd, an estimated water age of 12.4 days was calculated for typical winter conditions and 3.1 days for typical summer conditions.

Source water from each water supply site was collected and tested for temperature, pH, alkalinity, UV absorbance to 254 nanometers (UV-254), total organic carbon (TOC), iron, and manganese. Source water iron and manganese from the Indian Springs site was removed by completing a bench scale jar test consisting of the addition of potassium permanganate (at the stoichiometric requirement for iron and manganese oxidation), flocculating for 20 minutes, settling for 30 minutes, then filtering through a 1 micron glass fiber filter followed by a 0.45 micron membrane filter. The resulting source water quality used for the SDS-DBP study is presented below in Table 3.

**Table 3**  
**SDS-DBP Study**  
**Summary of Source Water Quality**

Water Quality Parameter	Indian Springs	Army Camp
Temperature (°F)	50	51
pH (SU)	7.3	7.5
Alkalinity (mg/L as CaCO <sub>3</sub> )	40.8	53.4
Iron (mg/L)	0	0.01
Manganese (mg/L)	0.19	0
UV-254 (1/cm)	0.023	0.005
TOC (mg/L)	< 0.5	0.585

A chlorine titration was then completed on the filtered water from the Indian Springs jar test and Army Camp source water to determine the chlorine demand and required dose to achieve a free chlorine residual between 1.1 and 1.5 mg/L. Water from each site was dosed with chlorine to achieve a free chlorine residual of 1.5 mg/L at Indian Springs and 1.1 mg/L at Army Camp. A slightly higher chlorine residual was targeted for Indian Springs due to the higher manganese level in this water (assuming that it would consume the stoichiometric chlorine demand of 0.4 mg/L over time). The water samples were not adjusted for pH and sealed in 1,000 mL brown glass jars with PTFE septa, and stored in the dark at a temperature of approximately 50 °F, for a period of 3 days and 12 days. An initial SDS-DBP sample (representative of Day 0), was also prepared and tested within 30 minutes after chlorine addition. After the representative holding times (Day 0, Day 3, Day 12), samples were collected and tested for pH, free chlorine residual, alkalinity, ORP, total trihalomethanes (TTHMs) and a group of five haloacetic acids (HAA5s). All samples were collected and sent to an independent laboratory for analysis. In addition, free chlorine residual was tested in the field as soon as the SDS incubation jars were opened in order to get a more accurate chlorine measurement (in case of decay during sample transport and holding at the independent laboratory).

All of the laboratory analysis sampling results are provided in Attachment B. A summary of the SDS-DBP sampling results are provided in Table 4.

**Table 4**  
**SDS-DBP Study**  
**Summary of Water Quality Results**

PIWD Supply:	Indian Springs			Army Camp		
Water Quality Parameter	Day 0	Day 3	Day 12	Day 0	Day 3	Day 12
<b>Free Chlorine Residual (mg/L)</b>	1.54	1.24	1.11	1.12	0.94	0.87
<b>pH (SU)</b>	7.7	7.5	6.9	7.7	7.4	6.8
<b>ORP (mV)</b>	570	540	410	590	570	360
<b>TTHMs (µg/L)</b>	0	2.53	4.4	0	3.7	7.2
<b>HAA5s (µg/L)</b>	1.8	2.1	1.1	0	0	1.7

A review and analysis of the SDS-DBP results provided above and in Attachment B indicated that the PIWD source water has very low levels of natural organic matter and very low levels of disinfection by-products are anticipated after the implementation of chlorine disinfection. TTHMs levels were less than 10 (µg/L) after 12 days of reaction time and HAA5 levels were all less than 3 (µg/L). Based on the current DBP maximum contaminant levels of 80 (µg/L) for TTHMs and 60 (µg/L) for HAA5s, based on locational running annual averages of quarterly sampling results, PIWD should have no problems maintaining compliance with the Disinfection/Disinfection By-Product Rule.

### **CORROSION CONTROL STUDY**

The purpose of the corrosion control study is to examine whether there is expected to be any alteration in water chemistry due to the addition of chlorine which could destabilize existing pipe scales leading to elevated levels of lead or copper in customer's taps. The corrosion control study consisted of a limited materials survey of customer water service lines, and an examination of water quality and desk-top study.

#### Materials Survey

H2Olson completed a detailed and comprehensive review of PIWD files and interviewed operations staff. The PIWD does not currently maintain a set of water service cards that provide details of the customers water service. However, PIWD recently completed a comprehensive backflow and cross connection survey of their customers and did not observe any lead water service materials. In addition, in over 20 years of working on the distribution system, making water service repairs and replacements, current operations staff have never observed a lead service pipe or lead gooseneck. The vast majority of customer water service lines are plastic. However, there are also some copper and iron pipe material services. However, there are no written records of customer water service materials.

### Water Characteristics and Desk-Top Study

H2Olson examined numerous engineering studies during the design phase of this project as referenced on page 2 of this Technical Memorandum. In addition to these engineering studies, and experience with numerous public water systems for corrosion control, a careful review of the USEPA Report “Optimal Corrosion Control Treatment Evaluation Technical Recommendations for Primacy Agencies and Public Water Systems (March 2016)” was completed. Based on the aforementioned study, there are several treatment changes to public water systems which could negatively affect lead and copper corrosion control, in particular for systems with lead service lines. The treatment changes identified which can affect lead and copper corrosivity include:

- Corrosion Control Treatment – changes in pH, alkalinity, dissolved inorganic carbon (DIC), and inhibitor types/concentrations (e.g. lowering the target pH or alkalinity).
- Disinfection – changing secondary disinfection from free chlorine to combined chlorine (chloramines) or changing the type of chlorine used (gaseous chlorine can decrease pH while sodium hypochlorite can increase pH).
- Coagulation – changes in the type of coagulant, in particular if it results in changes to the chloride to sulfate mass ratio (CSMR).
- Water Softening – adding softening can increase alkalinity and pH while eliminating softening can lower pH and alkalinity.
- Membrane Filtration – nanofiltration and reverse osmosis can remove alkalinity, hardness, and other dissolved compounds which can lower pH

With respect to the above noted potential water quality changes that can affect lead and copper corrosion control, only the first three bullet points are relevant. To assess potential chemistry changes PIWD source water and SDS-DBP study water was sampled and tested for several common corrosion control parameters. The SDS-DBP samples represent the future potential water quality within the PIWD distribution system after implementing chlorine disinfection. A summary of the sampling results is presented in Table 5.

**Table 5**  
**Corrosion Control Study**  
**Summary of Water Quality**

Water Quality Parameter	Indian Springs		Army Camp	
	Source Water Existing	Treated Future	Source Water Existing	Treated Future
Temperature (°F)	50	50	51	51
pH (SU)	7.3	7.4	7.5	7.3
ORP (mV)	41	507	53	507
Alkalinity (mg/L as CaCO <sub>3</sub> )	41	37	53	52
DIC (mg/L - calculated)	11	10	14	14
Chloride (mg/L)	10.0	13.6	7.5	14.8
Sulfate (mg/L)	22.5	23.8	7.3	7.3
CSMR	0.4	0.6	1.0	2.0

A review of the water quality information presented in Table 5 strongly suggests that the proposed PIWD disinfection facilities and Indian Springs treatment facility for the removal of source water iron and manganese will not independently negatively impact the District's compliance with the Lead and Copper Rule since the target point of entry pH and alkalinity will not change. Although the ORP is anticipated to increase, the dissolved inorganic carbon (DIC) levels will remain constant, and as a result there should be no destabilization of premise plumbing scales. In addition, the minor increases in CSMR are not indicative of problematic water chemistry changes. A review and comparison of PIWD source water quality information and SDS-DBP results from bench top study with USEPA Optimal Corrosion Control Treatment guidelines indicate that there should be no negative impacts on lead and copper corrosion control from either the application of chlorine for disinfection or the removal of source water iron and manganese, provided that the target finished water (point of entry) pH and alkalinity levels do not change significantly.

A review of existing available PIWD lead and copper sampling information indicates that customer tap water sampling results are always below the Action Levels for both lead and copper. The most recent round of customer tap water lead and copper sampling was conducted in July 2021. The results indicated a 90<sup>th</sup> percentile lead level of 0.0046 mg/L with 8 of 10 samples non-detect for lead and a 90th percentile copper level of 0.13 mg/L. All of the information reviewed herein suggests that the implementation of disinfection for the PIWD will not negatively impact the water chemistry resulting in increased levels of tap water lead or copper.



**Attachment A – 4-Log CT Calculations**



**Prudence Island Water District  
Groundwater Rule CT Evaluation  
Army Camp Well Site**

**Existing**

Pipe Diam "": **2** Pipe Length Ft: **260** Baffling Factor: **1**

1	2	3	4	5	6	7	8	9
Cl Conc	pH	Temp	Peak Flow	Storage	Total Detention	Contact time	CT calc	CT req
mg/L		°C	GPM	Volume	Time (TDT)	min	Cl Conc x	Table 2
				Gallons	Vol/Peak Flow	TDT x Baffling Factor	Contact Time	
0.2	7	10	23	42	1.84	1.84	0.37	6
<b>Total CT</b>							<b>0.37</b>	
<b>CT Calc/CT Req</b>							<b>0.06</b>	Needs to be > 1

**Proposed**

Pipe Diam "": **16** Pipe Length Ft: **70** Baffling Factor: **1**

1	2	3	4	5	6	7	8	9
Cl Conc	pH	Temp	Peak Flow	Storage	Total Detention	Contact time	CT calc	CT req
mg/L		°C	GPM	Volume	Time (TDT)	min	Cl Conc x	Table 2
				Gallons	Vol/Peak Flow	TDT x Baffling Factor	Contact Time	
0.2	7	10	23	731	31.77	31.77	6.35	6
<b>Total CT</b>							<b>6.35</b>	
<b>CT Calc/CT Req</b>							<b>1.06</b>	Needs to be > 1

**Table 1  
Baffling Factors**

Factor	Description
0.1	None, agitated basin, very low length to width ratio, high inlet/outlet velocities
0.3	Single or multiple unbaffled inlets or outlets, no intra-basin baffles
0.5	Baffled inlet/outlet with some intra-basin baffling
0.7	Perforated inlet baffle, serpentine or perforated intra-basin baffles, outlet weir or perforated launders
1	Very high length to width ratio (pipeline flow) perforated inlet, outlet and intra-basin baffles


**TABLE 2  
CT VALUES\* FOR**

**4- LOG INACTIVATION OF VIRUSES BY FREE CHLORINE**

Temperature(°C)	pH	
	6-9	10
0.5	12	90
5	8	60
10	6	45
15	4	30
20	3	22
25	2	15

USEPA Guidance Manual for Disinfection Profiling and Benchmarking

Temperature: 50 degrees F is 10 degrees C



**Prudence Island Water District  
Groundwater Rule CT Evaluation  
Indian Springs Well Site**

**1. From chlorine injection to filters**

Pipe Diam "": **2** Pipe Length Ft: **50** Baffling Factor: **1**

1	2	3	4	5	6	7	8	9
Cl Conc	pH	Temp	Peak Flow	Storage	Total Detention	Contact time	CT calc	CT req
mg/L		°C	Raw Water Q	Volume	Time (TDT)	min	Cl Conc x	Table 2
			GPM	Gallons	Vol/Peak Flow	TDT x Baffling Factor	Contact Time	
0.2	7	10	60	8	0.14	0.14	0.03	6

**2. From chlorine injection to filters**

Pipe Diam "": **16** Pipe Length Ft: **170** Baffling Factor: **1**

1	2	3	4	5	6	7	8	9
Cl Conc	pH	Temp	Peak Flow	Storage	Total Detention	Contact time	CT calc	CT req
mg/L		°C	Raw Water Q	Volume	Time (TDT)	min	Cl Conc x	Table 2
			GPM	Gallons	Vol/Peak Flow	TDT x Baffling Factor	Contact Time	
0.2	7	10	60	1,775	29.58	29.58	5.92	6

**3. Filter Rack & Building Piping**

Pipe Diam "": **2** Pipe Length Ft: **20** Baffling Factor: **1**

1	2	3	4	5	6	7	8	9
Cl Conc	pH	Temp	Peak Flow	Storage	Total Detention	Contact time	CT calc	CT req
mg/L		°C	Raw Water Q	Volume	Time (TDT)	min	Cl Conc x	Table 2
			GPM	Gallons	Vol/Peak Flow	TDT x Baffling Factor	Contact Time	
0.2	7	10	60	3	0.05	0.05	0.01	6

**4. Greensand Filter**

Baffling Factor: **0.5**

1	2	3	4	5	6	7	8	9
Cl Conc	pH	Temp	Peak Flow	Storage	Total Detention	Contact time	CT calc	CT req
mg/L		°C	Raw Water Q	Volume	Time (TDT)	min	Cl Conc x	Table 2
			GPM	1 Filter Gallons	Vol/Peak Flow	TDT x Baffling Factor	Contact Time	
0.2	8.3	10	60	185	3.08	3.08	0.62	6
<b>Total CT</b>							<b>6.56</b>	
<b>CT Calc/CT Req</b>							<b>1.09</b>	Needs to be > 1

**Table 1  
Baffling Factors**

Factor	Description
0.1	None, agitated basin, very low length to width ratio, high inlet/outlet velocities
0.3	Single or multiple unbaffled inlets or outlets, no intra-basin baffles
0.5	Baffled inlet/outlet with some intra-basin baffling
0.7	Perforated inlet baffle, serpentine or perforated intra-basin baffles, outlet weir or perforated launders
1	Very high length to width ratio (pipeline flow) perforated inlet, outlet and intra-basin baffles

**TABLE 2  
CT VALUES\* FOR**

**4- LOG INACTIVATION OF VIRUSES BY FREE CHLORIN**

Temperature(°C)	pH	
	6-9	10
0.5	12	90
5	8	60
10	6	45
15	4	30
20	3	22
25	2	15

**Filter Vessel Volume for CT**

**3' diameter X 6' height**

0.5' underdrain structure


1' gravel @ 50% porosity = 0.5' height

3' media @ 50% porosity = 1.5' height

1.5' water depth on top of media = 1.5' height

Total water height, ft = 3.5

Temperature: 50 degrees F is 10 degrees C



**Attachment B – Independent Laboratory Sampling Results**





## ANALYTICAL REPORT

Lab Number:	L2162231
Client:	H2Olson Engineering, Inc. 10 Riverside Drive, Suite 103 Lakeville, MA 02347
ATTN:	Stephen Olson
Phone:	(508) 375-7007
Project Name:	PRUDENCE ISLAND
Project Number:	119-21-01
Report Date:	11/29/21

The original project report/data package is held by Alpha Analytical. This report/data package is paginated and should be reproduced only in its entirety. Alpha Analytical holds no responsibility for results and/or data that are not consistent with the original.

Certifications & Approvals: MA (M-MA086), NH NELAP (2064), CT (PH-0574), IL (200077), ME (MA00086), MD (348), NJ (MA935), NY (11148), NC (25700/666), PA (68-03671), RI (LAO00065), TX (T104704476), VT (VT-0935), VA (460195), USDA (Permit #P330-17-00196).

---

Eight Walkup Drive, Westborough, MA 01581-1019  
508-898-9220 (Fax) 508-898-9193 800-624-9220 - [www.alphalab.com](http://www.alphalab.com)



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162231  
**Report Date:** 11/29/21

<b>Alpha Sample ID</b>	<b>Client ID</b>	<b>Matrix</b>	<b>Sample Location</b>	<b>Collection Date/Time</b>	<b>Receive Date</b>
L2162231-01	IS-RAW	DW	PRUDENCE ISLAND	11/11/21 13:00	11/11/21
L2162231-02	AC-RAW	DW	PRUDENCE ISLAND	11/11/21 13:15	11/11/21
L2162231-03	IS-DAYO	DW	PRUDENCE ISLAND	11/11/21 15:00	11/11/21
L2162231-04	AC-DAYO	DW	PRUDENCE ISLAND	11/11/21 15:30	11/11/21



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162231  
**Report Date:** 11/29/21

### Case Narrative

The samples were received in accordance with the Chain of Custody and no significant deviations were encountered during the preparation or analysis unless otherwise noted. Sample Receipt, Container Information, and the Chain of Custody are located at the back of the report.

Results contained within this report relate only to the samples submitted under this Alpha Lab Number and meet NELAP requirements for all NELAP accredited parameters unless otherwise noted in the following narrative. The data presented in this report is organized by parameter (i.e. VOC, SVOC, etc.). Sample specific Quality Control data (i.e. Surrogate Spike Recovery) is reported at the end of the target analyte list for each individual sample, followed by the Laboratory Batch Quality Control at the end of each parameter. Tentatively Identified Compounds (TICs), if requested, are reported for compounds identified to be present and are not part of the method/program Target Compound List, even if only a subset of the TCL are being reported. If a sample was re-analyzed or re-extracted due to a required quality control corrective action and if both sets of data are reported, the Laboratory ID of the re-analysis or re-extraction is designated with an "R" or "RE", respectively.

When multiple Batch Quality Control elements are reported (e.g. more than one LCS), the associated samples for each element are noted in the grey shaded header line of each data table. Any Laboratory Batch, Sample Specific % recovery or RPD value that is outside the listed Acceptance Criteria is bolded in the report. In reference to questions H (CAM) or 4 (RCP) when "NO" is checked, the performance criteria for CAM and RCP methods allow for some quality control failures to occur and still be within method compliance. In these instances, the specific failure is not narrated but noted in the associated QC Outlier Summary Report, located directly after the Case Narrative. QC information is also incorporated in the Data Usability Assessment table (Format 11) of our Data Merger tool, where it can be reviewed in conjunction with the sample result, associated regulatory criteria and any associated data usability implications.

Soil/sediments, solids and tissues are reported on a dry weight basis unless otherwise noted. Definitions of all data qualifiers and acronyms used in this report are provided in the Glossary located at the back of the report.

**HOLD POLICY** - For samples submitted on hold, Alpha's policy is to hold samples (with the exception of Air canisters) free of charge for 21 calendar days from the date the project is completed. After 21 calendar days, we will dispose of all samples submitted including those put on hold unless you have contacted your Alpha Project Manager and made arrangements for Alpha to continue to hold the samples. Air canisters will be disposed after 3 business days from the date the project is completed.

Please contact Project Management at 800-624-9220 with any questions.

---

**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162231  
**Report Date:** 11/29/21

### Case Narrative (continued)

#### Report Submission

The analysis of HAA was subcontracted. A copy of the laboratory report is included as an addendum. Please note: This data is only available in PDF format and is not available on Data Merger.

#### Chlorine, Total Residual

L2162231-03 and -04: The sample was analyzed with the method required holding time exceeded.

#### Oxidation/Reduction Potential

The WG1570624-2 Laboratory Duplicate RPD for oxidation/reduction potential (23%), performed on L2162231-01, is outside the acceptance criteria. The elevated RPD has been attributed to the non-homogeneous nature of the native sample.

#### Chlorine, Total Residual

WG1572235-1: A Matrix Spike and Laboratory Duplicate could not be performed due to insufficient sample volume available for analysis.

I, the undersigned, attest under the pains and penalties of perjury that, to the best of my knowledge and belief and based upon my personal inquiry of those responsible for providing the information contained in this analytical report, such information is accurate and complete. This certificate of analysis is not complete unless this page accompanies any and all pages of this report.

Authorized Signature:



Sebastian Corbin

Title: Technical Director/Representative

Date: 11/29/21

# ORGANICS



# VOLATILES



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162231  
**Report Date:** 11/29/21

**SAMPLE RESULTS**

Lab ID: L2162231-03  
 Client ID: IS-DAYO  
 Sample Location: PRUDENCE ISLAND

Date Collected: 11/11/21 15:00  
 Date Received: 11/11/21  
 Field Prep: Not Specified

Sample Depth:

Matrix: Dw  
 Analytical Method: 16,524.2  
 Analytical Date: 11/15/21 12:26  
 Analyst: NLK

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by GC/MS - Westborough Lab</b>						
Chloroform	ND		ug/l	0.50	--	1
Bromodichloromethane	ND		ug/l	0.50	--	1
Dibromochloromethane	ND		ug/l	0.50	--	1
Bromoform	ND		ug/l	0.50	--	1
THMs, Total	ND		ug/l	0.50	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichlorobenzene-d4	101		80-120
4-Bromofluorobenzene	97		80-120

**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162231  
**Report Date:** 11/29/21

**SAMPLE RESULTS**

Lab ID: L2162231-04  
 Client ID: AC-DAYO  
 Sample Location: PRUDENCE ISLAND

Date Collected: 11/11/21 15:30  
 Date Received: 11/11/21  
 Field Prep: Not Specified

Sample Depth:

Matrix: Dw  
 Analytical Method: 16,524.2  
 Analytical Date: 11/17/21 14:17  
 Analyst: GT

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by GC/MS - Westborough Lab</b>						
Chloroform	ND		ug/l	0.50	--	1
Bromodichloromethane	ND		ug/l	0.50	--	1
Dibromochloromethane	ND		ug/l	0.50	--	1
Bromoform	ND		ug/l	0.50	--	1
THMs, Total	ND		ug/l	0.50	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichlorobenzene-d4	101		80-120
4-Bromofluorobenzene	94		80-120



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162231  
**Report Date:** 11/29/21

**Method Blank Analysis**  
**Batch Quality Control**

Analytical Method: 16,524.2  
Analytical Date: 11/15/21 10:24  
Analyst: NLK

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by GC/MS - Westborough Lab for sample(s): 03 Batch: WG1571987-4					
Chloroform	ND		ug/l	0.50	--
Bromodichloromethane	ND		ug/l	0.50	--
Dibromochloromethane	ND		ug/l	0.50	--
Bromoform	ND		ug/l	0.50	--
THMs, Total	ND		ug/l	0.50	--

Surrogate	%Recovery	Qualifier	Acceptance Criteria
1,2-Dichlorobenzene-d4	102		80-120
4-Bromofluorobenzene	97		80-120

**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162231  
**Report Date:** 11/29/21

**Method Blank Analysis**  
**Batch Quality Control**

Analytical Method: 16,524.2  
Analytical Date: 11/17/21 12:44  
Analyst: GT

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by GC/MS - Westborough Lab for sample(s): 04 Batch: WG1573778-4					
Chloroform	ND		ug/l	0.50	--
Bromodichloromethane	ND		ug/l	0.50	--
Dibromochloromethane	ND		ug/l	0.50	--
Bromoform	ND		ug/l	0.50	--
THMs, Total	ND		ug/l	0.50	--

Surrogate	%Recovery	Qualifier	Acceptance Criteria
1,2-Dichlorobenzene-d4	104		80-120
4-Bromofluorobenzene	98		80-120

## Lab Control Sample Analysis

### Batch Quality Control

Project Name: PRUDENCE ISLAND

Lab Number: L2162231

Project Number: 119-21-01

Report Date: 11/29/21

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 03 Batch: WG1571987-3								
Chloroform	95		-		70-130	-		20
Bromodichloromethane	90		-		70-130	-		20
Dibromochloromethane	85		-		70-130	-		20
Bromoform	100		-		70-130	-		20

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria
1,2-Dichlorobenzene-d4	98				80-120
4-Bromofluorobenzene	97				80-120

## Lab Control Sample Analysis

Batch Quality Control

Project Name: PRUDENCE ISLAND

Lab Number: L2162231

Project Number: 119-21-01

Report Date: 11/29/21

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 04 Batch: WG1573778-3								
Chloroform	98		-		70-130	-		20
Bromodichloromethane	92		-		70-130	-		20
Dibromochloromethane	85		-		70-130	-		20
Bromoform	98		-		70-130	-		20

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria
1,2-Dichlorobenzene-d4	97				80-120
4-Bromofluorobenzene	100				80-120

## Matrix Spike Analysis

*Batch Quality Control*

**Project Name:** PRUDENCE ISLAND

**Lab Number:** L2162231

**Project Number:** 119-21-01

**Report Date:** 11/29/21

<i>Parameter</i>	<i>Native Sample</i>	<i>MS Added</i>	<i>MS Found</i>	<i>MS %Recovery</i>	<i>Qual</i>	<i>MSD Found</i>	<i>MSD %Recovery</i>	<i>Qual</i>	<i>Recovery Limits</i>	<i>RPD</i>	<i>Qual</i>	<i>RPD Limits</i>
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 03 QC Batch ID: WG1571987-5 WG1571987-6 QC Sample: L2102617-62 Client ID: MS Sample												
Dichlorodifluoromethane	ND	4	5.0	125		5.6	140	Q	70-130	11		20
Chloromethane	ND	4	5.6	140	Q	6.0	150	Q	70-130	7		20
Vinyl chloride	ND	4	6.3	158	Q	6.4	160	Q	70-130	2		20
Bromomethane	ND	4	3.8	95		4.2	105		70-130	10		20
Chloroethane	ND	4	4.8	120		5.6	140	Q	70-130	15		20
Trichlorofluoromethane	ND	4	4.7	118		4.9	123		70-130	4		20
Acetone	ND	8	9.0	113		9.4	118		70-130	4		20
1,1-Dichloroethene	ND	4	4.8	120		5.1	128		70-130	6		20
tert-Butyl Alcohol	ND	20	20	100		19	95		70-130	5		20
Methylene chloride	ND	4	4.7	118		5.0	125		70-130	6		20
Methyl tert butyl ether	ND	4	4.0	100		4.1	103		70-130	2		20
trans-1,2-Dichloroethene	ND	4	4.7	118		5.0	125		70-130	6		20
1,1-Dichloroethane	ND	4	4.8	120		5.0	125		70-130	4		20
2,2-Dichloropropane	ND	4	4.0	100		4.0	100		70-130	0		20
cis-1,2-Dichloroethene	ND	4	4.4	110		4.4	110		70-130	0		20
Chloroform	ND	4	4.4	110		4.6	115		70-130	4		20
Bromochloromethane	ND	4	4.2	105		5.2	130		70-130	21	Q	20
Tetrahydrofuran <sup>1</sup>	ND	8	7.1	89		9.3	116		70-130	27	Q	20
1,1,1-Trichloroethane	ND	4	4.1	103		4.0	100		70-130	2		20
1,1-Dichloropropene	ND	4	4.5	113		4.2	105		70-130	7		20
Carbon tetrachloride	ND	4	4.0	100		3.8	95		70-130	5		20
1,2-Dichloroethane	ND	4	4.6	115		4.4	110		70-130	4		20
Benzene	ND	4	4.4	110		4.2	105		70-130	5		20

## Matrix Spike Analysis

*Batch Quality Control*

**Project Name:** PRUDENCE ISLAND

**Lab Number:** L2162231

**Project Number:** 119-21-01

**Report Date:** 11/29/21

<b>Parameter</b>	<b>Native Sample</b>	<b>MS Added</b>	<b>MS Found</b>	<b>MS %Recovery</b>	<b>Qual</b>	<b>MSD Found</b>	<b>MSD %Recovery</b>	<b>Qual</b>	<b>Recovery Limits</b>	<b>RPD</b>	<b>Qual</b>	<b>RPD Limits</b>
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 03 QC Batch ID: WG1571987-5 WG1571987-6 QC Sample: L2102617-62 Client ID: MS Sample												
Trichloroethene	ND	4	3.8	95		3.7	92		70-130	3		20
1,2-Dichloropropane	ND	4	4.3	108		4.3	108		70-130	0		20
Bromodichloromethane	ND	4	3.9	98		3.8	95		70-130	3		20
Dibromomethane	ND	4	4.1	103		4.0	100		70-130	2		20
cis-1,3-Dichloropropene	ND	4	3.7	92		3.7	92		70-130	0		20
Toluene	ND	4	3.9	98		3.9	98		70-130	0		20
trans-1,3-Dichloropropene	ND	4	3.7	92		3.5	88		70-130	6		20
1,1,2-Trichloroethane	ND	4	3.8	95		4.1	103		70-130	8		20
1,3-Dichloropropane	ND	4	4.0	100		3.9	98		70-130	3		20
Tetrachloroethene	ND	4	3.4	85		3.6	90		70-130	6		20
Dibromochloromethane	ND	4	3.3	82		3.5	88		70-130	6		20
1,2-Dibromoethane	ND	4	3.6	90		3.8	95		70-130	5		20
Chlorobenzene	ND	4	4.4	110		4.1	103		70-130	7		20
1,1,1,2-Tetrachloroethane	ND	4	4.0	100		4.0	100		70-130	0		20
Ethylbenzene	ND	4	4.4	110		4.3	108		70-130	2		20
p/m-Xylene	ND	8	9.0	113		8.8	110		70-130	2		20
o-Xylene	ND	4	4.2	105		4.2	105		70-130	0		20
Styrene	ND	4	4.3	108		4.3	108		70-130	0		20
Isopropylbenzene	ND	4	4.2	105		4.2	105		70-130	0		20
Bromoform	ND	4	3.5	88		3.4	85		70-130	3		20
1,1,2,2-Tetrachloroethane	ND	4	4.8	120		4.4	110		70-130	9		20
1,2,3-Trichloropropane	ND	4	4.4	110		4.2	105		70-130	5		20
n-Propylbenzene	ND	4	4.6	115		4.5	113		70-130	2		20

## Matrix Spike Analysis

*Batch Quality Control*

**Project Name:** PRUDENCE ISLAND

**Project Number:** 119-21-01

**Lab Number:** L2162231

**Report Date:** 11/29/21

<i>Parameter</i>	<i>Native Sample</i>	<i>MS Added</i>	<i>MS Found</i>	<i>MS %Recovery</i>	<i>Qual</i>	<i>MSD Found</i>	<i>MSD %Recovery</i>	<i>Qual</i>	<i>Recovery Limits</i>	<i>RPD</i>	<i>Qual</i>	<i>RPD Limits</i>
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 03 QC Batch ID: WG1571987-5 WG1571987-6 QC Sample: L2102617-62 Client ID: MS Sample												
Bromobenzene	ND	4	4.7	118		4.7	118		70-130	0		20
1,3,5-Trimethylbenzene	ND	4	4.4	110		4.3	108		70-130	2		20
o-Chlorotoluene	ND	4	4.7	118		4.6	115		70-130	2		20
p-Chlorotoluene	ND	4	4.7	118		4.6	115		70-130	2		20
tert-Butylbenzene	ND	4	4.4	110		4.4	110		70-130	0		20
1,2,4-Trimethylbenzene	ND	4	4.4	110		4.4	110		70-130	0		20
sec-Butylbenzene	ND	4	4.6	115		4.4	110		70-130	4		20
p-Isopropyltoluene	ND	4	4.3	108		4.3	108		70-130	0		20
1,3-Dichlorobenzene	ND	4	4.3	108		4.4	110		70-130	2		20
1,4-Dichlorobenzene	ND	4	4.3	108		4.3	108		70-130	0		20
n-Butylbenzene	ND	4	4.4	110		4.5	113		70-130	2		20
1,2-Dichlorobenzene	ND	4	4.4	110		4.2	105		70-130	5		20
1,2-Dibromo-3-chloropropane	ND	4	4.1	103		3.5	88		70-130	16		20
1,2,4-Trichlorobenzene	ND	4	3.6	90		3.5	88		70-130	3		20
Hexachlorobutadiene	ND	4	3.7	92		3.7	92		70-130	0		20
Naphthalene	ND	4	3.6	90		3.5	88		70-130	3		20
1,2,3-Trichlorobenzene	ND	4	3.7	92		3.7	92		70-130	0		20

<i>Surrogate</i>	<i>MS % Recovery</i>	<i>Qualifier</i>	<i>MSD % Recovery</i>	<i>Qualifier</i>	<i>Acceptance Criteria</i>
1,2-Dichlorobenzene-d4	101		101		80-120
4-Bromofluorobenzene	103		103		80-120

## Matrix Spike Analysis

*Batch Quality Control*

**Project Name:** PRUDENCE ISLAND

**Lab Number:** L2162231

**Project Number:** 119-21-01

**Report Date:** 11/29/21

<i>Parameter</i>	<i>Native Sample</i>	<i>MS Added</i>	<i>MS Found</i>	<i>MS %Recovery</i>	<i>Qual</i>	<i>MSD Found</i>	<i>MSD %Recovery</i>	<i>Qual</i>	<i>Recovery Limits</i>	<i>RPD</i>	<i>Qual</i>	<i>RPD Limits</i>
Volatile Organics by GC/MS - Westborough Lab    Associated sample(s): 04    QC Batch ID: WG1573778-6    QC Sample: L2163057-02    Client ID: MS Sample												
Dichlorodifluoromethane	ND	4	7.8	195	Q	-	-		70-130	-		20
Chloromethane	ND	4	7.0	175	Q	-	-		70-130	-		20
Vinyl chloride	ND	4	7.9	198	Q	-	-		70-130	-		20
Bromomethane	ND	4	4.6	115		-	-		70-130	-		20
Chloroethane	ND	4	5.9	148	Q	-	-		70-130	-		20
Trichlorofluoromethane	ND	4	5.4	135	Q	-	-		70-130	-		20
1,1-Dichloroethene	ND	4	5.6	140	Q	-	-		70-130	-		20
Methylene chloride	ND	4	5.3	133	Q	-	-		70-130	-		20
Methyl tert butyl ether	ND	4	4.5	113		-	-		70-130	-		20
trans-1,2-Dichloroethene	ND	4	5.2	130		-	-		70-130	-		20
1,1-Dichloroethane	ND	4	5.3	133	Q	-	-		70-130	-		20
2,2-Dichloropropane	ND	4	4.5	113		-	-		70-130	-		20
cis-1,2-Dichloroethene	ND	4	5.1	128		-	-		70-130	-		20
Chloroform	1.4	4	6.4	125		-	-		70-130	-		20
Bromochloromethane	ND	4	6.0	150	Q	-	-		70-130	-		20
1,1,1-Trichloroethane	ND	4	5.4	135	Q	-	-		70-130	-		20
1,1-Dichloropropene	ND	4	5.1	128		-	-		70-130	-		20
Carbon tetrachloride	ND	4	4.3	108		-	-		70-130	-		20
1,2-Dichloroethane	ND	4	5.0	125		-	-		70-130	-		20
Benzene	ND	4	4.6	115		-	-		70-130	-		20
Trichloroethene	ND	4	4.0	100		-	-		70-130	-		20
1,2-Dichloropropane	ND	4	4.8	120		-	-		70-130	-		20
Bromodichloromethane	ND	4	4.2	105		-	-		70-130	-		20
Dibromomethane	ND	4	4.6	115		-	-		70-130	-		20



## Matrix Spike Analysis

*Batch Quality Control*

**Project Name:** PRUDENCE ISLAND

**Lab Number:** L2162231

**Project Number:** 119-21-01

**Report Date:** 11/29/21

<i>Parameter</i>	<i>Native Sample</i>	<i>MS Added</i>	<i>MS Found</i>	<i>MS %Recovery</i>	<i>Qual</i>	<i>MSD Found</i>	<i>MSD %Recovery</i>	<i>Qual</i>	<i>Recovery Limits</i>	<i>RPD</i>	<i>Qual</i>	<i>RPD Limits</i>
Volatile Organics by GC/MS - Westborough Lab    Associated sample(s): 04    QC Batch ID: WG1573778-6    QC Sample: L2163057-02    Client ID: MS Sample												
cis-1,3-Dichloropropene	ND	4	4.0	100		-	-		70-130	-		20
Toluene	ND	4	4.1	103		-	-		70-130	-		20
trans-1,3-Dichloropropene	ND	4	3.8	95		-	-		70-130	-		20
1,1,2-Trichloroethane	ND	4	4.1	103		-	-		70-130	-		20
1,3-Dichloropropane	ND	4	4.2	105		-	-		70-130	-		20
Tetrachloroethene	ND	4	4.0	100		-	-		70-130	-		20
Dibromochloromethane	ND	4	3.7	92		-	-		70-130	-		20
1,2-Dibromoethane	ND	4	4.0	100		-	-		70-130	-		20
Chlorobenzene	ND	4	4.8	120		-	-		70-130	-		20
1,1,1,2-Tetrachloroethane	ND	4	4.6	115		-	-		70-130	-		20
Ethylbenzene	ND	4	4.9	123		-	-		70-130	-		20
p/m-Xylene	ND	8	10	125		-	-		70-130	-		20
o-Xylene	ND	4	4.7	118		-	-		70-130	-		20
Styrene	ND	4	4.9	123		-	-		70-130	-		20
Isopropylbenzene	ND	4	4.8	120		-	-		70-130	-		20
Bromoform	ND	4	4.0	100		-	-		70-130	-		20
1,1,2,2-Tetrachloroethane	ND	4	5.1	128		-	-		70-130	-		20
1,2,3-Trichloropropane	ND	4	4.7	118		-	-		70-130	-		20
n-Propylbenzene	ND	4	5.2	130		-	-		70-130	-		20
Bromobenzene	ND	4	5.1	128		-	-		70-130	-		20
1,3,5-Trimethylbenzene	ND	4	5.0	125		-	-		70-130	-		20
o-Chlorotoluene	ND	4	5.1	128		-	-		70-130	-		20
p-Chlorotoluene	ND	4	5.2	130		-	-		70-130	-		20
tert-Butylbenzene	ND	4	4.8	120		-	-		70-130	-		20

## Matrix Spike Analysis

*Batch Quality Control*

**Project Name:** PRUDENCE ISLAND

**Project Number:** 119-21-01

**Lab Number:** L2162231

**Report Date:** 11/29/21

<i>Parameter</i>	<i>Native Sample</i>	<i>MS Added</i>	<i>MS Found</i>	<i>MS %Recovery</i>	<i>Qual</i>	<i>MSD Found</i>	<i>MSD %Recovery</i>	<i>Qual</i>	<i>Recovery Limits</i>	<i>RPD</i>	<i>Qual</i>	<i>RPD Limits</i>
Volatile Organics by GC/MS - Westborough Lab    Associated sample(s): 04    QC Batch ID: WG1573778-6    QC Sample: L2163057-02    Client ID: MS Sample												
1,2,4-Trimethylbenzene	ND	4	5.2	130		-	-		70-130	-		20
sec-Butylbenzene	ND	4	5.2	130		-	-		70-130	-		20
p-Isopropyltoluene	ND	4	4.9	123		-	-		70-130	-		20
1,3-Dichlorobenzene	ND	4	5.1	128		-	-		70-130	-		20
1,4-Dichlorobenzene	ND	4	4.5	113		-	-		70-130	-		20
n-Butylbenzene	ND	4	4.6	115		-	-		70-130	-		20
1,2-Dichlorobenzene	ND	4	4.6	115		-	-		70-130	-		20
1,2-Dibromo-3-chloropropane	ND	4	3.7	92		-	-		70-130	-		20
1,2,4-Trichlorobenzene	ND	4	4.0	100		-	-		70-130	-		20
Hexachlorobutadiene	ND	4	4.4	110		-	-		70-130	-		20
Naphthalene	ND	4	3.6	90		-	-		70-130	-		20
1,2,3-Trichlorobenzene	ND	4	4.0	100		-	-		70-130	-		20

<i>Surrogate</i>	<i>MS % Recovery</i>	<i>Qualifier</i>	<i>MSD % Recovery</i>	<i>Qualifier</i>	<i>Acceptance Criteria</i>
1,2-Dichlorobenzene-d4	98				80-120
4-Bromofluorobenzene	105				80-120

## Lab Duplicate Analysis

Batch Quality Control

Project Name: PRUDENCE ISLAND

Project Number: 119-21-01

Lab Number: L2162231

Report Date: 11/29/21

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 04 QC Batch ID: WG1573778-5 QC Sample: L2163054-02 Client ID: DUP Sample						
Dichlorodifluoromethane	ND	ND	ug/l	NC		20
Chloromethane	ND	ND	ug/l	NC		20
Vinyl chloride	ND	ND	ug/l	NC		20
Bromomethane	ND	ND	ug/l	NC		20
Chloroethane	ND	ND	ug/l	NC		20
Trichlorofluoromethane	ND	ND	ug/l	NC		20
1,1-Dichloroethene	ND	ND	ug/l	NC		20
Methylene chloride	ND	ND	ug/l	NC		20
Methyl tert butyl ether	ND	ND	ug/l	NC		20
trans-1,2-Dichloroethene	ND	ND	ug/l	NC		20
1,1-Dichloroethane	ND	ND	ug/l	NC		20
2,2-Dichloropropane	ND	ND	ug/l	NC		20
cis-1,2-Dichloroethene	ND	ND	ug/l	NC		20
Chloroform	2.2	2.0	ug/l	10		20
Bromochloromethane	ND	ND	ug/l	NC		20
1,1,1-Trichloroethane	ND	ND	ug/l	NC		20
1,1-Dichloropropene	ND	ND	ug/l	NC		20
Carbon tetrachloride	ND	ND	ug/l	NC		20
1,2-Dichloroethane	ND	ND	ug/l	NC		20
Benzene	ND	ND	ug/l	NC		20
Trichloroethene	ND	ND	ug/l	NC		20

## Lab Duplicate Analysis

Batch Quality Control

Project Name: PRUDENCE ISLAND

Project Number: 119-21-01

Lab Number: L2162231

Report Date: 11/29/21

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 04 QC Batch ID: WG1573778-5 QC Sample: L2163054-02 Client ID: DUP Sample						
1,2-Dichloropropane	ND	ND	ug/l	NC		20
Bromodichloromethane	ND	ND	ug/l	NC		20
Dibromomethane	ND	ND	ug/l	NC		20
cis-1,3-Dichloropropene	ND	ND	ug/l	NC		20
Toluene	ND	ND	ug/l	NC		20
trans-1,3-Dichloropropene	ND	ND	ug/l	NC		20
1,1,2-Trichloroethane	ND	ND	ug/l	NC		20
1,3-Dichloropropane	ND	ND	ug/l	NC		20
Tetrachloroethene	ND	ND	ug/l	NC		20
Dibromochloromethane	ND	ND	ug/l	NC		20
1,2-Dibromoethane	ND	ND	ug/l	NC		20
Chlorobenzene	ND	ND	ug/l	NC		20
1,1,1,2-Tetrachloroethane	ND	ND	ug/l	NC		20
Ethylbenzene	ND	ND	ug/l	NC		20
p/m-Xylene	ND	ND	ug/l	NC		20
o-Xylene	ND	ND	ug/l	NC		20
Styrene	ND	ND	ug/l	NC		20
Isopropylbenzene	ND	ND	ug/l	NC		20
Bromoform	ND	ND	ug/l	NC		20
1,1,2,2-Tetrachloroethane	ND	ND	ug/l	NC		20
1,2,3-Trichloropropane	ND	ND	ug/l	NC		20

## Lab Duplicate Analysis

Batch Quality Control

Project Name: PRUDENCE ISLAND

Project Number: 119-21-01

Lab Number: L2162231

Report Date: 11/29/21

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 04 QC Batch ID: WG1573778-5 QC Sample: L2163054-02 Client ID: DUP Sample						
n-Propylbenzene	ND	ND	ug/l	NC		20
Xylene (Total) <sup>1</sup>	ND	ND	ug/l	NC		20
Bromobenzene	ND	ND	ug/l	NC		20
Trihalomethanes, Total	2.2	2.0	ug/l	10		20
1,3,5-Trimethylbenzene	ND	ND	ug/l	NC		20
o-Chlorotoluene	ND	ND	ug/l	NC		20
p-Chlorotoluene	ND	ND	ug/l	NC		20
tert-Butylbenzene	ND	ND	ug/l	NC		20
1,2,4-Trimethylbenzene	ND	ND	ug/l	NC		20
sec-Butylbenzene	ND	ND	ug/l	NC		20
p-Isopropyltoluene	ND	ND	ug/l	NC		20
1,3-Dichlorobenzene	ND	ND	ug/l	NC		20
1,4-Dichlorobenzene	ND	ND	ug/l	NC		20
n-Butylbenzene	ND	ND	ug/l	NC		20
1,2-Dichlorobenzene	ND	ND	ug/l	NC		20
1,2-Dibromo-3-chloropropane	ND	ND	ug/l	NC		20
1,2,4-Trichlorobenzene	ND	ND	ug/l	NC		20
Hexachlorobutadiene	ND	ND	ug/l	NC		20
Naphthalene	ND	ND	ug/l	NC		20
1,2,3-Trichlorobenzene	ND	ND	ug/l	NC		20

## Lab Duplicate Analysis

Batch Quality Control

Project Name: PRUDENCE ISLAND

Lab Number: L2162231

Project Number: 119-21-01

Report Date: 11/29/21

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 04 QC Batch ID: WG1573778-5 QC Sample: L2163054-02 Client ID: DUP Sample						

Surrogate	%Recovery	Qualifier	%Recovery	Qualifier	Acceptance Criteria
1,2-Dichlorobenzene-d4	103		105		80-120
4-Bromofluorobenzene	96		91		80-120

# **INORGANICS & MISCELLANEOUS**





**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162231  
**Report Date:** 11/29/21

**SAMPLE RESULTS**

**Lab ID:** L2162231-01  
**Client ID:** IS-RAW  
**Sample Location:** PRUDENCE ISLAND

**Date Collected:** 11/11/21 13:00  
**Date Received:** 11/11/21  
**Field Prep:** Not Specified

**Sample Depth:**  
**Matrix:** Dw

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>General Chemistry - Westborough Lab</b>										
Alkalinity, Total	40.8		mg CaCO3/L	2.00	NA	1	-	11/23/21 10:12	121,2320B	JB
pH (H)	7.3		SU	-	NA	1	-	11/12/21 22:08	121,4500H+-B	AS
Total Organic Carbon	ND		mg/l	0.500	--	1	-	11/17/21 16:28	121,5310C	DW
Oxidation/Reduction Potential	27		mv	-	NA	1	-	11/12/21 10:28	12,1498	KP



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162231  
**Report Date:** 11/29/21

**SAMPLE RESULTS**

**Lab ID:** L2162231-02  
**Client ID:** AC-RAW  
**Sample Location:** PRUDENCE ISLAND

**Date Collected:** 11/11/21 13:15  
**Date Received:** 11/11/21  
**Field Prep:** Not Specified

**Sample Depth:**  
**Matrix:** Dw

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>General Chemistry - Westborough Lab</b>										
Alkalinity, Total	53.4		mg CaCO3/L	2.00	NA	1	-	11/23/21 10:12	121,2320B	JB
pH (H)	7.5		SU	-	NA	1	-	11/12/21 22:08	121,4500H+-B	AS
Total Organic Carbon	0.585		mg/l	0.500	--	1	-	11/17/21 16:44	121,5310C	DW
Oxidation/Reduction Potential	130		mv	-	NA	1	-	11/12/21 10:28	12,1498	KP



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162231  
**Report Date:** 11/29/21

**SAMPLE RESULTS**

**Lab ID:** L2162231-03  
**Client ID:** IS-DAYO  
**Sample Location:** PRUDENCE ISLAND

**Date Collected:** 11/11/21 15:00  
**Date Received:** 11/11/21  
**Field Prep:** Not Specified

**Sample Depth:**  
**Matrix:** Dw

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>General Chemistry - Westborough Lab</b>										
Alkalinity, Total	36.7		mg CaCO3/L	2.00	NA	1	-	11/23/21 10:12	121,2320B	JB
Chlorine, Total Residual	0.34		mg/l	0.02	--	1	-	11/16/21 23:09	121,4500CL-D	AS
pH (H)	7.7		SU	-	NA	1	-	11/12/21 22:08	121,4500H+-B	AS
Oxidation/Reduction Potential	570		mv	-	NA	1	-	11/12/21 10:28	12,1498	KP



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162231  
**Report Date:** 11/29/21

**SAMPLE RESULTS**

**Lab ID:** L2162231-04  
**Client ID:** AC-DAYO  
**Sample Location:** PRUDENCE ISLAND

**Date Collected:** 11/11/21 15:30  
**Date Received:** 11/11/21  
**Field Prep:** Not Specified

**Sample Depth:**  
**Matrix:** Dw

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>General Chemistry - Westborough Lab</b>										
Alkalinity, Total	52.2		mg CaCO3/L	2.00	NA	1	-	11/23/21 10:12	121,2320B	JB
Chlorine, Total Residual	0.17		mg/l	0.02	--	1	-	11/16/21 23:09	121,4500CL-D	AS
pH (H)	7.7		SU	-	NA	1	-	11/12/21 22:08	121,4500H+-B	AS
Oxidation/Reduction Potential	590		mv	-	NA	1	-	11/12/21 10:28	12,1498	KP



Project Name: PRUDENCE ISLAND

Lab Number: L2162231

Project Number: 119-21-01

Report Date: 11/29/21

**Method Blank Analysis**  
**Batch Quality Control**

Parameter	Result Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
General Chemistry - Westborough Lab for sample(s): 03-04 Batch: WG1572235-1									
Chlorine, Total Residual	ND	mg/l	0.02	--	1	-	11/16/21 23:09	121,4500CL-D	AS
General Chemistry - Westborough Lab for sample(s): 01-02 Batch: WG1572347-1									
Total Organic Carbon	ND	mg/l	0.500	--	1	-	11/17/21 08:44	121,5310C	DW
General Chemistry - Westborough Lab for sample(s): 01-02 Batch: WG1574988-1									
Alkalinity, Total	ND	mg CaCO3/L	2.00	NA	1	-	11/23/21 10:12	121,2320B	JB
General Chemistry - Westborough Lab for sample(s): 03-04 Batch: WG1574989-1									
Alkalinity, Total	ND	mg CaCO3/L	2.00	NA	1	-	11/23/21 10:12	121,2320B	JB



## Lab Control Sample Analysis

### Batch Quality Control

Project Name: PRUDENCE ISLAND

Project Number: 119-21-01

Lab Number: L2162231

Report Date: 11/29/21

Parameter	LCS		LCSD		%Recovery Limits	RPD	Qual	RPD Limits
	%Recovery	Qual	%Recovery	Qual				
General Chemistry - Westborough Lab Associated sample(s): 01-04 Batch: WG1570624-1								
Oxidation/Reduction Potential	103		-		90-110	-		20
General Chemistry - Westborough Lab Associated sample(s): 01-04 Batch: WG1570882-1								
pH	101		-		99-101	-		5
General Chemistry - Westborough Lab Associated sample(s): 03-04 Batch: WG1572235-2								
Chlorine, Total Residual	104		-		90-110	-		
General Chemistry - Westborough Lab Associated sample(s): 01-02 Batch: WG1572347-2								
Total Organic Carbon	100		-		90-110	-		
General Chemistry - Westborough Lab Associated sample(s): 01-02 Batch: WG1574988-2								
Alkalinity, Total	104		-		90-110	-		10
General Chemistry - Westborough Lab Associated sample(s): 03-04 Batch: WG1574989-2								
Alkalinity, Total	102		-		90-110	-		10

### Matrix Spike Analysis Batch Quality Control

**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162231  
**Report Date:** 11/29/21

Parameter	Native Sample	MS Added	MS Found	MS %Recovery	MSD Qual	MSD Found	MSD %Recovery	MSD Qual	Recovery Limits	RPD	RPD Qual	RPD Limits
General Chemistry - Westborough Lab Associated sample(s): 01-02 QC Batch ID: WG1572347-4 QC Sample: L2162966-01 Client ID: MS Sample												
Total Organic Carbon	3.87	16	20.0	101	-	-	-	-	80-120	-	-	20
General Chemistry - Westborough Lab Associated sample(s): 01-02 QC Batch ID: WG1574988-4 QC Sample: L2163203-03 Client ID: MS Sample												
Alkalinity, Total	282	100	385	103	-	-	-	-	86-116	-	-	10
General Chemistry - Westborough Lab Associated sample(s): 03-04 QC Batch ID: WG1574989-4 QC Sample: L2162696-03 Client ID: MS Sample												
Alkalinity, Total	55.2	100	158	103	-	-	-	-	86-116	-	-	10



## Lab Duplicate Analysis

*Batch Quality Control*

Project Name: PRUDENCE ISLAND

Project Number: 119-21-01

Lab Number: L2162231

Report Date: 11/29/21

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
General Chemistry - Westborough Lab Associated sample(s): 01-04 QC Batch ID: WG1570624-2 QC Sample: L2162231-01 Client ID: IS-RAW						
Oxidation/Reduction Potential	27	34	mv	23	Q	20
General Chemistry - Westborough Lab Associated sample(s): 01-04 QC Batch ID: WG1570882-2 QC Sample: L2162077-01 Client ID: DUP Sample						
pH	6.0	6.0	SU	0		5
General Chemistry - Westborough Lab Associated sample(s): 01-02 QC Batch ID: WG1572347-3 QC Sample: L2162966-01 Client ID: DUP Sample						
Total Organic Carbon	3.87	3.80	mg/l	2		20
General Chemistry - Westborough Lab Associated sample(s): 01-02 QC Batch ID: WG1574988-3 QC Sample: L2163203-03 Client ID: DUP Sample						
Alkalinity, Total	282	282	mg CaCO3/L	0		10
General Chemistry - Westborough Lab Associated sample(s): 03-04 QC Batch ID: WG1574989-3 QC Sample: L2162696-03 Client ID: DUP Sample						
Alkalinity, Total	55.2	55.3	mg CaCO3/L	0		10

**Project Name:** PRUDENCE ISLAND**Lab Number:** L2162231**Project Number:** 119-21-01**Report Date:** 11/29/21**Sample Receipt and Container Information**

Were project specific reporting limits specified?

YES

**Cooler Information**

<b>Cooler</b>	<b>Custody Seal</b>
A	Absent

**Container Information**

<b>Container ID</b>	<b>Container Type</b>	<b>Cooler</b>	<b>Initial pH</b>	<b>Final pH</b>	<b>Temp deg C</b>	<b>Pres</b>	<b>Seal</b>	<b>Frozen Date/Time</b>	<b>Analysis(*)</b>
L2162231-01A	Vial H2SO4 preserved	A	NA		4.5	Y	Absent		TOC-5310(28)
L2162231-01B	Vial H2SO4 preserved	A	NA		4.5	Y	Absent		TOC-5310(28)
L2162231-01C	Plastic 120ml unpreserved	A	7	7	4.5	Y	Absent		ORP(1),PH-4500(.01)
L2162231-01D	Plastic 250ml unpreserved/No Headspace	A	NA		4.5	Y	Absent		ALK-T-2320(14)
L2162231-02A	Vial H2SO4 preserved	A	NA		4.5	Y	Absent		TOC-5310(28)
L2162231-02B	Vial H2SO4 preserved	A	NA		4.5	Y	Absent		TOC-5310(28)
L2162231-02C	Plastic 120ml unpreserved	A	7	7	4.5	Y	Absent		ORP(1),PH-4500(.01)
L2162231-02D	Plastic 250ml unpreserved/No Headspace	A	NA		4.5	Y	Absent		ALK-T-2320(14)
L2162231-03A	Vial Ascorbic Acid/HCl preserved	A	NA		4.5	Y	Absent		524-THM(14)
L2162231-03B	Vial Ascorbic Acid/HCl preserved	A	NA		4.5	Y	Absent		524-THM(14)
L2162231-03C	Vial NH4Cl preserved	A	NA		4.5	Y	Absent		SUB-HAA(9)
L2162231-03D	Vial NH4Cl preserved	A	NA		4.5	Y	Absent		SUB-HAA(9)
L2162231-03E	Vial NH4Cl preserved	A	NA		4.5	Y	Absent		SUB-HAA(9)
L2162231-03F	Vial NH4Cl preserved	A	NA		4.5	Y	Absent		SUB-HAA(9)
L2162231-03G	Plastic 120ml unpreserved	A	7	7	4.5	Y	Absent		ORP(1),TRC-4500(1)
L2162231-03H	Plastic 60ml unpreserved	A	7	7	4.5	Y	Absent		PH-4500(.01)
L2162231-03I	Plastic 250ml unpreserved/No Headspace	A	NA		4.5	Y	Absent		ALK-T-2320(14)
L2162231-04A	Vial Ascorbic Acid/HCl preserved	A	NA		4.5	Y	Absent		524-THM(14)
L2162231-04B	Vial Ascorbic Acid/HCl preserved	A	NA		4.5	Y	Absent		524-THM(14)
L2162231-04C	Vial NH4Cl preserved	A	NA		4.5	Y	Absent		SUB-HAA(9)
L2162231-04D	Vial NH4Cl preserved	A	NA		4.5	Y	Absent		SUB-HAA(9)
L2162231-04E	Vial NH4Cl preserved	A	NA		4.5	Y	Absent		SUB-HAA(9)
L2162231-04F	Vial NH4Cl preserved	A	NA		4.5	Y	Absent		SUB-HAA(9)

**Project Name:** PRUDENCE ISLAND

**Project Number:** 119-21-01

Serial\_No:11292116:05

**Lab Number:** L2162231

**Report Date:** 11/29/21

**Container Information**

<b>Container ID</b>	<b>Container Type</b>	<b>Cooler</b>	<b>Initial pH</b>	<b>Final pH</b>	<b>Temp deg C</b>	<b>Pres</b>	<b>Seal</b>	<b>Frozen Date/Time</b>	<b>Analysis(*)</b>
L2162231-04G	Plastic 120ml unpreserved	A	7	7	4.5	Y	Absent		ORP(1),TRC-4500(1)
L2162231-04H	Plastic 60ml unpreserved	A	7	7	4.5	Y	Absent		PH-4500(.01)
L2162231-04I	Plastic 250ml unpreserved/No Headspace	A	NA		4.5	Y	Absent		ALK-T-2320(14)



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162231  
**Report Date:** 11/29/21

## GLOSSARY

### Acronyms

DL	- Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the limit of quantitation (LOQ). The DL includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)
EDL	- Estimated Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The EDL includes any adjustments from dilutions, concentrations or moisture content, where applicable. The use of EDLs is specific to the analysis of PAHs using Solid-Phase Microextraction (SPME).
EMPC	- Estimated Maximum Possible Concentration: The concentration that results from the signal present at the retention time of an analyte when the ions meet all of the identification criteria except the ion abundance ratio criteria. An EMPC is a worst-case estimate of the concentration.
EPA	- Environmental Protection Agency.
LCS	- Laboratory Control Sample: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
LCSD	- Laboratory Control Sample Duplicate: Refer to LCS.
LFB	- Laboratory Fortified Blank: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
LOD	- Limit of Detection: This value represents the level to which a target analyte can reliably be detected for a specific analyte in a specific matrix by a specific method. The LOD includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)
LOQ	- Limit of Quantitation: The value at which an instrument can accurately measure an analyte at a specific concentration. The LOQ includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)  Limit of Quantitation: The value at which an instrument can accurately measure an analyte at a specific concentration. The LOQ includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)
MDL	- Method Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The MDL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
MS	- Matrix Spike Sample: A sample prepared by adding a known mass of target analyte to a specified amount of matrix sample for which an independent estimate of target analyte concentration is available. For Method 332.0, the spike recovery is calculated using the native concentration, including estimated values.
MSD	- Matrix Spike Sample Duplicate: Refer to MS.
NA	- Not Applicable.
NC	- Not Calculated: Term is utilized when one or more of the results utilized in the calculation are non-detect at the parameter's reporting unit.
NDPA/DPA	- N-Nitrosodiphenylamine/Diphenylamine.
NI	- Not Ignitable.
NP	- Non-Plastic: Term is utilized for the analysis of Atterberg Limits in soil.
NR	- No Results: Term is utilized when 'No Target Compounds Requested' is reported for the analysis of Volatile or Semivolatile Organic TIC only requests.
RL	- Reporting Limit: The value at which an instrument can accurately measure an analyte at a specific concentration. The RL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
RPD	- Relative Percent Difference: The results from matrix and/or matrix spike duplicates are primarily designed to assess the precision of analytical results in a given matrix and are expressed as relative percent difference (RPD). Values which are less than five times the reporting limit for any individual parameter are evaluated by utilizing the absolute difference between the values; although the RPD value will be provided in the report.
SRM	- Standard Reference Material: A reference sample of a known or certified value that is of the same or similar matrix as the associated field samples.
STLP	- Semi-dynamic Tank Leaching Procedure per EPA Method 1315.
TEF	- Toxic Equivalency Factors: The values assigned to each dioxin and furan to evaluate their toxicity relative to 2,3,7,8-TCDD.
TEQ	- Toxic Equivalent: The measure of a sample's toxicity derived by multiplying each dioxin and furan by its corresponding TEF and then summing the resulting values.
TIC	- Tentatively Identified Compound: A compound that has been identified to be present and is not part of the target compound list (TCL) for the method and/or program. All TICs are qualitatively identified and reported as estimated concentrations.

Report Format: Data Usability Report



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162231  
**Report Date:** 11/29/21

#### Footnotes

- 1 - The reference for this analyte should be considered modified since this analyte is absent from the target analyte list of the original method.

#### Terms

**Analytical Method:** Both the document from which the method originates and the analytical reference method. (Example: EPA 8260B is shown as 1,8260B.) The codes for the reference method documents are provided in the References section of the Addendum.

**Difference:** With respect to Total Oxidizable Precursor (TOP) Assay analysis, the difference is defined as the Post-Treatment value minus the Pre-Treatment value.

**Final pH:** As it pertains to Sample Receipt & Container Information section of the report, Final pH reflects pH of container determined after adjustment at the laboratory, if applicable. If no adjustment required, value reflects Initial pH.

**Frozen Date/Time:** With respect to Volatile Organics in soil, Frozen Date/Time reflects the date/time at which associated Reagent Water-preserved vials were initially frozen. Note: If frozen date/time is beyond 48 hours from sample collection, value will be reflected in 'bold'.

**Initial pH:** As it pertains to Sample Receipt & Container Information section of the report, Initial pH reflects pH of container determined upon receipt, if applicable.

**PAH Total:** With respect to Alkylated PAH analyses, the 'PAHs, Total' result is defined as the summation of results for all or a subset of the following compounds: Naphthalene, C1-C4 Naphthalenes, 2-Methylnaphthalene, 1-Methylnaphthalene, Biphenyl, Acenaphthylene, Acenaphthene, Fluorene, C1-C3 Fluorenes, Phenanthrene, C1-C4 Phenanthrenes/Anthracenes, Anthracene, Fluoranthene, Pyrene, C1-C4 Fluoranthenes/Pyrenes, Benz(a)anthracene, Chrysene, C1-C4 Chrysenes, Benzo(b)fluoranthene, Benzo(j)+(k)fluoranthene, Benzo(e)pyrene, Benzo(a)pyrene, Perylene, Indeno(1,2,3-cd)pyrene, Dibenz(ah)+(ac)anthracene, Benzo(g,h,i)perylene. If a 'Total' result is requested, the results of its individual components will also be reported.

**PFAS Total:** With respect to PFAS analyses, the 'PFAS, Total (5)' result is defined as the summation of results for: PFHpA, PFHxS, PFOA, PFNA and PFOS. In addition, the 'PFAS, Total (6)' result is defined as the summation of results for: PFHpA, PFHxS, PFOA, PFNA, PFDA and PFOS. For MassDEP DW compliance analysis only, the 'PFAS, Total (6)' result is defined as the summation of results at or above the RL. Note: If a 'Total' result is requested, the results of its individual components will also be reported.

The target compound Chlordane (CAS No. 57-74-9) is reported for GC ECD analyses. Per EPA, this compound "refers to a mixture of chlordane isomers, other chlorinated hydrocarbons and numerous other components." (Reference: USEPA Toxicological Review of Chlordane, In Support of Summary Information on the Integrated Risk Information System (IRIS), December 1997.)

**Total:** With respect to Organic analyses, a 'Total' result is defined as the summation of results for individual isomers or Aroclors. If a 'Total' result is requested, the results of its individual components will also be reported. This is applicable to 'Total' results for methods 8260, 8081 and 8082.

#### Data Qualifiers

- A** - Spectra identified as "Aldol Condensates" are byproducts of the extraction/concentration procedures when acetone is introduced in the process.
- B** - The analyte was detected above the reporting limit in the associated method blank. Flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For MCP-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For DOD-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank AND the analyte was detected above one-half the reporting limit (or above the reporting limit for common lab contaminants) in the associated method blank. For NJ-Air-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte above the reporting limit. For NJ-related projects (excluding Air), flag only applies to associated field samples that have detectable concentrations of the analyte, which was detected above the reporting limit in the associated method blank or above five times the reporting limit for common lab contaminants (Phthalates, Acetone, Methylene Chloride, 2-Butanone).
- C** - Co-elution: The target analyte co-elutes with a known lab standard (i.e. surrogate, internal standards, etc.) for co-extracted analyses.
- D** - Concentration of analyte was quantified from diluted analysis. Flag only applies to field samples that have detectable concentrations of the analyte.
- E** - Concentration of analyte exceeds the range of the calibration curve and/or linear range of the instrument.
- F** - The ratio of quantifier ion response to qualifier ion response falls outside of the laboratory criteria. Results are considered to be an estimated maximum concentration.
- G** - The concentration may be biased high due to matrix interferences (i.e. co-elution) with non-target compound(s). The result should be considered estimated.
- H** - The analysis of pH was performed beyond the regulatory-required holding time of 15 minutes from the time of sample collection.
- I** - The lower value for the two columns has been reported due to obvious interference.
- J** - Estimated value. This represents an estimated concentration for Tentatively Identified Compounds (TICs).
- M** - Reporting Limit (RL) exceeds the MCP CAM Reporting Limit for this analyte.
- ND** - Not detected at the reporting limit (RL) for the sample.
- NJ** - Presumptive evidence of compound. This represents an estimated concentration for Tentatively Identified Compounds (TICs), where

Report Format: Data Usability Report



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162231  
**Report Date:** 11/29/21

**Data Qualifiers**

the identification is based on a mass spectral library search.

- P** - The RPD between the results for the two columns exceeds the method-specified criteria.
- Q** - The quality control sample exceeds the associated acceptance criteria. For DOD-related projects, LCS and/or Continuing Calibration Standard exceedences are also qualified on all associated sample results. Note: This flag is not applicable for matrix spike recoveries when the sample concentration is greater than 4x the spike added or for batch duplicate RPD when the sample concentrations are less than 5x the RL. (Metals only.)
- R** - Analytical results are from sample re-analysis.
- RE** - Analytical results are from sample re-extraction.
- S** - Analytical results are from modified screening analysis.
- V** - The surrogate associated with this target analyte has a recovery outside the QC acceptance limits. (Applicable to MassDEP DW Compliance samples only.)
- Z** - The batch matrix spike and/or duplicate associated with this target analyte has a recovery/RPD outside the QC acceptance limits. (Applicable to MassDEP DW Compliance samples only.)

**Project Name:** PRUDENCE ISLAND**Lab Number:** L2162231**Project Number:** 119-21-01**Report Date:** 11/29/21

## REFERENCES

- 12 Annual Book of ASTM Standards. (American Society for Testing and Materials) ASTM International.
- 16 Methods for the Determination of Organic Compounds in Drinking Water - Supplement II. EPA/600/R-92/129, August 1992.
- 121 Standard Methods for the Examination of Water and Wastewater. APHA-AWWA-WEF. Standard Methods Online.

## LIMITATION OF LIABILITIES

Alpha Analytical performs services with reasonable care and diligence normal to the analytical testing laboratory industry. In the event of an error, the sole and exclusive responsibility of Alpha Analytical shall be to re-perform the work at it's own expense. In no event shall Alpha Analytical be held liable for any incidental, consequential or special damages, including but not limited to, damages in any way connected with the use of, interpretation of, information or analysis provided by Alpha Analytical.

We strongly urge our clients to comply with EPA protocol regarding sample volume, preservation, cooling, containers, sampling procedures, holding time and splitting of samples in the field.





## Certification Information

The following analytes are not included in our Primary NELAP Scope of Accreditation:

### Westborough Facility

**EPA 624/624.1:** m/p-xylene, o-xylene, Naphthalene

**EPA 625/625.1:** alpha-Terpineol

**EPA 8260C/8260D:** NPW: 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene, Azobenzene; SCM: Iodomethane (methyl iodide), 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene.

**EPA 8270D/8270E:** NPW: Dimethylnaphthalene, 1,4-Diphenylhydrazine, alpha-Terpineol; SCM: Dimethylnaphthalene, 1,4-Diphenylhydrazine.

**SM4500:** NPW: Amenable Cyanide; SCM: Total Phosphorus, TKN, NO<sub>2</sub>, NO<sub>3</sub>.

### Mansfield Facility

**SM 2540D:** TSS

**EPA 8082A:** NPW: PCB: 1, 5, 31, 87,101, 110, 141, 151, 153, 180, 183, 187.

**EPA TO-15:** Halothane, 2,4,4-Trimethyl-2-pentene, 2,4,4-Trimethyl-1-pentene, Thiophene, 2-Methylthiophene,

3-Methylthiophene, 2-Ethylthiophene, 1,2,3-Trimethylbenzene, Indan, Indene, 1,2,4,5-Tetramethylbenzene, Benzothiophene, 1-Methylnaphthalene.

**Biological Tissue Matrix:** EPA 3050B

The following analytes are included in our Massachusetts DEP Scope of Accreditation

### Westborough Facility:

#### Drinking Water

**EPA 300.0:** Chloride, Nitrate-N, Fluoride, Sulfate; **EPA 353.2:** Nitrate-N, Nitrite-N; **SM4500NO3-F:** Nitrate-N, Nitrite-N; **SM4500F-C, SM4500CN-CE,**

**EPA 180.1, SM2130B, SM4500CI-D, SM2320B, SM2540C, SM4500H-B, SM4500NO2-B**

**EPA 332:** Perchlorate; **EPA 524.2:** THMs and VOCs; **EPA 504.1:** EDB, DBCP.

**Microbiology:** **SM9215B; SM9223-P/A, SM9223B-Colilert-QT, SM9222D.**

#### Non-Potable Water

**SM4500H,B, EPA 120.1, SM2510B, SM2540C, SM2320B, SM4500CL-E, SM4500F-BC, SM4500NH3-BH:** Ammonia-N and Kjeldahl-N, **EPA 350.1:**

Ammonia-N, **LCHAT 10-107-06-1-B:** Ammonia-N, **EPA 351.1, SM4500NO3-F, EPA 353.2:** Nitrate-N, **SM4500P-E, SM4500P-B, E, SM4500SO4-E,**

**SM5220D, EPA 410.4, SM5210B, SM5310C, SM4500CL-D, EPA 1664, EPA 420.1, SM4500-CN-CE, SM2540D, EPA 300:** Chloride, Sulfate, Nitrate.

**EPA 624.1:** Volatile Halocarbons & Aromatics,

**EPA 608.3:** Chlordane, Toxaphene, Aldrin, alpha-BHC, beta-BHC, gamma-BHC, delta-BHC, Dieldrin, DDD, DDE, DDT, Endosulfan I, Endosulfan II,

Endosulfan sulfate, Endrin, Endrin Aldehyde, Heptachlor, Heptachlor Epoxide, PCBs

**EPA 625.1:** SVOC (Acid/Base/Neutral Extractables), **EPA 600/4-81-045:** PCB-Oil.

**Microbiology:** **SM9223B-Colilert-QT; Enterolert-QT, SM9221E, EPA 1600, EPA 1603, SM9222D.**

### Mansfield Facility:

#### Drinking Water

**EPA 200.7:** Al, Ba, Cd, Cr, Cu, Fe, Mn, Ni, Na, Ag, Ca, Zn. **EPA 200.8:** Al, Sb, As, Ba, Be, Cd, Cr, Cu, Pb, Mn, Ni, Se, Ag, TL, Zn. **EPA 245.1 Hg.**

**EPA 522, EPA 537.1.**

#### Non-Potable Water

**EPA 200.7:** Al, Sb, As, Be, Cd, Ca, Cr, Co, Cu, Fe, Pb, Mg, Mn, Mo, Ni, K, Se, Ag, Na, Sr, TL, Ti, V, Zn.

**EPA 200.8:** Al, Sb, As, Be, Cd, Cr, Cu, Fe, Pb, Mn, Ni, K, Se, Ag, Na, TL, Zn.

**EPA 245.1 Hg.**

**SM2340B**

For a complete listing of analytes and methods, please contact your Alpha Project Manager.





H<sub>2</sub>O

# CHAIN OF CUSTODY

PAGE 1 OF 1

8 Walkup Drive  
Westboro, MA 01581  
Tel: 508-898-9220

320 Forbes Blvd  
Mansfield, MA 02048  
Tel: 508-822-9300

Date Rec'd in Lab: 11/11/21

ALPHA Job #: L2162231

### Project Information

Project Name: Prudence Island  
Project Location: Prudence Island  
Project #: 119-21-01  
Project Manager: Steve Olson  
ALPHA Quote #:

### Report Information - Data Deliverables

ADEX  EMAIL

### Billing Information

Same as Client info PO #:

### Client Information

Client: H<sub>2</sub>O Olson Engineering  
Address: 10 Riverside Drive  
Suite 103  
Phone: 508-375-7007  
Email: sco@h2o-olson-engineering.com  
Lakerville, MA 02043  
Additional Project Information:

### Turn-Around Time

Standard  RUSH (only confirmed if pre-approved)  
Date Due:

### Regulatory Requirements & Project Information Requirements

Yes  No MA MCP Analytical Methods  Yes  No CT RCP Analytical Methods  
 Yes  No Matrix Spike Required on this SDG? (Required for MCP Inorganics)  
 Yes  No GW1 Standards (Info Required for Metals & EPH with Targets)  
 Yes  No NPDES RGP  
 Other State /Fed Program \_\_\_\_\_ Criteria \_\_\_\_\_

ANALYSIS		SAMPLE INFO	
VOC: <input type="checkbox"/> 8260 <input type="checkbox"/> 624 <input type="checkbox"/> 524.2	<input type="checkbox"/> ABN <input type="checkbox"/> PAH	Filtration	<input type="checkbox"/> Field <input type="checkbox"/> Lab to do
METALS: <input type="checkbox"/> MCP 13 <input type="checkbox"/> MCP 14 <input type="checkbox"/> RCP 15	<input type="checkbox"/> RCRAS <input type="checkbox"/> RCR48 <input type="checkbox"/> PP13	Preservation	<input type="checkbox"/> Lab to do
EPH: <input type="checkbox"/> Ranges & Targets <input type="checkbox"/> Ranges Only	<input type="checkbox"/> Ranges & Targets <input type="checkbox"/> Ranges Only		
TPH: <input type="checkbox"/> Quant Only <input type="checkbox"/> Fingerprint	<input type="checkbox"/> Chlorine		
	pH		
	ORP		
	Alkalinity		
	TOC		
	TTTHMS		
	HAA5s		

ALPHA Lab ID (Lab Use Only)	Sample ID	Collection		Sample Matrix	Sampler Initials	ANALYSIS	SAMPLE INFO	Sample Comments	TOTAL # BOTTLES
		Date	Time						
62231-01	IS - Raw	11/11	1 PM	DW	SO			1:00 PM	4
-02	AC - Raw	11/11	1:15 PM	DW	SO			1:15 PM	4
-03	IS - DAYO	11/11	3 PM	DW	SO			3:00 PM	11
-04	AC - DAYO	11/11	3:30 PM	DW	SO			3:30 PM	11
								↑ Sample Times NOT on Labels	

**Container Type**  
P= Plastic  
A= Amber glass  
V= Vial  
G= Glass  
B= Bacteria cup  
C= Cube  
O= Other  
E= Encore  
D= BOD Bottle

**Preservative**  
A= None  
B= HCl  
C= HNO<sub>3</sub>  
D= H<sub>2</sub>SO<sub>4</sub>  
E= NaOH  
F= MeOH  
G= NaHSO<sub>4</sub>  
H= Na<sub>2</sub>S<sub>2</sub>O<sub>3</sub>  
I= Ascorbic Acid  
J= NH<sub>4</sub>Cl  
K= Zn Acetate  
O= Other

Container Type	P	P	P	P	V	V	V
Preservative	-	-	-	-	D	I	I

Relinquished By: [Signature] Date/Time: 11/11/21 4 PM / 11/11/21 18:00  
Received By: Rob Maerz Date/Time: 11/11/21 16:00

All samples submitted are subject to Alpha's Terms and Conditions. See reverse side.  
FORM NO: 01-01 (rev. 12-Mar-2012)





# GRANITE STATE ANALYTICAL SERVICES, LLC.

22 Manchester Road, Unit 2, Derry, NH 03038  
Phone (800) 699-9920 | (603) 432-3044 website www.granitestateanalytical.com

## Laboratory Report

Alpha Analytical-Westborough  
8 Walkup Dr.  
Westborough, MA 01581

Date Printed: 11/24/2021  
Work Order #: 2111-02054  
Client Job #:  
Date Received: 11/12/2021  
Sample collected in: Massachusetts

Attached please find results for the analysis of the samples received on the date referenced above.

Unless otherwise noted in the attached report, the analyses performed met the requirements of the analyzing laboratory's Quality Assurance Plan, Standard Operating Procedures and State Accreditation. This certificate shall not be reproduced, except in full, without the written approval of the analyzing laboratory. The results presented in this report relate to the samples listed on the following pages in the condition in which they were received. Accreditation for each analyte is identified by the \* symbol following the analyte name. Location of our analyzing laboratory is identified by the code in the Analyst Column.

**A & L Laboratory:**

*Identified by ME in Analyst Column*  
155 Center Street, Auburn, Maine 04210  
www.allaboratory.com

**Granite State Analytical Services LLC:**

*Identified by NH in Analyst Column*  
22 Manchester Road, Derry, NH 03038  
www.granitestateanalytical.com

**ANALYSIS RELATED NOTES:**

- RL: "Reporting limit" means the lowest level of an analyte that can be accurately recovered from the matrix of interest.
- A & L Laboratory / Granite State Analytical Services LLC. accreditation lists can be found on our websites listed above.
- Subcontracted samples will be identified by the Accreditation number of the subcontract laboratory in the analyst field for each analyte and the appropriate laboratory will be listed here. **None**
- Data Qualifiers (DQ) Flags provide additional information in regards to the receipt, analysis or quality control of a sample. These are indicated under the DQ Flags Column on your report and listed here if necessary: **Data Qualifier (DQ) Flags: None**

**SAMPLE STATE SPECIFIC NOTES:**

Additional Narrative or Comments: **None**

We appreciate the opportunity to provide you with laboratory services. If you have any questions regarding the enclosed report, please contact the laboratory and we will be happy to assist you.

Donald A. D'Anjou, Ph. D.  
Laboratory Director



# GRANITE STATE ANALYTICAL SERVICES, LLC.

Serial\_No:11292116:05

22 Manchester Road, Unit 2, Derry, NH 03038  
Phone (800) 699-9920 | (603) 432-3044 website www.granitestateanalytical.com

## CERTIFICATE OF ANALYSIS FOR DRINKING WATER

**DATE PRINTED:** 11/24/2021  
**CLIENT NAME:** Alpha Analytical-Westborough  
**CLIENT ADDRESS:** 8 Walkup Dr.  
Westborough, MA 01581

**SAMPLE ID #:** 2111-02054-001  
**SAMPLED BY:** Alpha Analytical-Westborough

**SAMPLE ADDRESS:** L2162231  
IS-DAYO  
MA

Legend	
Passes	✓
Fails EPA Primary	⊗
Fails EPA Secondary	▽
Fails State Guideline	✕
Attention	⚠

**DATE AND TIME COLLECTED:** 11/11/2021 03:00PM  
**DATE AND TIME RECEIVED:** 11/12/2021 01:51PM  
**ANALYSIS PACKAGE:** HAA GSA  
**RECEIPT TEMPERATURE:** ON ICE .5° CELSIUS

### MORE LOC INFO:

### CLIENT JOB #:

Test Description	Result	Test Units	Pass /Fail	DQ Flag	RL	Limit	Method	Analyst	Date - Time Analyzed
Date Extracted	-					No Limit	EPA 552.2	GQ-NH	11/18/2021 04:11PM
Dibromoacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 02:08AM
Dichloroacetic Acid*	1.8	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 02:08AM
Monobromoacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 02:08AM
Monochloroacetic Acid*	<2	ug/L			2	No Limit	EPA 552.2	KV-NH	11/20/2021 02:08AM
Total Haloacetic Acids*	1.8	ug/L	✓		1	60 ug/L	EPA 552.2	KV-NH	11/20/2021 02:08AM
Trichloroacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 02:08AM
2,3-Dibromopropionic Acid	74	%	✓			70-130%	EPA 552.2 - SS	KV-NH	11/20/2021 02:08AM

Donald A. D'Anjou, Ph. D.  
Laboratory Director



# GRANITE STATE ANALYTICAL SERVICES, LLC.

22 Manchester Road, Unit 2, Derry, NH 03038  
 Phone (800) 699-9920 | (603) 432-3044 website www.granitestateanalytical.com

## CERTIFICATE OF ANALYSIS FOR DRINKING WATER

**DATE PRINTED:** 11/24/2021  
**CLIENT NAME:** Alpha Analytical-Westborough  
**CLIENT ADDRESS:** 8 Walkup Dr.  
 Westborough, MA 01581

**SAMPLE ID #:** 2111-02054-002  
**SAMPLED BY:** Alpha Analytical-Westborough

**SAMPLE ADDRESS:** L2162231  
 AC-DAYO  
 MA

Legend	
Passes	✓
Fails EPA Primary	⊗
Fails EPA Secondary	⚠
Fails State Guideline	✗
Attention	⚠

**DATE AND TIME COLLECTED:** 11/11/2021 03:30PM  
**DATE AND TIME RECEIVED:** 11/12/2021 01:51PM  
**ANALYSIS PACKAGE:** HAA GSA  
**RECEIPT TEMPERATURE:** ON ICE .5° CELSIUS

**MORE LOC INFO:**

**CLIENT JOB #:**

Test Description	Result	Test Units	Pass /Fail	DQ Flag	RL	Limit	Method	Analyst	Date - Time Analyzed
Date Extracted	-					No Limit	EPA 552.2	GQ-NH	11/18/2021 04:11PM
Dibromoacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 02:48AM
Dichloroacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 02:48AM
Monobromoacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 02:48AM
Monochloroacetic Acid*	<2	ug/L			2	No Limit	EPA 552.2	KV-NH	11/20/2021 02:48AM
Total Haloacetic Acids*	<1	ug/L	✓		1	60 ug/L	EPA 552.2	KV-NH	11/20/2021 02:48AM
Trichloroacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 02:48AM
2,3-Dibromopropionic Acid	87	%	✓			70-130%	EPA 552.2 - SS	KV-NH	11/20/2021 02:48AM

Donald A. D'Anjou, Ph. D.  
 Laboratory Director



## ANALYTICAL REPORT

Lab Number:	L2162696
Client:	H2Olson Engineering, Inc. 10 Riverside Drive, Suite 103 Lakeville, MA 02347
ATTN:	Stephen Olson
Phone:	(508) 375-7007
Project Name:	PRUDENCE ISLAND
Project Number:	119-21-01
Report Date:	12/01/21

The original project report/data package is held by Alpha Analytical. This report/data package is paginated and should be reproduced only in its entirety. Alpha Analytical holds no responsibility for results and/or data that are not consistent with the original.

Certifications & Approvals: MA (M-MA086), NH NELAP (2064), CT (PH-0574), IL (200077), ME (MA00086), MD (348), NJ (MA935), NY (11148), NC (25700/666), PA (68-03671), RI (LAO00065), TX (T104704476), VT (VT-0935), VA (460195), USDA (Permit #P330-17-00196).

---

Eight Walkup Drive, Westborough, MA 01581-1019  
508-898-9220 (Fax) 508-898-9193 800-624-9220 - [www.alphalab.com](http://www.alphalab.com)





**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162696  
**Report Date:** 12/01/21

<b>Alpha Sample ID</b>	<b>Client ID</b>	<b>Matrix</b>	<b>Sample Location</b>	<b>Collection Date/Time</b>	<b>Receive Date</b>
L2162696-01	IS-DAY3	DW	PRUDENCE	11/14/21 15:30	11/15/21
L2162696-02	AC-DAY3	DW	PRUDENCE	11/14/21 15:30	11/15/21
L2162696-03	IS #2 RAW	DW	PRUDENCE	11/14/21 16:00	11/15/21



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162696  
**Report Date:** 12/01/21

### Case Narrative

The samples were received in accordance with the Chain of Custody and no significant deviations were encountered during the preparation or analysis unless otherwise noted. Sample Receipt, Container Information, and the Chain of Custody are located at the back of the report.

Results contained within this report relate only to the samples submitted under this Alpha Lab Number and meet NELAP requirements for all NELAP accredited parameters unless otherwise noted in the following narrative. The data presented in this report is organized by parameter (i.e. VOC, SVOC, etc.). Sample specific Quality Control data (i.e. Surrogate Spike Recovery) is reported at the end of the target analyte list for each individual sample, followed by the Laboratory Batch Quality Control at the end of each parameter. Tentatively Identified Compounds (TICs), if requested, are reported for compounds identified to be present and are not part of the method/program Target Compound List, even if only a subset of the TCL are being reported. If a sample was re-analyzed or re-extracted due to a required quality control corrective action and if both sets of data are reported, the Laboratory ID of the re-analysis or re-extraction is designated with an "R" or "RE", respectively.

When multiple Batch Quality Control elements are reported (e.g. more than one LCS), the associated samples for each element are noted in the grey shaded header line of each data table. Any Laboratory Batch, Sample Specific % recovery or RPD value that is outside the listed Acceptance Criteria is bolded in the report. In reference to questions H (CAM) or 4 (RCP) when "NO" is checked, the performance criteria for CAM and RCP methods allow for some quality control failures to occur and still be within method compliance. In these instances, the specific failure is not narrated but noted in the associated QC Outlier Summary Report, located directly after the Case Narrative. QC information is also incorporated in the Data Usability Assessment table (Format 11) of our Data Merger tool, where it can be reviewed in conjunction with the sample result, associated regulatory criteria and any associated data usability implications.

Soil/sediments, solids and tissues are reported on a dry weight basis unless otherwise noted. Definitions of all data qualifiers and acronyms used in this report are provided in the Glossary located at the back of the report.

**HOLD POLICY** - For samples submitted on hold, Alpha's policy is to hold samples (with the exception of Air canisters) free of charge for 21 calendar days from the date the project is completed. After 21 calendar days, we will dispose of all samples submitted including those put on hold unless you have contacted your Alpha Project Manager and made arrangements for Alpha to continue to hold the samples. Air canisters will be disposed after 3 business days from the date the project is completed.

Please contact Project Management at 800-624-9220 with any questions.

---

**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162696  
**Report Date:** 12/01/21

### Case Narrative (continued)

#### Report Submission

The analysis of HAAs was subcontracted. A copy of the laboratory report is included as an addendum. Please note: This data is only available in PDF format and is not available on Data Merger.

#### Sample Receipt

L2162696-03: The collection date and time on the chain of custody was 14-NOV-21 16:00; however, the collection date/time on the container label was 14-NOV-21 15:30. At the client's request, the collection date/time is reported as 14-NOV-21 16:00.

#### Chlorine, Total Residual


L2162696-01 and -02: The sample was analyzed with the method required holding time exceeded.  
WG1572235: A Matrix Spike and Laboratory Duplicate could not be performed due to insufficient sample volume available for analysis.

#### Oxidation/Reduction Potential

L2162696-01, -02, and -03: The sample was analyzed with the method required holding time exceeded.

I, the undersigned, attest under the pains and penalties of perjury that, to the best of my knowledge and belief and based upon my personal inquiry of those responsible for providing the information contained in this analytical report, such information is accurate and complete. This certificate of analysis is not complete unless this page accompanies any and all pages of this report.

Authorized Signature:

 Kelly Stenstrom

Title: Technical Director/Representative

Date: 12/01/21

# ORGANICS



# VOLATILES





**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162696  
**Report Date:** 12/01/21

**SAMPLE RESULTS**

Lab ID: L2162696-01  
 Client ID: IS-DAY3  
 Sample Location: PRUDENCE

Date Collected: 11/14/21 15:30  
 Date Received: 11/15/21  
 Field Prep: Not Specified

Sample Depth:

Matrix: Dw  
 Analytical Method: 16,524.2  
 Analytical Date: 11/16/21 14:27  
 Analyst: NLK

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by GC/MS - Westborough Lab</b>						
Chloroform	0.62		ug/l	0.50	--	1
Bromodichloromethane	0.96		ug/l	0.50	--	1
Dibromochloromethane	0.95		ug/l	0.50	--	1
Bromoform	ND		ug/l	0.50	--	1
THMs, Total	2.5		ug/l	0.50	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichlorobenzene-d4	103		80-120
4-Bromofluorobenzene	97		80-120

**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162696  
**Report Date:** 12/01/21

**SAMPLE RESULTS**

Lab ID: L2162696-02  
 Client ID: AC-DAY3  
 Sample Location: PRUDENCE

Date Collected: 11/14/21 15:30  
 Date Received: 11/15/21  
 Field Prep: Not Specified

Sample Depth:

Matrix: Dw  
 Analytical Method: 16,524.2  
 Analytical Date: 11/16/21 14:55  
 Analyst: NLK

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by GC/MS - Westborough Lab</b>						
Chloroform	1.3		ug/l	0.50	--	1
Bromodichloromethane	1.4		ug/l	0.50	--	1
Dibromochloromethane	1.0		ug/l	0.50	--	1
Bromoform	ND		ug/l	0.50	--	1
THMs, Total	3.7		ug/l	0.50	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichlorobenzene-d4	104		80-120
4-Bromofluorobenzene	96		80-120

**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162696  
**Report Date:** 12/01/21

**Method Blank Analysis**  
**Batch Quality Control**

Analytical Method: 16,524.2  
Analytical Date: 11/16/21 13:32  
Analyst: GT

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by GC/MS - Westborough Lab for sample(s): 01-02 Batch: WG1572447-4					
Chloroform	ND		ug/l	0.50	--
Bromodichloromethane	ND		ug/l	0.50	--
Dibromochloromethane	ND		ug/l	0.50	--
Bromoform	ND		ug/l	0.50	--
THMs, Total	ND		ug/l	0.50	--

Surrogate	%Recovery	Qualifier	Acceptance Criteria
1,2-Dichlorobenzene-d4	102		80-120
4-Bromofluorobenzene	95		80-120



## Lab Control Sample Analysis

Batch Quality Control

Project Name: PRUDENCE ISLAND

Lab Number: L2162696

Project Number: 119-21-01

Report Date: 12/01/21

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-02 Batch: WG1572447-3								
Chloroform	88		-		70-130	-		20
Bromodichloromethane	78		-		70-130	-		20
Dibromochloromethane	75		-		70-130	-		20
Bromoform	100		-		70-130	-		20

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria
1,2-Dichlorobenzene-d4	100				80-120
4-Bromofluorobenzene	101				80-120

## Matrix Spike Analysis

*Batch Quality Control*

**Project Name:** PRUDENCE ISLAND

**Lab Number:** L2162696

**Project Number:** 119-21-01

**Report Date:** 12/01/21

<i>Parameter</i>	<i>Native Sample</i>	<i>MS Added</i>	<i>MS Found</i>	<i>MS %Recovery</i>	<i>Qual</i>	<i>MSD Found</i>	<i>MSD %Recovery</i>	<i>Qual</i>	<i>Recovery Limits</i>	<i>RPD</i>	<i>Qual</i>	<i>RPD Limits</i>
Volatile Organics by GC/MS - Westborough Lab    Associated sample(s): 01-02    QC Batch ID: WG1572447-6    QC Sample: L2161603-03    Client ID: MS Sample												
Dichlorodifluoromethane	ND	4	7.2	180	Q	-	-		70-130	-		20
Chloromethane	ND	4	6.4	160	Q	-	-		70-130	-		20
Vinyl chloride	ND	4	7.1	178	Q	-	-		70-130	-		20
Bromomethane	ND	4	4.2	105		-	-		70-130	-		20
Chloroethane	ND	4	5.4	135	Q	-	-		70-130	-		20
Trichlorofluoromethane	ND	4	5.0	125		-	-		70-130	-		20
1,1-Dichloroethene	ND	4	5.1	128		-	-		70-130	-		20
Methylene chloride	ND	4	4.9	123		-	-		70-130	-		20
Methyl tert butyl ether	ND	4	4.0	100		-	-		70-130	-		20
trans-1,2-Dichloroethene	ND	4	4.8	120		-	-		70-130	-		20
1,1-Dichloroethane	ND	4	4.8	120		-	-		70-130	-		20
2,2-Dichloropropane	ND	4	4.4	110		-	-		70-130	-		20
cis-1,2-Dichloroethene	ND	4	4.7	118		-	-		70-130	-		20
Chloroform	ND	4	4.5	113		-	-		70-130	-		20
Bromochloromethane	ND	4	5.3	133	Q	-	-		70-130	-		20
1,1,1-Trichloroethane	ND	4	4.4	110		-	-		70-130	-		20
1,1-Dichloropropene	ND	4	4.7	118		-	-		70-130	-		20
Carbon tetrachloride	ND	4	4.2	105		-	-		70-130	-		20
1,2-Dichloroethane	ND	4	4.8	120		-	-		70-130	-		20
Benzene	ND	4	4.5	113		-	-		70-130	-		20
Trichloroethene	ND	4	3.9	98		-	-		70-130	-		20
1,2-Dichloropropane	ND	4	4.5	113		-	-		70-130	-		20
Bromodichloromethane	ND	4	4.1	103		-	-		70-130	-		20
Dibromomethane	ND	4	4.1	103		-	-		70-130	-		20

## Matrix Spike Analysis

*Batch Quality Control*

**Project Name:** PRUDENCE ISLAND

**Lab Number:** L2162696

**Project Number:** 119-21-01

**Report Date:** 12/01/21

<b>Parameter</b>	<b>Native Sample</b>	<b>MS Added</b>	<b>MS Found</b>	<b>MS %Recovery</b>	<b>Qual</b>	<b>MSD Found</b>	<b>MSD %Recovery</b>	<b>Qual</b>	<b>Recovery Limits</b>	<b>RPD</b>	<b>Qual</b>	<b>RPD Limits</b>
Volatile Organics by GC/MS - Westborough Lab    Associated sample(s): 01-02    QC Batch ID: WG1572447-6    QC Sample: L2161603-03    Client ID: MS Sample												
cis-1,3-Dichloropropene	ND	4	3.9	98		-	-		70-130	-		20
Toluene	ND	4	3.9	98		-	-		70-130	-		20
trans-1,3-Dichloropropene	ND	4	3.8	95		-	-		70-130	-		20
1,1,2-Trichloroethane	ND	4	4.0	100		-	-		70-130	-		20
1,3-Dichloropropane	ND	4	4.0	100		-	-		70-130	-		20
Tetrachloroethene	ND	4	3.8	95		-	-		70-130	-		20
Dibromochloromethane	ND	4	3.6	90		-	-		70-130	-		20
1,2-Dibromoethane	ND	4	3.8	95		-	-		70-130	-		20
Chlorobenzene	ND	4	4.5	113		-	-		70-130	-		20
1,1,1,2-Tetrachloroethane	ND	4	4.6	115		-	-		70-130	-		20
Ethylbenzene	ND	4	4.7	118		-	-		70-130	-		20
p/m-Xylene	ND	8	9.5	119		-	-		70-130	-		20
o-Xylene	ND	4	4.4	110		-	-		70-130	-		20
Styrene	ND	4	3.9	98		-	-		70-130	-		20
Isopropylbenzene	ND	4	4.4	110		-	-		70-130	-		20
Bromoform	ND	4	4.0	100		-	-		70-130	-		20
1,1,1,2,2-Tetrachloroethane	ND	4	4.8	120		-	-		70-130	-		20
1,2,3-Trichloropropane	ND	4	4.4	110		-	-		70-130	-		20
n-Propylbenzene	ND	4	4.7	118		-	-		70-130	-		20
Bromobenzene	ND	4	4.8	120		-	-		70-130	-		20
1,3,5-Trimethylbenzene	ND	4	4.4	110		-	-		70-130	-		20
o-Chlorotoluene	ND	4	4.9	123		-	-		70-130	-		20
p-Chlorotoluene	ND	4	4.6	115		-	-		70-130	-		20
tert-Butylbenzene	ND	4	4.5	113		-	-		70-130	-		20

## Matrix Spike Analysis

*Batch Quality Control*

**Project Name:** PRUDENCE ISLAND

**Lab Number:** L2162696

**Project Number:** 119-21-01

**Report Date:** 12/01/21

<i>Parameter</i>	<i>Native Sample</i>	<i>MS Added</i>	<i>MS Found</i>	<i>MS %Recovery</i>	<i>Qual</i>	<i>MSD Found</i>	<i>MSD %Recovery</i>	<i>Qual</i>	<i>Recovery Limits</i>	<i>RPD</i>	<i>Qual</i>	<i>RPD Limits</i>
Volatile Organics by GC/MS - Westborough Lab    Associated sample(s): 01-02    QC Batch ID: WG1572447-6    QC Sample: L2161603-03    Client ID: MS Sample												
1,2,4-Trimethylbenzene	ND	4	4.7	118		-	-		70-130	-		20
sec-Butylbenzene	ND	4	4.7	118		-	-		70-130	-		20
p-Isopropyltoluene	ND	4	4.5	113		-	-		70-130	-		20
1,3-Dichlorobenzene	ND	4	4.6	115		-	-		70-130	-		20
1,4-Dichlorobenzene	ND	4	4.3	108		-	-		70-130	-		20
n-Butylbenzene	ND	4	4.5	113		-	-		70-130	-		20
1,2-Dichlorobenzene	ND	4	4.3	108		-	-		70-130	-		20
1,2-Dibromo-3-chloropropane	ND	4	3.8	95		-	-		70-130	-		20
1,2,4-Trichlorobenzene	ND	4	3.8	95		-	-		70-130	-		20
Hexachlorobutadiene	ND	4	4.2	105		-	-		70-130	-		20
Naphthalene	ND	4	3.2	80		-	-		70-130	-		20
1,2,3-Trichlorobenzene	ND	4	3.7	92		-	-		70-130	-		20

<i>Surrogate</i>	<i>MS % Recovery</i>	<i>MS Qualifier</i>	<i>MSD % Recovery</i>	<i>MSD Qualifier</i>	<i>Acceptance Criteria</i>
1,2-Dichlorobenzene-d4	99				80-120
4-Bromofluorobenzene	102				80-120



## Lab Duplicate Analysis

Batch Quality Control

Project Name: PRUDENCE ISLAND

Project Number: 119-21-01

Lab Number: L2162696

Report Date: 12/01/21

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-02 QC Batch ID: WG1572447-5 QC Sample: L2161603-01 Client ID: DUP Sample						
Dichlorodifluoromethane	ND	ND	ug/l	NC		20
Chloromethane	ND	ND	ug/l	NC		20
Vinyl chloride	ND	ND	ug/l	NC		20
Bromomethane	ND	ND	ug/l	NC		20
Chloroethane	ND	ND	ug/l	NC		20
Trichlorofluoromethane	ND	ND	ug/l	NC		20
1,1-Dichloroethene	ND	ND	ug/l	NC		20
Methylene chloride	ND	ND	ug/l	NC		20
Methyl tert butyl ether	ND	ND	ug/l	NC		20
trans-1,2-Dichloroethene	ND	ND	ug/l	NC		20
1,1-Dichloroethane	ND	ND	ug/l	NC		20
2,2-Dichloropropane	ND	ND	ug/l	NC		20
cis-1,2-Dichloroethene	ND	ND	ug/l	NC		20
Chloroform	ND	ND	ug/l	NC		20
Bromochloromethane	ND	ND	ug/l	NC		20
1,1,1-Trichloroethane	ND	ND	ug/l	NC		20
1,1-Dichloropropene	ND	ND	ug/l	NC		20
Carbon tetrachloride	ND	ND	ug/l	NC		20
1,2-Dichloroethane	ND	ND	ug/l	NC		20
Benzene	ND	ND	ug/l	NC		20
Trichloroethene	ND	ND	ug/l	NC		20

## Lab Duplicate Analysis

Batch Quality Control

Project Name: PRUDENCE ISLAND

Project Number: 119-21-01

Lab Number: L2162696

Report Date: 12/01/21

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-02 QC Batch ID: WG1572447-5 QC Sample: L2161603-01 Client ID: DUP Sample						
1,2-Dichloropropane	ND	ND	ug/l	NC		20
Bromodichloromethane	ND	ND	ug/l	NC		20
Dibromomethane	ND	ND	ug/l	NC		20
cis-1,3-Dichloropropene	ND	ND	ug/l	NC		20
Toluene	ND	ND	ug/l	NC		20
trans-1,3-Dichloropropene	ND	ND	ug/l	NC		20
1,1,2-Trichloroethane	ND	ND	ug/l	NC		20
1,3-Dichloropropane	ND	ND	ug/l	NC		20
Tetrachloroethene	ND	ND	ug/l	NC		20
Dibromochloromethane	ND	ND	ug/l	NC		20
1,2-Dibromoethane	ND	ND	ug/l	NC		20
Chlorobenzene	ND	ND	ug/l	NC		20
1,1,1,2-Tetrachloroethane	ND	ND	ug/l	NC		20
Ethylbenzene	ND	ND	ug/l	NC		20
p/m-Xylene	ND	ND	ug/l	NC		20
o-Xylene	ND	ND	ug/l	NC		20
Styrene	ND	ND	ug/l	NC		20
Isopropylbenzene	ND	ND	ug/l	NC		20
Bromoform	ND	ND	ug/l	NC		20
1,1,1,2-Tetrachloroethane	ND	ND	ug/l	NC		20
1,2,3-Trichloropropane	ND	ND	ug/l	NC		20

## Lab Duplicate Analysis

Batch Quality Control

Project Name: PRUDENCE ISLAND

Project Number: 119-21-01

Lab Number: L2162696

Report Date: 12/01/21

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-02 QC Batch ID: WG1572447-5 QC Sample: L2161603-01 Client ID: DUP Sample						
Xylene (Total) <sup>1</sup>	ND	ND	ug/l	NC		20
n-Propylbenzene	ND	ND	ug/l	NC		20
Bromobenzene	ND	ND	ug/l	NC		20
Trihalomethanes, Total	ND	ND	ug/l	NC		20
1,3,5-Trimethylbenzene	ND	ND	ug/l	NC		20
o-Chlorotoluene	ND	ND	ug/l	NC		20
p-Chlorotoluene	ND	ND	ug/l	NC		20
tert-Butylbenzene	ND	ND	ug/l	NC		20
1,2,4-Trimethylbenzene	ND	ND	ug/l	NC		20
sec-Butylbenzene	ND	ND	ug/l	NC		20
p-Isopropyltoluene	ND	ND	ug/l	NC		20
1,3-Dichlorobenzene	ND	ND	ug/l	NC		20
1,4-Dichlorobenzene	ND	ND	ug/l	NC		20
n-Butylbenzene	ND	ND	ug/l	NC		20
1,2-Dichlorobenzene	ND	ND	ug/l	NC		20
1,2-Dibromo-3-chloropropane	ND	ND	ug/l	NC		20
1,2,4-Trichlorobenzene	ND	ND	ug/l	NC		20
Hexachlorobutadiene	ND	ND	ug/l	NC		20
Naphthalene	ND	ND	ug/l	NC		20
1,2,3-Trichlorobenzene	ND	ND	ug/l	NC		20

## Lab Duplicate Analysis

Batch Quality Control

Project Name: PRUDENCE ISLAND

Project Number: 119-21-01

Lab Number: L2162696

Report Date: 12/01/21

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-02 QC Batch ID: WG1572447-5 QC Sample: L2161603-01 Client ID: DUP Sample						

Surrogate	%Recovery	Qualifier	%Recovery	Qualifier	Acceptance Criteria
1,2-Dichlorobenzene-d4	102		104		80-120
4-Bromofluorobenzene	96		95		80-120

# **INORGANICS & MISCELLANEOUS**



Project Name: PRUDENCE ISLAND

Lab Number: L2162696

Project Number: 119-21-01

Report Date: 12/01/21

## SAMPLE RESULTS

Lab ID: L2162696-01

Date Collected: 11/14/21 15:30

Client ID: IS-DAY3

Date Received: 11/15/21

Sample Location: PRUDENCE

Field Prep: Not Specified

Sample Depth:

Matrix: Dw

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>General Chemistry - Westborough Lab</b>										
Chlorine, Total Residual	0.30		mg/l	0.02	--	1	-	11/16/21 23:09	121,4500CL-D	AS
pH (H)	7.5		SU	-	NA	1	-	11/16/21 03:49	121,4500H+-B	KA
Oxidation/Reduction Potential	540		mv	-	NA	1	-	11/15/21 23:17	12,1498	AS



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162696  
**Report Date:** 12/01/21

**SAMPLE RESULTS**

**Lab ID:** L2162696-02  
**Client ID:** AC-DAY3  
**Sample Location:** PRUDENCE

**Date Collected:** 11/14/21 15:30  
**Date Received:** 11/15/21  
**Field Prep:** Not Specified

**Sample Depth:**  
**Matrix:** Dw

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>General Chemistry - Westborough Lab</b>										
Chlorine, Total Residual	0.25		mg/l	0.02	--	1	-	11/16/21 23:09	121,4500CL-D	AS
pH (H)	7.4		SU	-	NA	1	-	11/16/21 03:49	121,4500H+-B	KA
Oxidation/Reduction Potential	570		mv	-	NA	1	-	11/15/21 23:17	12,1498	AS





**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162696  
**Report Date:** 12/01/21

**SAMPLE RESULTS**

**Lab ID:** L2162696-03  
**Client ID:** IS #2 RAW  
**Sample Location:** PRUDENCE

**Date Collected:** 11/14/21 16:00  
**Date Received:** 11/15/21  
**Field Prep:** Not Specified

**Sample Depth:**  
**Matrix:** Dw

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>General Chemistry - Westborough Lab</b>										
Alkalinity, Total	55.2		mg CaCO3/L	2.00	NA	1	-	11/23/21 10:12	121,2320B	JB
pH (H)	7.4		SU	-	NA	1	-	11/16/21 03:49	121,4500H+-B	KA
Total Organic Carbon	ND		mg/l	0.500	--	1	-	11/30/21 12:27	121,5310C	DW
Oxidation/Reduction Potential	490		mv	-	NA	1	-	11/15/21 23:17	12,1498	AS



Project Name: PRUDENCE ISLAND

Lab Number: L2162696

Project Number: 119-21-01

Report Date: 12/01/21

**Method Blank Analysis**  
**Batch Quality Control**

Parameter	Result Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
General Chemistry - Westborough Lab for sample(s): 01-02 Batch: WG1572235-1									
Chlorine, Total Residual	ND	mg/l	0.02	--	1	-	11/16/21 23:09	121,4500CL-D	AS
General Chemistry - Westborough Lab for sample(s): 03 Batch: WG1574989-1									
Alkalinity, Total	ND	mg CaCO3/L	2.00	NA	1	-	11/23/21 10:12	121,2320B	JB
General Chemistry - Westborough Lab for sample(s): 03 Batch: WG1576924-1									
Total Organic Carbon	ND	mg/l	0.500	--	1	-	11/30/21 06:53	121,5310C	DW

## Lab Control Sample Analysis

### Batch Quality Control

Project Name: PRUDENCE ISLAND

Project Number: 119-21-01

Lab Number: L2162696

Report Date: 12/01/21

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
General Chemistry - Westborough Lab Associated sample(s): 01-03 Batch: WG1571768-1								
Oxidation/Reduction Potential	102		-		90-110	-		20
General Chemistry - Westborough Lab Associated sample(s): 01-03 Batch: WG1571795-1								
pH	100		-		99-101	-		5
General Chemistry - Westborough Lab Associated sample(s): 01-02 Batch: WG1572235-2								
Chlorine, Total Residual	104		-		90-110	-		
General Chemistry - Westborough Lab Associated sample(s): 03 Batch: WG1574989-2								
Alkalinity, Total	102		-		90-110	-		10
General Chemistry - Westborough Lab Associated sample(s): 03 Batch: WG1576924-2								
Total Organic Carbon	96		-		90-110	-		

### Matrix Spike Analysis Batch Quality Control

**Project Name:** PRUDENCE ISLAND

**Lab Number:** L2162696

**Project Number:** 119-21-01

**Report Date:** 12/01/21

Parameter	Native Sample	MS Added	MS Found	MS %Recovery	MSD Qual	MSD Found	MSD %Recovery	MSD Qual	Recovery Limits	RPD	RPD Qual	RPD Limits
General Chemistry - Westborough Lab Associated sample(s): 03 QC Batch ID: WG1574989-4 QC Sample: L2162696-03 Client ID: IS #2 RAW												
Alkalinity, Total	55.2	100	158	103	-	-	-	-	86-116	-	-	10
General Chemistry - Westborough Lab Associated sample(s): 03 QC Batch ID: WG1576924-4 QC Sample: L2161355-03 Client ID: MS Sample												
Total Organic Carbon	1.13	4	4.94	95	-	-	-	-	80-120	-	-	20

## Lab Duplicate Analysis

*Batch Quality Control*

Project Name: PRUDENCE ISLAND

Project Number: 119-21-01

Lab Number: L2162696

Report Date: 12/01/21

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
General Chemistry - Westborough Lab Associated sample(s): 01-03 QC Batch ID: WG1571768-2 QC Sample: L2162696-01 Client ID: IS-DAY3						
Oxidation/Reduction Potential	540	560	mv	4		20
General Chemistry - Westborough Lab Associated sample(s): 01-03 QC Batch ID: WG1571795-2 QC Sample: L2162696-01 Client ID: IS-DAY3						
pH (H)	7.5	7.4	SU	1		5
General Chemistry - Westborough Lab Associated sample(s): 03 QC Batch ID: WG1574989-3 QC Sample: L2162696-03 Client ID: IS #2 RAW						
Alkalinity, Total	55.2	55.3	mg CaCO3/L	0		10
General Chemistry - Westborough Lab Associated sample(s): 03 QC Batch ID: WG1576924-3 QC Sample: L2161355-02 Client ID: DUP Sample						
Total Organic Carbon	1.12	1.14	mg/l	2		20

**Project Name:** PRUDENCE ISLAND**Lab Number:** L2162696**Project Number:** 119-21-01**Report Date:** 12/01/21**Sample Receipt and Container Information**

Were project specific reporting limits specified?

YES

**Cooler Information**

<b>Cooler</b>	<b>Custody Seal</b>
A	Absent

**Container Information**

<b>Container ID</b>	<b>Container Type</b>	<b>Cooler</b>	<b>Initial pH</b>	<b>Final pH</b>	<b>Temp deg C</b>	<b>Pres</b>	<b>Seal</b>	<b>Frozen Date/Time</b>	<b>Analysis(*)</b>
L2162696-01A	Vial NH4Cl preserved	A	NA		5.8	Y	Absent		SUB-HAA(9)
L2162696-01B	Vial NH4Cl preserved	A	NA		5.8	Y	Absent		SUB-HAA(9)
L2162696-01C	Vial NH4Cl preserved	A	NA		5.8	Y	Absent		SUB-HAA(9)
L2162696-01D	Vial NH4Cl preserved	A	NA		5.8	Y	Absent		SUB-HAA(9)
L2162696-01E	Vial Ascorbic Acid/HCl preserved	A	NA		5.8	Y	Absent		524-THM(14)
L2162696-01F	Vial Ascorbic Acid/HCl preserved	A	NA		5.8	Y	Absent		524-THM(14)
L2162696-01G	Plastic 60ml unpreserved	A	7	7	5.8	Y	Absent		PH-4500(.01)
L2162696-01H	Plastic 120ml unpreserved	A	7	7	5.8	Y	Absent		ORP(1),TRC-4500(1)
L2162696-02A	Vial NH4Cl preserved	A	NA		5.8	Y	Absent		SUB-HAA(9)
L2162696-02B	Vial NH4Cl preserved	A	NA		5.8	Y	Absent		SUB-HAA(9)
L2162696-02C	Vial NH4Cl preserved	A	NA		5.8	Y	Absent		SUB-HAA(9)
L2162696-02D	Vial NH4Cl preserved	A	NA		5.8	Y	Absent		SUB-HAA(9)
L2162696-02E	Vial Ascorbic Acid/HCl preserved	A	NA		5.8	Y	Absent		524-THM(14)
L2162696-02F	Vial Ascorbic Acid/HCl preserved	A	NA		5.8	Y	Absent		524-THM(14)
L2162696-02G	Plastic 60ml unpreserved	A	7	7	5.8	Y	Absent		PH-4500(.01)
L2162696-02H	Plastic 120ml unpreserved	A	7	7	5.8	Y	Absent		ORP(1),TRC-4500(1)
L2162696-03A	Vial H2SO4 preserved	A	NA		5.8	Y	Absent		TOC-5310(28)
L2162696-03B	Vial H2SO4 preserved	A	NA		5.8	Y	Absent		TOC-5310(28)
L2162696-03C	Plastic 120ml unpreserved	A	7	7	5.8	Y	Absent		ORP(1),PH-4500(.01)
L2162696-03D	Plastic 250ml unpreserved/No Headspace	A	NA		5.8	Y	Absent		ALK-T-2320(14)

**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162696  
**Report Date:** 12/01/21

## GLOSSARY

### Acronyms

DL	- Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the limit of quantitation (LOQ). The DL includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)
EDL	- Estimated Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The EDL includes any adjustments from dilutions, concentrations or moisture content, where applicable. The use of EDLs is specific to the analysis of PAHs using Solid-Phase Microextraction (SPME).
EMPC	- Estimated Maximum Possible Concentration: The concentration that results from the signal present at the retention time of an analyte when the ions meet all of the identification criteria except the ion abundance ratio criteria. An EMPC is a worst-case estimate of the concentration.
EPA	- Environmental Protection Agency.
LCS	- Laboratory Control Sample: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
LCSD	- Laboratory Control Sample Duplicate: Refer to LCS.
LFB	- Laboratory Fortified Blank: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
LOD	- Limit of Detection: This value represents the level to which a target analyte can reliably be detected for a specific analyte in a specific matrix by a specific method. The LOD includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)
LOQ	- Limit of Quantitation: The value at which an instrument can accurately measure an analyte at a specific concentration. The LOQ includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)  Limit of Quantitation: The value at which an instrument can accurately measure an analyte at a specific concentration. The LOQ includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)
MDL	- Method Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The MDL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
MS	- Matrix Spike Sample: A sample prepared by adding a known mass of target analyte to a specified amount of matrix sample for which an independent estimate of target analyte concentration is available. For Method 332.0, the spike recovery is calculated using the native concentration, including estimated values.
MSD	- Matrix Spike Sample Duplicate: Refer to MS.
NA	- Not Applicable.
NC	- Not Calculated: Term is utilized when one or more of the results utilized in the calculation are non-detect at the parameter's reporting unit.
NDPA/DPA	- N-Nitrosodiphenylamine/Diphenylamine.
NI	- Not Ignitable.
NP	- Non-Plastic: Term is utilized for the analysis of Atterberg Limits in soil.
NR	- No Results: Term is utilized when 'No Target Compounds Requested' is reported for the analysis of Volatile or Semivolatile Organic TIC only requests.
RL	- Reporting Limit: The value at which an instrument can accurately measure an analyte at a specific concentration. The RL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
RPD	- Relative Percent Difference: The results from matrix and/or matrix spike duplicates are primarily designed to assess the precision of analytical results in a given matrix and are expressed as relative percent difference (RPD). Values which are less than five times the reporting limit for any individual parameter are evaluated by utilizing the absolute difference between the values; although the RPD value will be provided in the report.
SRM	- Standard Reference Material: A reference sample of a known or certified value that is of the same or similar matrix as the associated field samples.
STLP	- Semi-dynamic Tank Leaching Procedure per EPA Method 1315.
TEF	- Toxic Equivalency Factors: The values assigned to each dioxin and furan to evaluate their toxicity relative to 2,3,7,8-TCDD.
TEQ	- Toxic Equivalent: The measure of a sample's toxicity derived by multiplying each dioxin and furan by its corresponding TEF and then summing the resulting values.
TIC	- Tentatively Identified Compound: A compound that has been identified to be present and is not part of the target compound list (TCL) for the method and/or program. All TICs are qualitatively identified and reported as estimated concentrations.

Report Format: Data Usability Report



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162696  
**Report Date:** 12/01/21

#### Footnotes

- 1 - The reference for this analyte should be considered modified since this analyte is absent from the target analyte list of the original method.

#### Terms

**Analytical Method:** Both the document from which the method originates and the analytical reference method. (Example: EPA 8260B is shown as 1,8260B.) The codes for the reference method documents are provided in the References section of the Addendum.

**Difference:** With respect to Total Oxidizable Precursor (TOP) Assay analysis, the difference is defined as the Post-Treatment value minus the Pre-Treatment value.

**Final pH:** As it pertains to Sample Receipt & Container Information section of the report, Final pH reflects pH of container determined after adjustment at the laboratory, if applicable. If no adjustment required, value reflects Initial pH.

**Frozen Date/Time:** With respect to Volatile Organics in soil, Frozen Date/Time reflects the date/time at which associated Reagent Water-preserved vials were initially frozen. Note: If frozen date/time is beyond 48 hours from sample collection, value will be reflected in 'bold'.

**Initial pH:** As it pertains to Sample Receipt & Container Information section of the report, Initial pH reflects pH of container determined upon receipt, if applicable.

**PAH Total:** With respect to Alkylated PAH analyses, the 'PAHs, Total' result is defined as the summation of results for all or a subset of the following compounds: Naphthalene, C1-C4 Naphthalenes, 2-Methylnaphthalene, 1-Methylnaphthalene, Biphenyl, Acenaphthylene, Acenaphthene, Fluorene, C1-C3 Fluorenes, Phenanthrene, C1-C4 Phenanthrenes/Anthracenes, Anthracene, Fluoranthene, Pyrene, C1-C4 Fluoranthenes/Pyrenes, Benz(a)anthracene, Chrysene, C1-C4 Chrysenes, Benzo(b)fluoranthene, Benzo(j)+(k)fluoranthene, Benzo(e)pyrene, Benzo(a)pyrene, Perylene, Indeno(1,2,3-cd)pyrene, Dibenz(ah)+(ac)anthracene, Benzo(g,h,i)perylene. If a 'Total' result is requested, the results of its individual components will also be reported.

**PFAS Total:** With respect to PFAS analyses, the 'PFAS, Total (5)' result is defined as the summation of results for: PFHpA, PFHxS, PFOA, PFNA and PFOS. In addition, the 'PFAS, Total (6)' result is defined as the summation of results for: PFHpA, PFHxS, PFOA, PFNA, PFDA and PFOS. For MassDEP DW compliance analysis only, the 'PFAS, Total (6)' result is defined as the summation of results at or above the RL. Note: If a 'Total' result is requested, the results of its individual components will also be reported.

The target compound Chlordane (CAS No. 57-74-9) is reported for GC ECD analyses. Per EPA, this compound "refers to a mixture of chlordane isomers, other chlorinated hydrocarbons and numerous other components." (Reference: USEPA Toxicological Review of Chlordane, In Support of Summary Information on the Integrated Risk Information System (IRIS), December 1997.)

**Total:** With respect to Organic analyses, a 'Total' result is defined as the summation of results for individual isomers or Aroclors. If a 'Total' result is requested, the results of its individual components will also be reported. This is applicable to 'Total' results for methods 8260, 8081 and 8082.

#### Data Qualifiers

- A** - Spectra identified as "Aldol Condensates" are byproducts of the extraction/concentration procedures when acetone is introduced in the process.
- B** - The analyte was detected above the reporting limit in the associated method blank. Flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For MCP-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For DOD-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank AND the analyte was detected above one-half the reporting limit (or above the reporting limit for common lab contaminants) in the associated method blank. For NJ-Air-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte above the reporting limit. For NJ-related projects (excluding Air), flag only applies to associated field samples that have detectable concentrations of the analyte, which was detected above the reporting limit in the associated method blank or above five times the reporting limit for common lab contaminants (Phthalates, Acetone, Methylene Chloride, 2-Butanone).
- C** - Co-elution: The target analyte co-elutes with a known lab standard (i.e. surrogate, internal standards, etc.) for co-extracted analyses.
- D** - Concentration of analyte was quantified from diluted analysis. Flag only applies to field samples that have detectable concentrations of the analyte.
- E** - Concentration of analyte exceeds the range of the calibration curve and/or linear range of the instrument.
- F** - The ratio of quantifier ion response to qualifier ion response falls outside of the laboratory criteria. Results are considered to be an estimated maximum concentration.
- G** - The concentration may be biased high due to matrix interferences (i.e. co-elution) with non-target compound(s). The result should be considered estimated.
- H** - The analysis of pH was performed beyond the regulatory-required holding time of 15 minutes from the time of sample collection.
- I** - The lower value for the two columns has been reported due to obvious interference.
- J** - Estimated value. This represents an estimated concentration for Tentatively Identified Compounds (TICs).
- M** - Reporting Limit (RL) exceeds the MCP CAM Reporting Limit for this analyte.
- ND** - Not detected at the reporting limit (RL) for the sample.
- NJ** - Presumptive evidence of compound. This represents an estimated concentration for Tentatively Identified Compounds (TICs), where

Report Format: Data Usability Report





**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2162696  
**Report Date:** 12/01/21

#### **Data Qualifiers**

the identification is based on a mass spectral library search.

- P** - The RPD between the results for the two columns exceeds the method-specified criteria.
- Q** - The quality control sample exceeds the associated acceptance criteria. For DOD-related projects, LCS and/or Continuing Calibration Standard exceedences are also qualified on all associated sample results. Note: This flag is not applicable for matrix spike recoveries when the sample concentration is greater than 4x the spike added or for batch duplicate RPD when the sample concentrations are less than 5x the RL. (Metals only.)
- R** - Analytical results are from sample re-analysis.
- RE** - Analytical results are from sample re-extraction.
- S** - Analytical results are from modified screening analysis.
- V** - The surrogate associated with this target analyte has a recovery outside the QC acceptance limits. (Applicable to MassDEP DW Compliance samples only.)
- Z** - The batch matrix spike and/or duplicate associated with this target analyte has a recovery/RPD outside the QC acceptance limits. (Applicable to MassDEP DW Compliance samples only.)

**Project Name:** PRUDENCE ISLAND**Lab Number:** L2162696**Project Number:** 119-21-01**Report Date:** 12/01/21

## REFERENCES

- 12 Annual Book of ASTM Standards. (American Society for Testing and Materials) ASTM International.
- 16 Methods for the Determination of Organic Compounds in Drinking Water - Supplement II. EPA/600/R-92/129, August 1992.
- 121 Standard Methods for the Examination of Water and Wastewater. APHA-AWWA-WEF. Standard Methods Online.

## LIMITATION OF LIABILITIES

Alpha Analytical performs services with reasonable care and diligence normal to the analytical testing laboratory industry. In the event of an error, the sole and exclusive responsibility of Alpha Analytical shall be to re-perform the work at it's own expense. In no event shall Alpha Analytical be held liable for any incidental, consequential or special damages, including but not limited to, damages in any way connected with the use of, interpretation of, information or analysis provided by Alpha Analytical.

We strongly urge our clients to comply with EPA protocol regarding sample volume, preservation, cooling, containers, sampling procedures, holding time and splitting of samples in the field.



## Certification Information

The following analytes are not included in our Primary NELAP Scope of Accreditation:

### Westborough Facility

**EPA 624/624.1:** m/p-xylene, o-xylene, Naphthalene

**EPA 625/625.1:** alpha-Terpineol

**EPA 8260C/8260D:** NPW: 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene, Azobenzene; SCM: Iodomethane (methyl iodide), 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene.

**EPA 8270D/8270E:** NPW: Dimethylnaphthalene, 1,4-Diphenylhydrazine, alpha-Terpineol; SCM: Dimethylnaphthalene, 1,4-Diphenylhydrazine.

**SM4500:** NPW: Amenable Cyanide; SCM: Total Phosphorus, TKN, NO<sub>2</sub>, NO<sub>3</sub>.

### Mansfield Facility

**SM 2540D:** TSS

**EPA 8082A:** NPW: PCB: 1, 5, 31, 87,101, 110, 141, 151, 153, 180, 183, 187.

**EPA TO-15:** Halothane, 2,4,4-Trimethyl-2-pentene, 2,4,4-Trimethyl-1-pentene, Thiophene, 2-Methylthiophene,

3-Methylthiophene, 2-Ethylthiophene, 1,2,3-Trimethylbenzene, Indan, Indene, 1,2,4,5-Tetramethylbenzene, Benzothiophene, 1-Methylnaphthalene.

**Biological Tissue Matrix:** EPA 3050B

The following analytes are included in our Massachusetts DEP Scope of Accreditation

### Westborough Facility:

#### Drinking Water

**EPA 300.0:** Chloride, Nitrate-N, Fluoride, Sulfate; **EPA 353.2:** Nitrate-N, Nitrite-N; **SM4500NO3-F:** Nitrate-N, Nitrite-N; **SM4500F-C, SM4500CN-CE,**

**EPA 180.1, SM2130B, SM4500CI-D, SM2320B, SM2540C, SM4500H-B, SM4500NO2-B**

**EPA 332:** Perchlorate; **EPA 524.2:** THMs and VOCs; **EPA 504.1:** EDB, DBCP.

**Microbiology:** **SM9215B; SM9223-P/A, SM9223B-Colilert-QT, SM9222D.**

#### Non-Potable Water

**SM4500H,B, EPA 120.1, SM2510B, SM2540C, SM2320B, SM4500CL-E, SM4500F-BC, SM4500NH3-BH:** Ammonia-N and Kjeldahl-N, **EPA 350.1:**

Ammonia-N, **LCHAT 10-107-06-1-B:** Ammonia-N, **EPA 351.1, SM4500NO3-F, EPA 353.2:** Nitrate-N, **SM4500P-E, SM4500P-B, E, SM4500SO4-E,**

**SM5220D, EPA 410.4, SM5210B, SM5310C, SM4500CL-D, EPA 1664, EPA 420.1, SM4500-CN-CE, SM2540D, EPA 300:** Chloride, Sulfate, Nitrate.

**EPA 624.1:** Volatile Halocarbons & Aromatics,

**EPA 608.3:** Chlordane, Toxaphene, Aldrin, alpha-BHC, beta-BHC, gamma-BHC, delta-BHC, Dieldrin, DDD, DDE, DDT, Endosulfan I, Endosulfan II,

Endosulfan sulfate, Endrin, Endrin Aldehyde, Heptachlor, Heptachlor Epoxide, PCBs

**EPA 625.1:** SVOC (Acid/Base/Neutral Extractables), **EPA 600/4-81-045:** PCB-Oil.

**Microbiology:** **SM9223B-Colilert-QT; Enterolert-QT, SM9221E, EPA 1600, EPA 1603, SM9222D.**

### Mansfield Facility:

#### Drinking Water

**EPA 200.7:** Al, Ba, Cd, Cr, Cu, Fe, Mn, Ni, Na, Ag, Ca, Zn. **EPA 200.8:** Al, Sb, As, Ba, Be, Cd, Cr, Cu, Pb, Mn, Ni, Se, Ag, TL, Zn. **EPA 245.1 Hg.**

**EPA 522, EPA 537.1.**

#### Non-Potable Water

**EPA 200.7:** Al, Sb, As, Be, Cd, Ca, Cr, Co, Cu, Fe, Pb, Mg, Mn, Mo, Ni, K, Se, Ag, Na, Sr, TL, Ti, V, Zn.

**EPA 200.8:** Al, Sb, As, Be, Cd, Cr, Cu, Fe, Pb, Mn, Ni, K, Se, Ag, Na, TL, Zn.

**EPA 245.1 Hg.**

**SM2340B**

For a complete listing of analytes and methods, please contact your Alpha Project Manager.





# CHAIN OF CUSTODY

PAGE 1 OF 1

Date Rec'd in Lab: 11/15/21

ALPHA Job #: 2162696

8 Walkup Drive  
Westboro, MA 01581  
Tel: 508-898-9220

320 Forbes Blvd  
Mansfield, MA 02048  
Tel: 508-822-9300

### Project Information

Project Name: Prudence Island

Project Location: Prudence

Project #: 119.21.01

Project Manager: Steve Olson

ALPHA Quote #:

### Report Information - Data Deliverables

ADEX  EMAIL

### Billing Information

Same as Client info PO #:

### Client Information

Client: H2 Olson Engineers

Address: 10 River side

Phone: 508 375 7007

Email: sco@h2olsonengineers.com

Additional Project Information:

### Turn-Around Time

Standard  RUSH (only confirmed if pre-approved)

Date Due:

### Regulatory Requirements & Project Information Requirements

- Yes  No MA MCP Analytical Methods  Yes  No CT RCP Analytical Methods
- Yes  No Matrix Spike Required on this SDG? (Required for MCP Inorganics)
- Yes  No GW1 Standards (Info Required for Metals & EPH with Targets)
- Yes  No NPDES RGP
- Other State / Fed Program \_\_\_\_\_ Criteria \_\_\_\_\_

ANALYSIS		SAMPLE INFO	TOTAL # BOTTLES
VOC: <input type="checkbox"/> 8260 <input type="checkbox"/> 624 <input type="checkbox"/> 524.2			
SVOC: <input type="checkbox"/> ABN <input type="checkbox"/> PAH		Filtration	
METALS: <input type="checkbox"/> MCP 13 <input type="checkbox"/> MCP 14 <input type="checkbox"/> MCP 15		<input type="checkbox"/> Field	
METALS: <input type="checkbox"/> RCRA5 <input type="checkbox"/> RCRA8		<input type="checkbox"/> Lab to do	
EPH: <input type="checkbox"/> Ranges & Targets <input type="checkbox"/> Ranges Only		Preservation	
VPH: <input type="checkbox"/> Ranges & Targets <input type="checkbox"/> Ranges Only		<input type="checkbox"/> Lab to do	
PCB: <input type="checkbox"/> PEST			
TPH: <input type="checkbox"/> Quant Only <input type="checkbox"/> Fingerprint			
THMS			
HHAAS			
Chlorine - ORP			
Alkalinity			
TOC			
Sample Comments			

ALPHA Lab ID (Lab Use Only)	Sample ID	Collection		Sample Matrix	Sampler Initials
		Date	Time		
62696-01	IS - Day 3	11/14	3:30p	DW	SO
-02	AC - Day 3	11/14	3:30p	DW	SO
-03	IS #2 Raw	11/14	4:00p	DW	SO

**Container Type**  
P= Plastic  
A= Amber glass  
V= Vial  
G= Glass  
B= Bacteria cup  
C= Cube  
O= Other  
E= Encore  
D= BOD Bottle

**Preservative**  
A= None  
B= HCl  
C= HNO<sub>3</sub>  
D= H<sub>2</sub>SO<sub>4</sub>  
E= NaOH  
F= MeOH  
G= NaHSO<sub>4</sub>  
H= Na<sub>2</sub>S<sub>2</sub>O<sub>3</sub>  
I= Ascorbic Acid  
J= NH<sub>4</sub>Cl  
K= Zn Acetate  
O= Other

Container Type

Preservative

Relinquished By:

Date/Time

Received By:

Date/Time

Relinquished By: *Rob Maerls*  
Date/Time: 11/15/21 12:45  
Date/Time: 11/15/21 19:30

Received By: *Rob Maerls*  
Date/Time: 11/15/21 12:35  
Date/Time: 11/15/21 19:30

All samples submitted are subject to Alpha's Terms and Conditions. See reverse side.

FORM NO: 01-01 (rev. 12-Mar-2012)





# GRANITE STATE ANALYTICAL SERVICES, LLC.

22 Manchester Road, Unit 2, Derry, NH 03038  
Phone (800) 699-9920 | (603) 432-3044 website [www.granitestateanalytical.com](http://www.granitestateanalytical.com)

## Laboratory Report

Alpha Analytical-Westborough  
8 Walkup Dr.  
Westborough, MA 01581

Date Printed: 11/24/2021  
Work Order #: 2111-02494  
Client Job #:  
Date Received: 11/16/2021  
Sample collected in: Rhode Island

Attached please find results for the analysis of the samples received on the date referenced above.

Unless otherwise noted in the attached report, the analyses performed met the requirements of the analyzing laboratory's Quality Assurance Plan, Standard Operating Procedures and State Accreditation. This certificate shall not be reproduced, except in full, without the written approval of the analyzing laboratory. The results presented in this report relate to the samples listed on the following pages in the condition in which they were received. Accreditation for each analyte is identified by the \* symbol following the analyte name. Location of our analyzing laboratory is identified by the code in the Analyst Column.

**A & L Laboratory:**

*Identified by ME in Analyst Column*  
155 Center Street, Auburn, Maine 04210  
[www.allaboratory.com](http://www.allaboratory.com)

**Granite State Analytical Services LLC:**

*Identified by NH in Analyst Column*  
22 Manchester Road, Derry, NH 03038  
[www.granitestateanalytical.com](http://www.granitestateanalytical.com)

**ANALYSIS RELATED NOTES:**

- RL: "Reporting limit" means the lowest level of an analyte that can be accurately recovered from the matrix of interest.
- A & L Laboratory / Granite State Analytical Services LLC. accreditation lists can be found on our websites listed above.
- Subcontracted samples will be identified by the Accreditation number of the subcontract laboratory in the analyst field for each analyte and the appropriate laboratory will be listed here. **None**
- Data Qualifiers (DQ) Flags provide additional information in regards to the receipt, analysis or quality control of a sample. These are indicated under the DQ Flags Column on your report and listed here if necessary: **Data Qualifier (DQ) Flags: None**

**SAMPLE STATE SPECIFIC NOTES:**

Additional Narrative or Comments: **None**

We appreciate the opportunity to provide you with laboratory services. If you have any questions regarding the enclosed report, please contact the laboratory and we will be happy to assist you.

Donald A. D'Anjou, Ph. D.  
Laboratory Director



# GRANITE STATE ANALYTICAL SERVICES, LLC.

22 Manchester Road, Unit 2, Derry, NH 03038  
 Phone (800) 699-9920 | (603) 432-3044 website www.granitestateanalytical.com

## CERTIFICATE OF ANALYSIS FOR DRINKING WATER

**DATE PRINTED:** 11/24/2021  
**CLIENT NAME:** Alpha Analytical-Westborough  
**CLIENT ADDRESS:** 8 Walkup Dr.  
 Westborough, MA 01581

**SAMPLE ID #:** 2111-02494-001  
**SAMPLED BY:** Alpha Analytical-Westborough

**SAMPLE ADDRESS:** L2162696  
 IS-DAY3  
 RI

Legend	
Passes	✓
Fails EPA Primary	⊗
Fails EPA Secondary	▼
Fails State Guideline	✕
Attention	⚠

**DATE AND TIME COLLECTED:** 11/14/2021 03:30PM  
**DATE AND TIME RECEIVED:** 11/16/2021 04:46PM  
**ANALYSIS PACKAGE:** HAA GSA  
**RECEIPT TEMPERATURE:** ON ICE 0.9° CELSIUS

**MORE LOC INFO:**

**CLIENT JOB #:**

Test Description	Result	Test Units	Pass /Fail	DQ Flag	RL	Limit	Method	Analyst	Date - Time Analyzed
Date Extracted	-					No Limit	EPA 552.2	GQ-NH	11/18/2021 04:11PM
Dibromoacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 03:29PM
Dichloroacetic Acid*	2.1	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 03:29PM
Monobromoacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 03:29PM
Monochloroacetic Acid*	<2	ug/L			2	No Limit	EPA 552.2	KV-NH	11/20/2021 03:29PM
Total Haloacetic Acids*	2.1	ug/L	✓		1	60 ug/L	EPA 552.2	KV-NH	11/20/2021 03:29PM
Trichloroacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 03:29PM
2,3-Dibromopropionic Acid	78	%	✓			70-130%	EPA 552.2 - SS	KV-NH	11/20/2021 03:29PM

Donald A. D'Anjou, Ph. D.  
 Laboratory Director





# GRANITE STATE ANALYTICAL SERVICES, LLC.

22 Manchester Road, Unit 2, Derry, NH 03038  
 Phone (800) 699-9920 | (603) 432-3044 website www.granitestateanalytical.com

## CERTIFICATE OF ANALYSIS FOR DRINKING WATER

**DATE PRINTED:** 11/24/2021  
**CLIENT NAME:** Alpha Analytical-Westborough  
**CLIENT ADDRESS:** 8 Walkup Dr.  
 Westborough, MA 01581  
**SAMPLE ID #:** 2111-02494-002  
**SAMPLED BY:** Alpha Analytical-Westborough  
**SAMPLE ADDRESS:** L2162696  
 AC-DAY3  
 RI

Legend	
Passes	✓
Fails EPA Primary	⊗
Fails EPA Secondary	▼
Fails State Guideline	✕
Attention	⚠

**DATE AND TIME COLLECTED:** 11/14/2021 03:30PM  
**DATE AND TIME RECEIVED:** 11/16/2021 04:46PM  
**ANALYSIS PACKAGE:** HAA GSA  
**RECEIPT TEMPERATURE:** ON ICE 0.9° CELSIUS

**MORE LOC INFO:**

**CLIENT JOB #:**

Test Description	Result	Test Units	Pass /Fail	DQ Flag	RL	Limit	Method	Analyst	Date - Time Analyzed
Date Extracted	-					No Limit	EPA 552.2	GQ-NH	11/18/2021 04:11PM
Dibromoacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 04:09PM
Dichloroacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 04:09PM
Monobromoacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 04:09PM
Monochloroacetic Acid*	<2	ug/L			2	No Limit	EPA 552.2	KV-NH	11/20/2021 04:09PM
Total Haloacetic Acids*	<1	ug/L	✓		1	60 ug/L	EPA 552.2	KV-NH	11/20/2021 04:09PM
Trichloroacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	11/20/2021 04:09PM
2,3-Dibromopropionic Acid	98	%	✓			70-130%	EPA 552.2 - SS	KV-NH	11/20/2021 04:09PM

Donald A. D'Anjou, Ph. D.  
 Laboratory Director





## ANALYTICAL REPORT

Lab Number:	L2164713
Client:	H2Olson Engineering, Inc. 10 Riverside Drive, Suite 103 Lakeville, MA 02347
ATTN:	Stephen Olson
Phone:	(508) 375-7007
Project Name:	PRUDENCE ISLAND
Project Number:	119-21-01
Report Date:	12/10/21

The original project report/data package is held by Alpha Analytical. This report/data package is paginated and should be reproduced only in its entirety. Alpha Analytical holds no responsibility for results and/or data that are not consistent with the original.

Certifications & Approvals: MA (M-MA086), NH NELAP (2064), CT (PH-0574), IL (200077), ME (MA00086), MD (348), NJ (MA935), NY (11148), NC (25700/666), PA (68-03671), RI (LAO00065), TX (T104704476), VT (VT-0935), VA (460195), USDA (Permit #P330-17-00196).

---

Eight Walkup Drive, Westborough, MA 01581-1019  
508-898-9220 (Fax) 508-898-9193 800-624-9220 - [www.alphalab.com](http://www.alphalab.com)



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2164713  
**Report Date:** 12/10/21

<b>Alpha Sample ID</b>	<b>Client ID</b>	<b>Matrix</b>	<b>Sample Location</b>	<b>Collection Date/Time</b>	<b>Receive Date</b>
L2164713-01	AC-DAY 12	DW	PRUDENCE	11/23/21 10:00	11/23/21
L2164713-02	IS-DAY 12	DW	PRUDENCE	11/23/21 10:00	11/23/21
L2164713-03	AC-RAW	DW	PRUDENCE	11/23/21 10:00	11/23/21
L2164713-04	IS-RAW	DW	PRUDENCE	11/23/21 10:00	11/23/21

**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2164713  
**Report Date:** 12/10/21

### Case Narrative

The samples were received in accordance with the Chain of Custody and no significant deviations were encountered during the preparation or analysis unless otherwise noted. Sample Receipt, Container Information, and the Chain of Custody are located at the back of the report.

Results contained within this report relate only to the samples submitted under this Alpha Lab Number and meet NELAP requirements for all NELAP accredited parameters unless otherwise noted in the following narrative. The data presented in this report is organized by parameter (i.e. VOC, SVOC, etc.). Sample specific Quality Control data (i.e. Surrogate Spike Recovery) is reported at the end of the target analyte list for each individual sample, followed by the Laboratory Batch Quality Control at the end of each parameter. Tentatively Identified Compounds (TICs), if requested, are reported for compounds identified to be present and are not part of the method/program Target Compound List, even if only a subset of the TCL are being reported. If a sample was re-analyzed or re-extracted due to a required quality control corrective action and if both sets of data are reported, the Laboratory ID of the re-analysis or re-extraction is designated with an "R" or "RE", respectively.

When multiple Batch Quality Control elements are reported (e.g. more than one LCS), the associated samples for each element are noted in the grey shaded header line of each data table. Any Laboratory Batch, Sample Specific % recovery or RPD value that is outside the listed Acceptance Criteria is bolded in the report. In reference to questions H (CAM) or 4 (RCP) when "NO" is checked, the performance criteria for CAM and RCP methods allow for some quality control failures to occur and still be within method compliance. In these instances, the specific failure is not narrated but noted in the associated QC Outlier Summary Report, located directly after the Case Narrative. QC information is also incorporated in the Data Usability Assessment table (Format 11) of our Data Merger tool, where it can be reviewed in conjunction with the sample result, associated regulatory criteria and any associated data usability implications.

Soil/sediments, solids and tissues are reported on a dry weight basis unless otherwise noted. Definitions of all data qualifiers and acronyms used in this report are provided in the Glossary located at the back of the report.

**HOLD POLICY** - For samples submitted on hold, Alpha's policy is to hold samples (with the exception of Air canisters) free of charge for 21 calendar days from the date the project is completed. After 21 calendar days, we will dispose of all samples submitted including those put on hold unless you have contacted your Alpha Project Manager and made arrangements for Alpha to continue to hold the samples. Air canisters will be disposed after 3 business days from the date the project is completed.

Please contact Project Management at 800-624-9220 with any questions.

---

**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2164713  
**Report Date:** 12/10/21

**Case Narrative (continued)**

Report Submission

The HAA analysis was subcontracted. A copy of the laboratory report is included as an addendum. Please note: This data is only available in PDF format and is not available on Data Merger.

Volatile Organics by Method 524.2

The WG1576530-5 Laboratory Duplicate RPD for bromodichloromethane (24%), performed on L2164713-01, is outside the acceptance criteria. The elevated RPD has been attributed to vial discrepancy.

I, the undersigned, attest under the pains and penalties of perjury that, to the best of my knowledge and belief and based upon my personal inquiry of those responsible for providing the information contained in this analytical report, such information is accurate and complete. This certificate of analysis is not complete unless this page accompanies any and all pages of this report.

Authorized Signature:

 Cristin Walker

Title: Technical Director/Representative

Date: 12/10/21

# ORGANICS





# VOLATILES



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2164713  
**Report Date:** 12/10/21

**SAMPLE RESULTS**

Lab ID: L2164713-01  
 Client ID: AC-DAY 12  
 Sample Location: PRUDENCE

Date Collected: 11/23/21 10:00  
 Date Received: 11/23/21  
 Field Prep: Not Specified

Sample Depth:

Matrix: Dw  
 Analytical Method: 16,524.2  
 Analytical Date: 11/28/21 14:34  
 Analyst: KJD

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by GC/MS - Westborough Lab</b>						
Chloroform	2.7		ug/l	0.50	--	1
Bromodichloromethane	2.8		ug/l	0.50	--	1
Dibromochloromethane	1.7		ug/l	0.50	--	1
Bromoform	ND		ug/l	0.50	--	1
THMs, Total	7.2		ug/l	0.50	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichlorobenzene-d4	103		80-120
4-Bromofluorobenzene	98		80-120

**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2164713  
**Report Date:** 12/10/21

**SAMPLE RESULTS**

Lab ID: L2164713-02  
 Client ID: IS-DAY 12  
 Sample Location: PRUDENCE

Date Collected: 11/23/21 10:00  
 Date Received: 11/23/21  
 Field Prep: Not Specified

Sample Depth:

Matrix: Dw  
 Analytical Method: 16,524.2  
 Analytical Date: 11/28/21 15:02  
 Analyst: KJD

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by GC/MS - Westborough Lab</b>						
Chloroform	1.1		ug/l	0.50	--	1
Bromodichloromethane	1.8		ug/l	0.50	--	1
Dibromochloromethane	1.5		ug/l	0.50	--	1
Bromoform	ND		ug/l	0.50	--	1
THMs, Total	4.4		ug/l	0.50	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichlorobenzene-d4	105		80-120
4-Bromofluorobenzene	93		80-120

**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2164713  
**Report Date:** 12/10/21

**Method Blank Analysis**  
**Batch Quality Control**

Analytical Method: 16,524.2  
Analytical Date: 11/28/21 13:39  
Analyst: KJD

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by GC/MS - Westborough Lab for sample(s): 01-02 Batch: WG1576530-4					
Chloroform	ND		ug/l	0.50	--
Bromodichloromethane	ND		ug/l	0.50	--
Dibromochloromethane	ND		ug/l	0.50	--
Bromoform	ND		ug/l	0.50	--
THMs, Total	ND		ug/l	0.50	--

Surrogate	%Recovery	Qualifier	Acceptance Criteria
1,2-Dichlorobenzene-d4	104		80-120
4-Bromofluorobenzene	96		80-120

## Lab Control Sample Analysis

Batch Quality Control

Project Name: PRUDENCE ISLAND

Lab Number: L2164713

Project Number: 119-21-01

Report Date: 12/10/21

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-02 Batch: WG1576530-3								
Chloroform	90		-		70-130	-		20
Bromodichloromethane	90		-		70-130	-		20
Dibromochloromethane	75		-		70-130	-		20
Bromoform	102		-		70-130	-		20

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria
1,2-Dichlorobenzene-d4	98				80-120
4-Bromofluorobenzene	97				80-120

### Matrix Spike Analysis Batch Quality Control

**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2164713  
**Report Date:** 12/10/21

<i>Parameter</i>	<i>Native Sample</i>	<i>MS Added</i>	<i>MS Found</i>	<i>MS %Recovery</i>	<i>Qual</i>	<i>MSD Found</i>	<i>MSD %Recovery</i>	<i>Qual</i>	<i>Recovery Limits</i>	<i>RPD</i>	<i>Qual</i>	<i>RPD Limits</i>
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-02 QC Batch ID: WG1576530-6 QC Sample: L2164713-02 Client ID: IS-DAY 12												
Chloroform	1.1	4	5.6	113		-	-		70-130	-		20
Bromodichloromethane	1.8	4	5.8	100		-	-		70-130	-		20
Dibromochloromethane	1.5	4	4.9	85		-	-		70-130	-		20
Bromoform	ND	4	4.1	103		-	-		70-130	-		20

<i>Surrogate</i>	<i>MS % Recovery</i>	<i>Qualifier</i>	<i>MSD % Recovery</i>	<i>Qualifier</i>	<i>Acceptance Criteria</i>
1,2-Dichlorobenzene-d4	100				80-120
4-Bromofluorobenzene	105				80-120

## Lab Duplicate Analysis

Batch Quality Control

Project Name: PRUDENCE ISLAND

Project Number: 119-21-01

Lab Number: L2164713

Report Date: 12/10/21

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
Volatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-02 QC Batch ID: WG1576530-5 QC Sample: L2164713-01 Client ID: AC-DAY 12						
Chloroform	2.7	2.2	ug/l	20		20
Bromodichloromethane	2.8	2.2	ug/l	24	Q	20
Dibromochloromethane	1.7	1.4	ug/l	19		20
Bromoform	ND	ND	ug/l	NC		20
THMs, Total	7.2	5.8	ug/l	22	Q	20

Surrogate	%Recovery	Qualifier	%Recovery	Qualifier	Acceptance Criteria
1,2-Dichlorobenzene-d4	103		108		80-120
4-Bromofluorobenzene	98		95		80-120



# **INORGANICS & MISCELLANEOUS**



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2164713  
**Report Date:** 12/10/21

**SAMPLE RESULTS**

**Lab ID:** L2164713-01  
**Client ID:** AC-DAY 12  
**Sample Location:** PRUDENCE

**Date Collected:** 11/23/21 10:00  
**Date Received:** 11/23/21  
**Field Prep:** Not Specified

**Sample Depth:**  
**Matrix:** Dw

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>General Chemistry - Westborough Lab</b>										
Chlorine, Total Residual	0.98		mg/l	0.04	--	2	-	11/24/21 00:27	121,4500CL-D	KA
pH (H)	6.8		SU	-	NA	1	-	11/24/21 00:01	121,4500H+-B	AS
Oxidation/Reduction Potential	360		mv	-	NA	1	-	11/23/21 23:40	12,1498	AS
<b>Anions by Ion Chromatography - Westborough Lab</b>										
Chloride	14.8		mg/l	0.500	--	1	-	12/09/21 03:50	44,300.0	AT
Sulfate	7.31		mg/l	1.00	--	1	-	12/09/21 03:50	44,300.0	AT



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2164713  
**Report Date:** 12/10/21

**SAMPLE RESULTS**

**Lab ID:** L2164713-02  
**Client ID:** IS-DAY 12  
**Sample Location:** PRUDENCE

**Date Collected:** 11/23/21 10:00  
**Date Received:** 11/23/21  
**Field Prep:** Not Specified

**Sample Depth:**  
**Matrix:** Dw

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>General Chemistry - Westborough Lab</b>										
Chlorine, Total Residual	0.65		mg/l	0.04	--	2	-	11/24/21 00:27	121,4500CL-D	KA
pH (H)	6.9		SU	-	NA	1	-	11/24/21 00:01	121,4500H+-B	AS
Oxidation/Reduction Potential	410		mv	-	NA	1	-	11/23/21 23:40	12,1498	AS
<b>Anions by Ion Chromatography - Westborough Lab</b>										
Chloride	13.6		mg/l	0.500	--	1	-	12/09/21 04:01	44,300.0	AT
Sulfate	23.8		mg/l	1.00	--	1	-	12/09/21 04:01	44,300.0	AT



Project Name: PRUDENCE ISLAND

Lab Number: L2164713

Project Number: 119-21-01

Report Date: 12/10/21

**SAMPLE RESULTS**

Lab ID: L2164713-03

Date Collected: 11/23/21 10:00

Client ID: AC-RAW

Date Received: 11/23/21

Sample Location: PRUDENCE

Field Prep: Not Specified

Sample Depth:

Matrix: Dw

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>Anions by Ion Chromatography - Westborough Lab</b>										
Chloride	9.96		mg/l	0.500	--	1	-	12/08/21 21:38	44,300.0	AT
Sulfate	22.5		mg/l	1.00	--	1	-	12/08/21 21:38	44,300.0	AT



Project Name: PRUDENCE ISLAND

Lab Number: L2164713

Project Number: 119-21-01

Report Date: 12/10/21

## SAMPLE RESULTS

Lab ID: L2164713-04

Date Collected: 11/23/21 10:00

Client ID: IS-RAW

Date Received: 11/23/21

Sample Location: PRUDENCE

Field Prep: Not Specified

Sample Depth:

Matrix: Dw

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
Anions by Ion Chromatography - Westborough Lab										
Chloride	7.45		mg/l	0.500	--	1	-	12/08/21 21:49	44,300.0	AT
Sulfate	7.33		mg/l	1.00	--	1	-	12/08/21 21:49	44,300.0	AT



Project Name: PRUDENCE ISLAND

Lab Number: L2164713

Project Number: 119-21-01

Report Date: 12/10/21

**Method Blank Analysis**  
**Batch Quality Control**

Parameter	Result Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
General Chemistry - Westborough Lab for sample(s): 01-02 Batch: WG1575339-1									
Chlorine, Total Residual	ND	mg/l	0.02	--	1	-	11/24/21 00:27	121,4500CL-D	KA
Anions by Ion Chromatography - Westborough Lab for sample(s): 01-04 Batch: WG1580925-1									
Sulfate	ND	mg/l	1.00	--	1	-	12/08/21 17:15	44,300.0	AT
Anions by Ion Chromatography - Westborough Lab for sample(s): 01-04 Batch: WG1580925-1									
Chloride	ND	mg/l	0.500	--	1	-	12/08/21 17:15	44,300.0	AT

## Lab Control Sample Analysis

Batch Quality Control

Project Name: PRUDENCE ISLAND

Project Number: 119-21-01

Lab Number: L2164713

Report Date: 12/10/21

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
General Chemistry - Westborough Lab Associated sample(s): 01-02 Batch: WG1575324-1								
Oxidation/Reduction Potential	103		-		90-110	-		20
General Chemistry - Westborough Lab Associated sample(s): 01-02 Batch: WG1575326-1								
pH	100		-		99-101	-		5
General Chemistry - Westborough Lab Associated sample(s): 01-02 Batch: WG1575339-2								
Chlorine, Total Residual	96		-		90-110	-		
Anions by Ion Chromatography - Westborough Lab Associated sample(s): 01-04 Batch: WG1580925-2								
Chloride	101		-		90-110	-		
Sulfate	96		-		90-110	-		



### Matrix Spike Analysis Batch Quality Control

**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2164713  
**Report Date:** 12/10/21

Parameter	Native Sample	MS Added	MS Found	MS %Recovery	MSD Qual	MSD Found	MSD %Recovery	MSD Qual	Recovery Limits	RPD	RPD Qual	RPD Limits
General Chemistry - Westborough Lab Associated sample(s): 01-02 QC Batch ID: WG1575339-4 QC Sample: L2164681-01 Client ID: MS Sample												
Chlorine, Total Residual	2.3	2.5	4.5	86	-	-	-	-	80-120	-	-	20
Anions by Ion Chromatography - Westborough Lab Associated sample(s): 01-04 QC Batch ID: WG1580925-3 QC Sample: L2164713-04 Client ID: IS-RAW												
Chloride	7.45	4	11.3	96	-	-	-	-	90-110	-	-	18
Sulfate	7.33	8	15.2	98	-	-	-	-	90-110	-	-	20

## Lab Duplicate Analysis

*Batch Quality Control*

Project Name: PRUDENCE ISLAND

Project Number: 119-21-01

Lab Number: L2164713

Report Date: 12/10/21

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
General Chemistry - Westborough Lab Associated sample(s): 01-02 QC Batch ID: WG1575324-2 QC Sample: L2164713-01 Client ID: AC-DAY 12						
Oxidation/Reduction Potential	360	360	mv	0		20
General Chemistry - Westborough Lab Associated sample(s): 01-02 QC Batch ID: WG1575326-2 QC Sample: L2164713-01 Client ID: AC-DAY 12						
pH (H)	6.8	6.7	SU	1		5
General Chemistry - Westborough Lab Associated sample(s): 01-02 QC Batch ID: WG1575339-3 QC Sample: L2164664-01 Client ID: DUP Sample						
Chlorine, Total Residual	3.2	3.1	mg/l	3		20
Anions by Ion Chromatography - Westborough Lab Associated sample(s): 01-04 QC Batch ID: WG1580925-4 QC Sample: L2164713-04 Client ID: IS-RAW						
Chloride	7.45	7.58	mg/l	2		18
Sulfate	7.33	7.51	mg/l	2		20

**Project Name:** PRUDENCE ISLAND**Lab Number:** L2164713**Project Number:** 119-21-01**Report Date:** 12/10/21**Sample Receipt and Container Information**

Were project specific reporting limits specified?

YES

**Cooler Information**

<b>Cooler</b>	<b>Custody Seal</b>
A	Absent

**Container Information**

<b>Container ID</b>	<b>Container Type</b>	<b>Cooler</b>	<b>Initial pH</b>	<b>Final pH</b>	<b>Temp deg C</b>	<b>Pres</b>	<b>Seal</b>	<b>Frozen Date/Time</b>	<b>Analysis(*)</b>
L2164713-01A	Vial NH4Cl preserved	A	NA	NA	2.3	Y	Absent		SUB-HAA(9)
L2164713-01B	Vial NH4Cl preserved	A	NA	NA	2.3	Y	Absent		SUB-HAA(9)
L2164713-01C	Vial NH4Cl preserved	A	NA	NA	2.3	Y	Absent		SUB-HAA(9)
L2164713-01D	Vial NH4Cl preserved	A	NA	NA	2.3	Y	Absent		SUB-HAA(9)
L2164713-01E	Vial Ascorbic Acid/HCl preserved	A	NA		2.3	Y	Absent		524-THM(14)
L2164713-01F	Vial Ascorbic Acid/HCl preserved	A	NA		2.3	Y	Absent		524-THM(14)
L2164713-01G	Plastic 120ml unpreserved	A	7	7	2.3	Y	Absent		SO4-300(28)
L2164713-01H	Plastic 250ml unpreserved	A	7	7	2.3	Y	Absent		ORP(1),TRC-4500(1),PH-4500(.01)
L2164713-01I	Plastic 500ml unpreserved	A	7	7	2.3	Y	Absent		CL-300(28)
L2164713-02A	Vial NH4Cl preserved	A	NA	NA	2.3	Y	Absent		SUB-HAA(9)
L2164713-02B	Vial NH4Cl preserved	A	NA	NA	2.3	Y	Absent		SUB-HAA(9)
L2164713-02C	Vial NH4Cl preserved	A	NA	NA	2.3	Y	Absent		SUB-HAA(9)
L2164713-02D	Vial NH4Cl preserved	A	NA	NA	2.3	Y	Absent		SUB-HAA(9)
L2164713-02E	Vial Ascorbic Acid/HCl preserved	A	NA		2.3	Y	Absent		524-THM(14)
L2164713-02F	Vial Ascorbic Acid/HCl preserved	A	NA		2.3	Y	Absent		524-THM(14)
L2164713-02G	Plastic 120ml unpreserved	A	7	7	2.3	Y	Absent		SO4-300(28)
L2164713-02H	Plastic 250ml unpreserved	A	7	7	2.3	Y	Absent		ORP(1),TRC-4500(1),PH-4500(.01)
L2164713-02I	Plastic 500ml unpreserved	A	7	7	2.3	Y	Absent		CL-300(28)
L2164713-03A	Plastic 120ml unpreserved	A	7	7	2.3	Y	Absent		SO4-300(28)
L2164713-03B	Plastic 250ml unpreserved	A	7	7	2.3	Y	Absent		CL-300(28)
L2164713-04A	Plastic 60ml unpreserved	A	7	7	2.3	Y	Absent		CL-300(28)
L2164713-04B	Plastic 120ml unpreserved	A	7	7	2.3	Y	Absent		CL-300(28)
L2164713-04C	Plastic 120ml unpreserved	A	7	7	2.3	Y	Absent		SO4-300(28)

**Project Name:** PRUDENCE ISLAND

**Project Number:** 119-21-01

Serial\_No:12102111:53

**Lab Number:** L2164713

**Report Date:** 12/10/21

**Container Information**

**Container ID    Container Type**

<b>Cooler</b>	<b>Initial pH</b>	<b>Final pH</b>	<b>Temp deg C</b>	<b>Pres</b>	<b>Seal</b>	<b>Frozen Date/Time</b>	<b>Analysis(*)</b>
---------------	-----------------------	---------------------	-----------------------	-------------	-------------	-----------------------------	--------------------

**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2164713  
**Report Date:** 12/10/21

## GLOSSARY

### Acronyms

DL	- Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the limit of quantitation (LOQ). The DL includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)
EDL	- Estimated Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The EDL includes any adjustments from dilutions, concentrations or moisture content, where applicable. The use of EDLs is specific to the analysis of PAHs using Solid-Phase Microextraction (SPME).
EMPC	- Estimated Maximum Possible Concentration: The concentration that results from the signal present at the retention time of an analyte when the ions meet all of the identification criteria except the ion abundance ratio criteria. An EMPC is a worst-case estimate of the concentration.
EPA	- Environmental Protection Agency.
LCS	- Laboratory Control Sample: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
LCSD	- Laboratory Control Sample Duplicate: Refer to LCS.
LFB	- Laboratory Fortified Blank: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
LOD	- Limit of Detection: This value represents the level to which a target analyte can reliably be detected for a specific analyte in a specific matrix by a specific method. The LOD includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)
LOQ	- Limit of Quantitation: The value at which an instrument can accurately measure an analyte at a specific concentration. The LOQ includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)  Limit of Quantitation: The value at which an instrument can accurately measure an analyte at a specific concentration. The LOQ includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)
MDL	- Method Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The MDL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
MS	- Matrix Spike Sample: A sample prepared by adding a known mass of target analyte to a specified amount of matrix sample for which an independent estimate of target analyte concentration is available. For Method 332.0, the spike recovery is calculated using the native concentration, including estimated values.
MSD	- Matrix Spike Sample Duplicate: Refer to MS.
NA	- Not Applicable.
NC	- Not Calculated: Term is utilized when one or more of the results utilized in the calculation are non-detect at the parameter's reporting unit.
NDPA/DPA	- N-Nitrosodiphenylamine/Diphenylamine.
NI	- Not Ignitable.
NP	- Non-Plastic: Term is utilized for the analysis of Atterberg Limits in soil.
NR	- No Results: Term is utilized when 'No Target Compounds Requested' is reported for the analysis of Volatile or Semivolatile Organic TIC only requests.
RL	- Reporting Limit: The value at which an instrument can accurately measure an analyte at a specific concentration. The RL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
RPD	- Relative Percent Difference: The results from matrix and/or matrix spike duplicates are primarily designed to assess the precision of analytical results in a given matrix and are expressed as relative percent difference (RPD). Values which are less than five times the reporting limit for any individual parameter are evaluated by utilizing the absolute difference between the values; although the RPD value will be provided in the report.
SRM	- Standard Reference Material: A reference sample of a known or certified value that is of the same or similar matrix as the associated field samples.
STLP	- Semi-dynamic Tank Leaching Procedure per EPA Method 1315.
TEF	- Toxic Equivalency Factors: The values assigned to each dioxin and furan to evaluate their toxicity relative to 2,3,7,8-TCDD.
TEQ	- Toxic Equivalent: The measure of a sample's toxicity derived by multiplying each dioxin and furan by its corresponding TEF and then summing the resulting values.
TIC	- Tentatively Identified Compound: A compound that has been identified to be present and is not part of the target compound list (TCL) for the method and/or program. All TICs are qualitatively identified and reported as estimated concentrations.

Report Format: Data Usability Report



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2164713  
**Report Date:** 12/10/21

#### Footnotes

- 1 - The reference for this analyte should be considered modified since this analyte is absent from the target analyte list of the original method.

#### Terms

**Analytical Method:** Both the document from which the method originates and the analytical reference method. (Example: EPA 8260B is shown as 1,8260B.) The codes for the reference method documents are provided in the References section of the Addendum.

**Difference:** With respect to Total Oxidizable Precursor (TOP) Assay analysis, the difference is defined as the Post-Treatment value minus the Pre-Treatment value.

**Final pH:** As it pertains to Sample Receipt & Container Information section of the report, Final pH reflects pH of container determined after adjustment at the laboratory, if applicable. If no adjustment required, value reflects Initial pH.

**Frozen Date/Time:** With respect to Volatile Organics in soil, Frozen Date/Time reflects the date/time at which associated Reagent Water-preserved vials were initially frozen. Note: If frozen date/time is beyond 48 hours from sample collection, value will be reflected in 'bold'.

**Initial pH:** As it pertains to Sample Receipt & Container Information section of the report, Initial pH reflects pH of container determined upon receipt, if applicable.

**PAH Total:** With respect to Alkylated PAH analyses, the 'PAHs, Total' result is defined as the summation of results for all or a subset of the following compounds: Naphthalene, C1-C4 Naphthalenes, 2-Methylnaphthalene, 1-Methylnaphthalene, Biphenyl, Acenaphthylene, Acenaphthene, Fluorene, C1-C3 Fluorenes, Phenanthrene, C1-C4 Phenanthrenes/Anthracenes, Anthracene, Fluoranthene, Pyrene, C1-C4 Fluoranthenes/Pyrenes, Benz(a)anthracene, Chrysene, C1-C4 Chrysenes, Benzo(b)fluoranthene, Benzo(j)+(k)fluoranthene, Benzo(e)pyrene, Benzo(a)pyrene, Perylene, Indeno(1,2,3-cd)pyrene, Dibenz(ah)+(ac)anthracene, Benzo(g,h,i)perylene. If a 'Total' result is requested, the results of its individual components will also be reported.

**PFAS Total:** With respect to PFAS analyses, the 'PFAS, Total (5)' result is defined as the summation of results for: PFHpA, PFHxS, PFOA, PFNA and PFOS. In addition, the 'PFAS, Total (6)' result is defined as the summation of results for: PFHpA, PFHxS, PFOA, PFNA, PFDA and PFOS. For MassDEP DW compliance analysis only, the 'PFAS, Total (6)' result is defined as the summation of results at or above the RL. Note: If a 'Total' result is requested, the results of its individual components will also be reported.

The target compound Chlordane (CAS No. 57-74-9) is reported for GC ECD analyses. Per EPA, this compound "refers to a mixture of chlordane isomers, other chlorinated hydrocarbons and numerous other components." (Reference: USEPA Toxicological Review of Chlordane, In Support of Summary Information on the Integrated Risk Information System (IRIS), December 1997.)

**Total:** With respect to Organic analyses, a 'Total' result is defined as the summation of results for individual isomers or Aroclors. If a 'Total' result is requested, the results of its individual components will also be reported. This is applicable to 'Total' results for methods 8260, 8081 and 8082.

#### Data Qualifiers

- A** - Spectra identified as "Aldol Condensates" are byproducts of the extraction/concentration procedures when acetone is introduced in the process.
- B** - The analyte was detected above the reporting limit in the associated method blank. Flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For MCP-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For DOD-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank AND the analyte was detected above one-half the reporting limit (or above the reporting limit for common lab contaminants) in the associated method blank. For NJ-Air-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte above the reporting limit. For NJ-related projects (excluding Air), flag only applies to associated field samples that have detectable concentrations of the analyte, which was detected above the reporting limit in the associated method blank or above five times the reporting limit for common lab contaminants (Phthalates, Acetone, Methylene Chloride, 2-Butanone).
- C** - Co-elution: The target analyte co-elutes with a known lab standard (i.e. surrogate, internal standards, etc.) for co-extracted analyses.
- D** - Concentration of analyte was quantified from diluted analysis. Flag only applies to field samples that have detectable concentrations of the analyte.
- E** - Concentration of analyte exceeds the range of the calibration curve and/or linear range of the instrument.
- F** - The ratio of quantifier ion response to qualifier ion response falls outside of the laboratory criteria. Results are considered to be an estimated maximum concentration.
- G** - The concentration may be biased high due to matrix interferences (i.e. co-elution) with non-target compound(s). The result should be considered estimated.
- H** - The analysis of pH was performed beyond the regulatory-required holding time of 15 minutes from the time of sample collection.
- I** - The lower value for the two columns has been reported due to obvious interference.
- J** - Estimated value. This represents an estimated concentration for Tentatively Identified Compounds (TICs).
- M** - Reporting Limit (RL) exceeds the MCP CAM Reporting Limit for this analyte.
- ND** - Not detected at the reporting limit (RL) for the sample.
- NJ** - Presumptive evidence of compound. This represents an estimated concentration for Tentatively Identified Compounds (TICs), where

Report Format: Data Usability Report



**Project Name:** PRUDENCE ISLAND  
**Project Number:** 119-21-01

**Lab Number:** L2164713  
**Report Date:** 12/10/21

#### **Data Qualifiers**

the identification is based on a mass spectral library search.

- P** - The RPD between the results for the two columns exceeds the method-specified criteria.
- Q** - The quality control sample exceeds the associated acceptance criteria. For DOD-related projects, LCS and/or Continuing Calibration Standard exceedences are also qualified on all associated sample results. Note: This flag is not applicable for matrix spike recoveries when the sample concentration is greater than 4x the spike added or for batch duplicate RPD when the sample concentrations are less than 5x the RL. (Metals only.)
- R** - Analytical results are from sample re-analysis.
- RE** - Analytical results are from sample re-extraction.
- S** - Analytical results are from modified screening analysis.
- V** - The surrogate associated with this target analyte has a recovery outside the QC acceptance limits. (Applicable to MassDEP DW Compliance samples only.)
- Z** - The batch matrix spike and/or duplicate associated with this target analyte has a recovery/RPD outside the QC acceptance limits. (Applicable to MassDEP DW Compliance samples only.)

**Project Name:** PRUDENCE ISLAND**Lab Number:** L2164713**Project Number:** 119-21-01**Report Date:** 12/10/21

## REFERENCES

- 12 Annual Book of ASTM Standards. (American Society for Testing and Materials) ASTM International.
- 16 Methods for the Determination of Organic Compounds in Drinking Water - Supplement II. EPA/600/R-92/129, August 1992.
- 44 Methods for the Determination of Inorganic Substances in Environmental Samples, EPA/600/R-93/100, August 1993.
- 121 Standard Methods for the Examination of Water and Wastewater. APHA-AWWA-WEF. Standard Methods Online.

## LIMITATION OF LIABILITIES

Alpha Analytical performs services with reasonable care and diligence normal to the analytical testing laboratory industry. In the event of an error, the sole and exclusive responsibility of Alpha Analytical shall be to re-perform the work at it's own expense. In no event shall Alpha Analytical be held liable for any incidental, consequential or special damages, including but not limited to, damages in any way connected with the use of, interpretation of, information or analysis provided by Alpha Analytical.

We strongly urge our clients to comply with EPA protocol regarding sample volume, preservation, cooling, containers, sampling procedures, holding time and splitting of samples in the field.





## Certification Information

The following analytes are not included in our Primary NELAP Scope of Accreditation:

### Westborough Facility

**EPA 624/624.1:** m/p-xylene, o-xylene, Naphthalene

**EPA 625/625.1:** alpha-Terpineol

**EPA 8260C/8260D:** NPW: 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene, Azobenzene; SCM: Iodomethane (methyl iodide), 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene.

**EPA 8270D/8270E:** NPW: Dimethylnaphthalene, 1,4-Diphenylhydrazine, alpha-Terpineol; SCM: Dimethylnaphthalene, 1,4-Diphenylhydrazine.

**SM4500:** NPW: Amenable Cyanide; SCM: Total Phosphorus, TKN, NO<sub>2</sub>, NO<sub>3</sub>.

### Mansfield Facility

**SM 2540D:** TSS

**EPA 8082A:** NPW: PCB: 1, 5, 31, 87,101, 110, 141, 151, 153, 180, 183, 187.

**EPA TO-15:** Halothane, 2,4,4-Trimethyl-2-pentene, 2,4,4-Trimethyl-1-pentene, Thiophene, 2-Methylthiophene,

3-Methylthiophene, 2-Ethylthiophene, 1,2,3-Trimethylbenzene, Indan, Indene, 1,2,4,5-Tetramethylbenzene, Benzothiophene, 1-Methylnaphthalene.

**Biological Tissue Matrix:** EPA 3050B

The following analytes are included in our Massachusetts DEP Scope of Accreditation

### Westborough Facility:

#### Drinking Water

**EPA 300.0:** Chloride, Nitrate-N, Fluoride, Sulfate; **EPA 353.2:** Nitrate-N, Nitrite-N; **SM4500NO3-F:** Nitrate-N, Nitrite-N; **SM4500F-C, SM4500CN-CE,**

**EPA 180.1, SM2130B, SM4500CI-D, SM2320B, SM2540C, SM4500H-B, SM4500NO2-B**

**EPA 332:** Perchlorate; **EPA 524.2:** THMs and VOCs; **EPA 504.1:** EDB, DBCP.

**Microbiology:** **SM9215B; SM9223-P/A, SM9223B-Colilert-QT, SM9222D.**

#### Non-Potable Water

**SM4500H,B, EPA 120.1, SM2510B, SM2540C, SM2320B, SM4500CL-E, SM4500F-BC, SM4500NH3-BH:** Ammonia-N and Kjeldahl-N, **EPA 350.1:**

Ammonia-N, **LCHAT 10-107-06-1-B:** Ammonia-N, **EPA 351.1, SM4500NO3-F, EPA 353.2:** Nitrate-N, **SM4500P-E, SM4500P-B, E, SM4500SO4-E,**

**SM5220D, EPA 410.4, SM5210B, SM5310C, SM4500CL-D, EPA 1664, EPA 420.1, SM4500-CN-CE, SM2540D, EPA 300:** Chloride, Sulfate, Nitrate.

**EPA 624.1:** Volatile Halocarbons & Aromatics,

**EPA 608.3:** Chlordane, Toxaphene, Aldrin, alpha-BHC, beta-BHC, gamma-BHC, delta-BHC, Dieldrin, DDD, DDE, DDT, Endosulfan I, Endosulfan II,

Endosulfan sulfate, Endrin, Endrin Aldehyde, Heptachlor, Heptachlor Epoxide, PCBs

**EPA 625.1:** SVOC (Acid/Base/Neutral Extractables), **EPA 600/4-81-045:** PCB-Oil.

**Microbiology:** **SM9223B-Colilert-QT; Enterolert-QT, SM9221E, EPA 1600, EPA 1603, SM9222D.**

### Mansfield Facility:

#### Drinking Water

**EPA 200.7:** Al, Ba, Cd, Cr, Cu, Fe, Mn, Ni, Na, Ag, Ca, Zn. **EPA 200.8:** Al, Sb, As, Ba, Be, Cd, Cr, Cu, Pb, Mn, Ni, Se, Ag, TL, Zn. **EPA 245.1 Hg.**

**EPA 522, EPA 537.1.**

#### Non-Potable Water

**EPA 200.7:** Al, Sb, As, Be, Cd, Ca, Cr, Co, Cu, Fe, Pb, Mg, Mn, Mo, Ni, K, Se, Ag, Na, Sr, TL, Ti, V, Zn.

**EPA 200.8:** Al, Sb, As, Be, Cd, Cr, Cu, Fe, Pb, Mn, Ni, K, Se, Ag, Na, TL, Zn.

**EPA 245.1 Hg.**

**SM2340B**

For a complete listing of analytes and methods, please contact your Alpha Project Manager.





# CHAIN OF CUSTODY

PAGE 1 OF 1

8 Walkup Drive  
Westboro, MA 01581  
Tel: 508-898-9220

320 Forbes Blvd  
Mansfield, MA 02048  
Tel: 508-822-9300

Date Rec'd in Lab: 11-23-21

ALPHA Job #: 2164713

### Project Information

Project Name: Prudence

Project Location: Prudence Island

Project #: 119.21.01

Project Manager: Steve Olson

ALPHA Quote #:

### Report Information - Data Deliverables

ADEx  EMAIL

### Billing Information

Same as Client info PO #:

### Client Information

Client: H2 Olson Engineering, Inc.

Address: 10 Riverside Dr, Suite 103  
Lakerville, MA 02347

Phone: 781 588 6800

Email: SCU@h2olsonengineering.com

### Turn-Around Time

Standard  RUSH (only confirmed if pre-approved!)

Date Due:

### Regulatory Requirements & Project Information Requirements

Yes  No MA MCP Analytical Methods  Yes  No CT RCP Analytical Methods

Yes  No Matrix Spike Required on this SDG? (Required for MCP Inorganics)

Yes  No GW1 Standards (Info Required for Metals & EPH with Targets)

Yes  No NPDES RGP

Other State /Fed Program \_\_\_\_\_ Criteria \_\_\_\_\_

Additional Project Information:

ANALYSIS		SAMPLE INFO	
VOC: <input type="checkbox"/> 8260 <input type="checkbox"/> 624 <input type="checkbox"/> 524.2	SVOC: <input type="checkbox"/> ABN <input type="checkbox"/> PAH	<input type="checkbox"/> Filtration	<input type="checkbox"/> Field
METALS: <input type="checkbox"/> MCP 13 <input type="checkbox"/> MCP 14 <input type="checkbox"/> MCP 15	METALS: <input type="checkbox"/> RCRA5 <input type="checkbox"/> RCRA8 <input type="checkbox"/> PPH3	<input type="checkbox"/> Lab to do	
EPH: <input type="checkbox"/> Ranges & Targets <input type="checkbox"/> Ranges Only	VPH: <input type="checkbox"/> Ranges & Targets <input type="checkbox"/> Ranges Only	Preservation	<input type="checkbox"/> Lab to do
PCB	TPH: <input type="checkbox"/> Quant Only <input type="checkbox"/> Fingerprint		
<p><u>PH-ORP-Chloride</u></p> <p><u>Sulfate</u></p> <p><u>TTHMs</u></p> <p><u>HAAs</u></p>		Sample Comments	

ALPHA Lab ID (Lab Use Only)	Sample ID	Collection		Sample Matrix	Sampler Initials	ANALYSIS	SAMPLE INFO	T O T A L # B O T T L E S
		Date	Time					
<u>64713-01</u>	<u>AC-DAY 12</u>	<u>11/23</u>	<u>10</u>	<u>DW</u>	<u>SO</u>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/>	<u>9</u>
<u>-02</u>	<u>IS-DAY 12</u>	↓	↓	↓	↓	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/>	<u>9</u>
<u>-03</u>	<u>AC-RAW</u>	↓	↓	↓	↓	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> <input checked="" type="checkbox"/>	<u>3</u>
<u>-04</u>	<u>IS-RAW</u>	↓	↓	↓	↓	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<u>2</u>

**Container Type**  
P= Plastic  
A= Amber glass  
V= Vial  
G= Glass  
B= Bacteria cup  
C= Cube  
O= Other  
E= Encore  
D= BOD Bottle

**Preservative**  
A= None  
B= HCl  
C= HNO3  
D= H2SO4  
E= NaOH  
F= MeOH  
G= NaHSO4  
H= Na2S2O3  
I= Ascorbic Acid  
J= NH4Cl  
K= Zn Acetate  
O= Other

Container Type	Preservative

Relinquished By: [Signature] Date/Time: 11/23/21 12:57

Received By: [Signature] Date/Time: 11/23/21 1:45

All samples submitted are subject to Alpha's Terms and Conditions. See reverse side.  
FORM NO: 01-01 (rev. 12-Mar-2012)





# GRANITE STATE ANALYTICAL SERVICES, LLC.

22 Manchester Road, Unit 2, Derry, NH 03038  
Phone (800) 699-9920 | (603) 432-3044 website [www.granitestateanalytical.com](http://www.granitestateanalytical.com)

## Laboratory Report

Alpha Analytical-Westborough  
8 Walkup Dr.  
Westborough, MA 01581

Date Printed: 12/03/2021  
Work Order #: 2111-03708  
Client Job #: L2164713  
Date Received: 11/24/2021  
Sample collected in: Rhode Island

Attached please find results for the analysis of the samples received on the date referenced above.

Unless otherwise noted in the attached report, the analyses performed met the requirements of the analyzing laboratory's Quality Assurance Plan, Standard Operating Procedures and State Accreditation. This certificate shall not be reproduced, except in full, without the written approval of the analyzing laboratory. The results presented in this report relate to the samples listed on the following pages in the condition in which they were received. Accreditation for each analyte is identified by the \* symbol following the analyte name. Location of our analyzing laboratory is identified by the code in the Analyst Column.

### A & L Laboratory:

Identified by ME in Analyst Column  
155 Center Street, Auburn, Maine 04210  
[www.allaboratory.com](http://www.allaboratory.com)

### Granite State Analytical Services LLC:

Identified by NH in Analyst Column  
22 Manchester Road, Derry, NH 03038  
[www.granitestateanalytical.com](http://www.granitestateanalytical.com)

### ANALYSIS RELATED NOTES:

- RL: "Reporting limit" means the lowest level of an analyte that can be accurately recovered from the matrix of interest.
- A & L Laboratory / Granite State Analytical Services LLC. accreditation lists can be found on our websites listed above.
- Subcontracted samples will be identified by the Accreditation number of the subcontract laboratory in the analyst field for each analyte and the appropriate laboratory will be listed here. **None**
- Data Qualifiers (DQ) Flags provide additional information in regards to the receipt, analysis or quality control of a sample. These are indicated under the DQ Flags Column on your report and listed here if necessary: **Data Qualifier (DQ) Flags: None**

### SAMPLE STATE SPECIFIC NOTES:

Additional Narrative or Comments: **None**

We appreciate the opportunity to provide you with laboratory services. If you have any questions regarding the enclosed report, please contact the laboratory and we will be happy to assist you.

Donald A. D'Anjou, Ph. D.  
Laboratory Director



# GRANITE STATE ANALYTICAL SERVICES, LLC.

22 Manchester Road, Unit 2, Derry, NH 03038  
 Phone (800) 699-9920 | (603) 432-3044 website www.granitestateanalytical.com

## CERTIFICATE OF ANALYSIS FOR DRINKING WATER

**DATE PRINTED:** 12/03/2021  
**CLIENT NAME:** Alpha Analytical-Westborough  
**CLIENT ADDRESS:** 8 Walkup Dr.  
 Westborough, MA 01581

**SAMPLE ID #:** 2111-03708-001  
**SAMPLED BY:** Alpha Analytical-Westborough

**SAMPLE ADDRESS:** L2164713  
 AC-Day 12  
 RI

**DATE AND TIME COLLECTED:** 11/23/2021 10:00AM  
**DATE AND TIME RECEIVED:** 11/24/2021 01:20PM  
**ANALYSIS PACKAGE:** HAA GSA  
**RECEIPT TEMPERATURE:** ON ICE .5° CELSIUS

Legend	
Passes	✓
Fails EPA Primary	⊗
Fails EPA Secondary	▼
Fails State Guideline	✕
Attention	⚠

**MORE LOC INFO:**

Test Description	Result	Test Units	Pass /Fail	DQ Flag	CLIENT JOB #:		Method	Analyst	Date - Time Analyzed
					RL	Limit			
Date Extracted	-					No Limit	EPA 552.2	GQ-NH	11/30/2021 08:45AM
Dibromoacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	12/01/2021 09:52AM
Dichloroacetic Acid*	1.1	ug/L			1	No Limit	EPA 552.2	KV-NH	12/01/2021 09:52AM
Monobromoacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	12/01/2021 09:52AM
Monochloroacetic Acid*	<2	ug/L			2	No Limit	EPA 552.2	KV-NH	12/01/2021 09:52AM
Total Haloacetic Acids*	1.1	ug/L	✓		1	60 ug/L	EPA 552.2	KV-NH	12/01/2021 09:52AM
Trichloroacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	12/01/2021 09:52AM
2,3-Dibromopropionic Acid	97	%	✓			70-130%	EPA 552.2 - SS	KV-NH	12/01/2021 09:52AM

Donald A. D'Anjou, Ph. D.  
 Laboratory Director



# GRANITE STATE ANALYTICAL SERVICES, LLC.

22 Manchester Road, Unit 2, Derry, NH 03038  
 Phone (800) 699-9920 | (603) 432-3044 website www.granitestateanalytical.com

## CERTIFICATE OF ANALYSIS FOR DRINKING WATER

**DATE PRINTED:** 12/03/2021  
**CLIENT NAME:** Alpha Analytical-Westborough  
**CLIENT ADDRESS:** 8 Walkup Dr.  
 Westborough, MA 01581  
**SAMPLE ID #:** 2111-03708-002  
**SAMPLED BY:** Alpha Analytical-Westborough  
**SAMPLE ADDRESS:** L2164713  
 IS-Day 12  
 RI

Legend	
Passes	✓
Fails EPA Primary	⊗
Fails EPA Secondary	▼
Fails State Guideline	✕
Attention	⚠

**DATE AND TIME COLLECTED:** 11/23/2021 10:00AM  
**DATE AND TIME RECEIVED:** 11/24/2021 01:20PM  
**ANALYSIS PACKAGE:** HAA GSA  
**RECEIPT TEMPERATURE:** ON ICE .5° CELSIUS

**MORE LOC INFO:**

**CLIENT JOB #:** L2164713

Test Description	Result	Test Units	Pass /Fail	DQ Flag	RL	Limit	Method	Analyst	Date - Time Analyzed
Date Extracted	-					No Limit	EPA 552.2	GQ-NH	11/30/2021 08:45AM
Dibromoacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	12/01/2021 10:32AM
Dichloroacetic Acid*	1.7	ug/L			1	No Limit	EPA 552.2	KV-NH	12/01/2021 10:32AM
Monobromoacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	12/01/2021 10:32AM
Monochloroacetic Acid*	<2	ug/L			2	No Limit	EPA 552.2	KV-NH	12/01/2021 10:32AM
Total Haloacetic Acids*	1.7	ug/L	✓		1	60 ug/L	EPA 552.2	KV-NH	12/01/2021 10:32AM
Trichloroacetic Acid*	<1	ug/L			1	No Limit	EPA 552.2	KV-NH	12/01/2021 10:32AM
2,3-Dibromopropionic Acid	108	%	✓			70-130%	EPA 552.2 - SS	KV-NH	12/01/2021 10:32AM

Donald A. D'Anjou, Ph. D.  
 Laboratory Director






## **Attachment D**

### **NRCS Web Soil Surveys**

DRAFT




Hydrologic Soil Group—State of Rhode Island: Bristol, Kent, Newport, Providence, and Washington Counties  
(Indian Spring)



Soil Map may not be valid at this scale.


Map Scale: 1:1,360 if printed on A landscape (11" x 8.5") sheet.



Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 19N WGS84

## MAP LEGEND

### Area of Interest (AOI)









 Area of Interest (AOI)

### Soils

#### Soil Rating Polygons





 A  
 A/D  
 B  
 B/D  
 C  
 C/D  
 D  
 Not rated or not available

#### Soil Rating Lines

 A  
 A/D  
 B  
 B/D  
 C  
 C/D  
 D  
 Not rated or not available

#### Soil Rating Points




 A  
 A/D  
 B  
 B/D

 C  
 C/D  
 D  
 Not rated or not available


### Water Features

 Streams and Canals

### Transportation

 Rails  
 Interstate Highways  
 US Routes  
 Major Roads  
 Local Roads

### Background

 Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:12,000.

**Warning:** Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: State of Rhode Island: Bristol, Kent, Newport, Providence, and Washington Counties  
 Survey Area Data: Version 21, Sep 3, 2021

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: May 14, 2010—Apr 1, 2017

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
QoC	Quonset gravelly sandy loam, rolling	A	1.8	24.8%
Sb	Scarboro mucky fine sandy loam, 0 to 3 percent slopes	A/D	1.9	26.5%
WgA	Windsor loamy sand, 0 to 3 percent slopes	A	3.5	48.7%
<b>Totals for Area of Interest</b>			<b>7.2</b>	<b>100.0%</b>

### Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

## Rating Options

*Aggregation Method:* Dominant Condition


*Component Percent Cutoff:* None Specified

*Tie-break Rule:* Higher

Hydrologic Soil Group—State of Rhode Island: Bristol, Kent, Newport, Providence, and Washington Counties  
(Army Camp)




Soil Map may not be valid at this scale.



## MAP LEGEND

### Area of Interest (AOI)









 Area of Interest (AOI)

### Soils

#### Soil Rating Polygons





 A  
 A/D  
 B  
 B/D  
 C  
 C/D  
 D  
 Not rated or not available

#### Soil Rating Lines

 A  
 A/D  
 B  
 B/D  
 C  
 C/D  
 D  
 Not rated or not available

#### Soil Rating Points




 A  
 A/D  
 B  
 B/D

 C  
 C/D  
 D  
 Not rated or not available


### Water Features

 Streams and Canals

### Transportation

 Rails  
 Interstate Highways  
 US Routes  
 Major Roads  
 Local Roads

### Background

 Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:12,000.

**Warning:** Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: State of Rhode Island: Bristol, Kent, Newport, Providence, and Washington Counties  
 Survey Area Data: Version 21, Sep 3, 2021

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: May 14, 2010—Apr 1, 2017

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.



## Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
NeA	Newport silt loam, 0 to 3 percent slopes	C	1.4	36.5%
NeB	Newport silt loam, 3 to 8 percent slopes	C	2.3	63.5%
<b>Totals for Area of Interest</b>			<b>3.7</b>	<b>100.0%</b>

### Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

### Rating Options

*Aggregation Method:* Dominant Condition

*Component Percent Cutoff: None Specified*

*Tie-break Rule: Higher*

**Attachment E**

**Zoning Map**

DRAFT





Town of Portsmouth, Rhode Island  
 Web GIS Maps and Online Property Information

by MainStreetGIS, LLC Town Website

[User Guide](#) [Feedback](#) [Disclaimer](#)


Base Map: Town Base Map

**GIS Map** | Street View | Tax Maps | GIS Links

MainStreet Maps

**Layers** | Property | Selection

- Parcel Address Text
- Parcel ID Text
- Parcel Area Text
- Parcel Dimension Text
- Address Points (E911 2016)
- Roads (E911 2018)
- Tax Map Index
- Town Boundary
- Towns
- Watershed Protection District
- Unofficial Zoning Map (Planning Dept.)
  - (C) Commercial
  - (HI) Heavy Industrial
  - (LI) Light Industrial
  - (OS) Open Space & Public Lands
  - (R-10) Residential - 10
  - (R-20) Residential - 20
  - (R-30) Residential - 30
  - (R-40) Residential - 40
  - (R-60) Residential - 60
  - (RD) Redevelopment
  - (TC) Town Center
  - (WD) Waterfront
- Water Supply District (RIGIS)
- Watershed (RIGIS)
- Flood Zones Group (2015)
- Hydrant (PW&FD)
- Hydrant (E911 2016)
- Parcels (Yellow)
- Parcels (12/31/2020)





## **Attachment F**

### **FEMA FIRM Maps**

DRAFT






# National Flood Hazard Layer FIRMMette



71°18'59"W 41°37'27"N



## Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) Zone A, V, A99
		With BFE or Depth Zone AE, AO, AH, VE, AR
		Regulatory Floodway

OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
		Future Conditions 1% Annual Chance Flood Hazard Zone X
		Area with Reduced Flood Risk due to Levee. See Notes. Zone X
		Area with Flood Risk due to Levee Zone D

OTHER AREAS		NO SCREEN Area of Minimal Flood Hazard Zone X
		Effective LOMRs
		Area of Undetermined Flood Hazard Zone D

GENERAL STRUCTURES		Channel, Culvert, or Storm Sewer
		Levee, Dike, or Floodwall

OTHER FEATURES		20.2 Cross Sections with 1% Annual Chance Water Surface Elevation
		17.5 Water Surface Elevation
		Coastal Transect
		Base Flood Elevation Line (BFE)
		Limit of Study
		Jurisdiction Boundary
OTHER FEATURES		Coastal Transect Baseline
		Profile Baseline
		Hydrographic Feature

MAP PANELS		Digital Data Available
		No Digital Data Available
		Unmapped
		The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.



This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on **8/1/2022 at 9:52 AM** and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.


This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.



# National Flood Hazard Layer FIRMMette



71°19'4"W 41°36'43"N



## Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) <i>Zone A, V, A99</i>	
		With BFE or Depth <i>Zone AE, AO, AH, VE, AR</i>	
		Regulatory Floodway	
OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile <i>Zone X</i>	
		Future Conditions 1% Annual Chance Flood Hazard <i>Zone X</i>	
		Area with Reduced Flood Risk due to Levee. See Notes. <i>Zone X</i>	
		Area with Flood Risk due to Levee <i>Zone D</i>	
OTHER AREAS		NO SCREEN Area of Minimal Flood Hazard <i>Zone X</i>	
		Effective LOMRs	
GENERAL STRUCTURES		Area of Undetermined Flood Hazard <i>Zone D</i>	
		Channel, Culvert, or Storm Sewer	
OTHER FEATURES		Levee, Dike, or Floodwall	
		20.2 Cross Sections with 1% Annual Chance	
		17.5 Water Surface Elevation	
		Coastal Transect	
		Base Flood Elevation Line (BFE)	
		Limit of Study	
		Jurisdiction Boundary	
MAP PANELS		Coastal Transect Baseline	
		Profile Baseline	
		Hydrographic Feature	
MAP PANELS		Digital Data Available	
		No Digital Data Available	
		Unmapped	
			The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on **8/1/2022 at 9:48 AM** and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.




## **Attachment G**

### **National Wetlands Inventory Map**

DRAFT





## National Wetlands Inventory

source: [www.rigis.org](http://www.rigis.org)

### Legend

★ Site Locations

 Wetlands





## **Attachment H**


### **Natural Heritage Areas Map**

DRAFT





Esri, HERE, Garmin, (c) OpenStreetMap contributors, and the GIS user community, Source: Esri, Maxar, Earthstar Geographics, and the GIS User Community





# Rhode Island Natural Heritage Areas

source: [www.rigis.org](http://www.rigis.org)



## Legend

-  Site Locations
-  Natural Heritage Areas



# **Attachment I**

## **Species Profiles**

DRAFT



Rhode Island Wildlife Action Plan Species Profiles  
Species of Greatest Conservation Need

## Big Sand Tiger Beetle


*Cicindela formosa generosa*

INVERTEBRATES

Tiger Beetles



Image: Chris Raithe



~See map disclaimer in profiles introduction

### Distribution & Abundance

*Cicindela formosa generosa* occurs exclusively in inland sand flats and barrens. Although this species has been known from about 10 recent sites in Rhode Island, some populations have disappeared or are extremely threatened. Except for one large population in the Big River Management Area, sites tend to contain only a few individuals. Most of the recent localities for this species occur on state managed lands and other preserves. However, many of these sites have been degraded or lost because of trampling by illegal ORV usage or revegetation of the habitat. There are very few places where this species could be considered secure. One is the Nockum Hill area of Barrington, where the habitat is maintained for the benefit of nesting turtles and vehicular traffic is prohibited. A TNC preserve in North Kingstown has an intact inland sand flat that is not often visited by vehicles or pedestrians.

Habitat Community: Pitch Pine Woodland/Barren, Type: Barren

### Status

STSTAT: C. SRANK: S1. GRANK: G5T5. Res/B: 1. FORM: 1. GRP: 17. PRIOR: 1. Climate Change Vulnerability: Low=2100

### Threats and Actions

**Threat 1 - Natural system modifications; Succession of sand patches, anything that fills sand patch (grass, trees, asphalt)**

- Actions:
- Site/area management. Rank: 2
  - Manage for sand patches. Rank: 2

**Threat 2 - Residential and commercial development; Development of sand patches**

- Actions:
- Land/water protection. Rank: 2
  - Protect sand patches. Rank: 2

**Threat 3 - Recreational activities; Impacts from human disturbance of habitats**

- Actions:
- Land/water protection. Rank: 2
  - Protect habitats. Rank: 2

Refer to the Community: Pitch Pine Woodland/Barren, Type: Barren - Habitat Profile for additional threats to this species.

Rhode Island Wildlife Action Plan Species Profiles  
Species of Greatest Conservation Need

**Oblique-lined Tiger Beetle**

INVERTEBRATES

Tiger Beetles

*Cicindela tranquebarica tranquebarica*




Image: Chris Raithel

~See map disclaimer in profiles introduction

**Distribution & Abundance**

*Cicindela tranquebarica* mirrors the status of *C. purpurea* except that it is still extant at a few mainland sites in southern New England. In Rhode Island, remaining populations are known only from Prudence Island and Tiverton, where the species resides on protected managed lands. As with *Cicindela purpurea*, trampling and over-collection do not seem to be affecting populations at this time. However, active habitat management, including the reintroduction of fire, must occur to retain populations.

Habitat Community: Pitch Pine Woodland/Barren, Type: Barren

**Status**

SRANK: S1. GRANK: G5. Res/B: 1. GRP: 28. PRIOR: 1. Climate Change Vulnerability: Low=2100

**Threats and Actions**

**Threat 1 - Human intrusions and disturbance; Disturbance from recreation**

- Actions:
- Land/water protection. Rank: 2
  - Protect habitats. Rank: 2

Refer to the Community: Pitch Pine Woodland/Barren, Type: Barren - Habitat Profile for additional threats to this species.



## **Attachment J**

### **Agency Correspondence**

DRAFT





July 18, 2022

Ron Gagnon, PE  
Administrator  
Rhode Island Department of Environmental Management  
Office of Technical and Customer Assistance  
235 Promenade St.  
Providence, RI 02908  
401-222-4700 ext. 2777500  
ron.gagnon@dem.ri.gov

**SUBJECT:** Intergovernmental Review Comments

**PROJECT:** Prudence Island Water District, Proposed Water Treatment Facilities

Dear Ron Gagnon:

The Prudence Island Water District (PIWD) is under an Administrative Consent Order (ACO) with the Rhode Island Department of Health (RIDOH) to install permanent disinfection facilities for their two water supply sources, including the pre-treatment for the removal of iron and manganese at the Indian Springs well site. PIWD retained the services of H2Olson Engineering, Inc. (10 Riverside Drive, Lakeville, MA 02347) to complete the design and permitting of these facilities in accordance with RIDOH ACO requirements.

One of the requirements of the State Environmental Review Process is to have the RIDEM Office of Technical and Customer Assistance review the proposed project and comment on the potential impact that the project might have, as well as its compliance with rules, regulations, environmental standards, and the permitting process. As such, I am attaching the following documents for your use and information:

- A proposed scope of work generally describing the project components.
- A copy of the project overview plan showing the project limits.
- Proposed site location.

Can you please review the attached information and let me know if you have any comments or concerns with the proposed water treatment project on Prudence Island? The project is being propped to improve the water quality and protect the public health for PIWD customers.

Review comments are requested within 30 days of receipt of this letter.

If you have any questions, please feel free to contact us at 508-375-7007 at your convenience.

Very Truly Yours,  
H2Olson Engineering, Inc.

Stephen C. Olson, P.E.  
President





July 18, 2022

Jenny Kilburn  
Principal Biologist  
Rhode Island Department of Environmental Management  
Division of Fish and Wildlife  
Great Swamp Field Headquarters  
277 Great Neck Road  
West Kingston, RI 02892  
401-789-0281  
jennifer.kilburn@dem.ri.gov

SUBJECT: Identification of Threats to Wildlife

PROJECT: Prudence Island Water District, Proposed Water Treatment Facilities

Dear Jenny Kilburn:

The Prudence Island Water District (PIWD) is under an Administrative Consent Order (ACO) with the Rhode Island Department of Health (RIDOH) to install permanent disinfection facilities for their two water supply sources, including the pre-treatment for the removal of iron and manganese at the Indian Springs well site. PIWD retained the services of H2Olson Engineering, Inc. (10 Riverside Drive, Lakeville, MA 02347) to complete the design and permitting of these facilities in accordance with RIDOH ACO requirements.

One of the requirements of the State Environmental Review Process is to have the Division of Fish and Wildlife review the proposed project and comment on the potential impact that the project might have on any local wildlife. As such, I am attaching the following documents for your use and information:


- A proposed scope of work generally describing the project components.
- A copy of the project overview plan showing the project limits.
- Proposed site location.

Can you please review the attached information and let me know if you have any comments or concerns with the proposed water treatment project on Prudence Island? The project is being propped to improve the water quality and protect the public health for PIWD customers.

Review comments are requested within 30 days of receipt of this letter.

If you have any questions, please feel free to contact us at 508-375-7007 at your convenience.

Very Truly Yours,  
H2Olson Engineering, Inc.



Stephen C. Olson, P.E.  
President



**From:** [Lisa Goyer](#)  
**To:** [Lauren Blair](#)  
**Subject:** FW: Request for Project Review  
**Date:** Tuesday, August 2, 2022 2:31:51 PM  
**Attachments:** [image006.png](#)  
[image007.png](#)  
[NEPARC2022-02\\_construction\\_decon-4.pdf](#)  
[easternbox-turtle-cmp.pdf](#)  
[NEPARC\\_Pub\\_2014-02\\_Disinfection\\_Protocol.pdf](#)  
**Importance:** High

---

**From:** Stephen Olson <[sco@h2olsonengineering.com](mailto:sco@h2olsonengineering.com)>  
**Sent:** Tuesday, August 2, 2022 2:23 PM  
**To:** Lisa Goyer <[lmg@h2olsonengineering.com](mailto:lmg@h2olsonengineering.com)>  
**Subject:** Fw: Request for Project Review  
**Importance:** High

~ Steve O

**Stephen C. Olson, P.E. | President**  
**H<sub>2</sub>Olson Engineering, Inc.**  
10 Riverside Drive | Lakeville, MA 02347  
O: 508.375.7007 | F: 508.748.5960 | C: 781.588.6800  
[www.h2olsonengineering.com](http://www.h2olsonengineering.com)  
[LinkedIn](#)



---

**From:** McIntyre, Jenna (DEM) <[jenna.mcintyre@dem.ri.gov](mailto:jenna.mcintyre@dem.ri.gov)>  
**Sent:** Tuesday, August 2, 2022 12:07 PM  
**To:** Stephen Olson <[sco@h2olsonengineering.com](mailto:sco@h2olsonengineering.com)>  
**Cc:** DEM.Filereview <[DEM.Filereview@dem.ri.gov](mailto:DEM.Filereview@dem.ri.gov)>  
**Subject:** FW: Request for Project Review

Good afternoon,

Please the 4 comments below and attachments. This should complete your records request.

1. Expect wildlife in the roads. Prudence Island is home to a host of sensitive wildlife, including eastern box turtles and spotted turtles. Turtles are particularly vulnerable to being hit by vehicles and caution should be used at all times when travelling in vehicles. Spotted turtles and eastern box turtles are active and could be found crossing roads from approximately April 1 through November 1. Do not exceed local speed limits and use caution *at all times* when driving on all paved and dirt roads. If a turtle is found in the road, stop the vehicle, approach the turtle when conditions are safe, and move the turtle at least 15 feet off the road in natural vegetation in the direction it was headed. Do not proceed until the turtle is out of harm's way.
2. Expect turtles within the Limit of Work. Eastern box turtles are likely to be present within the Limit of Work at both the Indian Springs and Army Camps sites. Eastern box turtles are active on the surface from approximately April 1 through November 1. Prior to any construction activity, use daily visual sweeps within the Limit of Work

- to look for box turtles. If a box turtle is located, move outside the Limit of Work at least 200 feet and place in a forested, upland area. See attached BMPs for more information on how to limit impacts to box turtles.
3. Islands are extremely sensitive to introduction of wildlife pathogens. Clean and decontaminate all construction equipment, footwear, and hand-held equipment before loading on the ferry to bring to Prudence Island. Follow the instructions in the attached protocols.
  4. Islands are extremely sensitive to introduction of invasive species. The current plans call for loaming and seeding within construction areas. No soil should be imported from off-island. Only native species seed mixes should be used.

Thank You,

Jenna

**Rhode Island Department of Environmental Management**  
235 Promenade Street | Room 260 | Providence, RI 02908



**Jenna McIntyre**  
**Chief Program Development**  
*Permit Application Center, Supervisor*  
*Office of Customer & Technical Assistance*  
Tel: (401) 222-4700 ext. 2777049

Email: [Jenna.McIntyre@dem.ri.gov](mailto:Jenna.McIntyre@dem.ri.gov)  
Permit Application Center: [DEM.PAC@dem.ri.gov](mailto:DEM.PAC@dem.ri.gov)  
File Reviews: [DEM.filereview@dem.ri.gov](mailto:DEM.filereview@dem.ri.gov)

---

**From:** Stephen Olson <[sco@h2olsonengineering.com](mailto:sco@h2olsonengineering.com)>  
**Sent:** Thursday, July 21, 2022 10:40 AM  
**To:** DEM.Filereview <[DEM.Filereview@dem.ri.gov](mailto:DEM.Filereview@dem.ri.gov)>  
**Cc:** Lauren Blair <[lab@h2olsonengineering.com](mailto:lab@h2olsonengineering.com)>  
**Subject:** [EXTERNAL] : FW: Request for Project Review

Good Morning,

We were instructed to forward this request to you (see below).

Can you please review the attached and provide us with a response?

Thank you for your time and cooperation.

~ Steve O

**Stephen C. Olson, P.E. | President**

**H<sub>2</sub>Olson Engineering, Inc.**

10 Riverside Drive, Suite 103 | Lakeville, MA 02347  
O: 508.375.7007 | F: 508.748.5960 | C: 781.588.6800  
[www.h2olsonengineering.com](http://www.h2olsonengineering.com) [[h2olsonengineering.com](http://h2olsonengineering.com)]  
[LinkedIn](https://www.linkedin.com) [[linkedin.com](https://www.linkedin.com)]



**From:** Lauren Blair [lab@h2olsonengineering.com](mailto:lab@h2olsonengineering.com)  
**Sent:** Thursday, July 21, 2022 10:33 AM  
**To:** Stephen Olson [sco@h2olsonengineering.com](mailto:sco@h2olsonengineering.com)  
**Subject:** FW: [EXTERNAL] : Request for Project Review



**Lauren Blair | Engineering Intern**

**H<sub>2</sub>Olsen Engineering, Inc.**

10 Riverside Drive, Suite 103

Lakeville, MA 02347

O: 508.375.7007 | C: 941.348.8209

[www.h2olsonengineering.com](http://www.h2olsonengineering.com) [[h2olsonengineering.com](http://h2olsonengineering.com)]



**From:** Kilburn, Jennifer (DEM) <[Jennifer.Kilburn@dem.ri.gov](mailto:Jennifer.Kilburn@dem.ri.gov)>

**Sent:** Wednesday, July 20, 2022 2:14 PM

**To:** Lauren Blair <[lab@h2olsonengineering.com](mailto:lab@h2olsonengineering.com)>

**Subject:** RE: [EXTERNAL] : Request for Project Review

Hi,

Please submit this project review request through this email [dem.filereview@dem.ri.gov](mailto:dem.filereview@dem.ri.gov)

Thanks



**Jennifer Kilburn AWB®**

**Principal Biologist-Waterfowl Program**

Rhode Island Department of Environmental Management

Division of Fish and Wildlife

277 Great Neck Road

West Kingston, RI 02892

Office: (401)-284-2245

---

**From:** Lauren Blair

**Sent:** Wednesday, July 20, 2022 1:49 PM

**To:** [jennifer.kilburn@dem.ri.gov](mailto:jennifer.kilburn@dem.ri.gov)

**Subject:** Request for Project Review

Dear Jenny Kilburn,

I hope this email finds you well. H2Olsen Engineering is seeking review comments from the RIDEM Division of Fish and Wildlife regarding a proposed water treatment project on Prudence Island, in accordance with the State Environmental Review Process. The attached documents provide further information on this request and the proposed project. A copy of these items will be sent by mail as well. Please let us know if you have any questions or concerns. We look forward to hearing from you.

Best regards,

**Lauren Blair | Engineering Intern**

**H<sub>2</sub>Olsen Engineering, Inc.**

10 Riverside Drive, Suite 103

Lakeville, MA 02347

O: 508.375.7007 | C: 941.348.8209

[www.h2olsonengineering.com](http://www.h2olsonengineering.com) [[h2olsonengineering.com](http://h2olsonengineering.com)]



# DISINFECTION OF FIELD EQUIPMENT TO MINIMIZE RISK OF SPREAD OF CHYTRIDIOMYCOSIS AND RANAVIRUS<sup>1</sup>

## IMPORTANCE OF DISINFECTION

The spread of pathogens is a major threat to amphibians and reptiles worldwide.<sup>2-5</sup> This is particularly true for Ranavirus (RV) and *Batrachochytrium dendrobatidis* (Bd) responsible for chytridiomycosis. Humans can transmit diseases from one place to another and from one organism to another in a short amount of time and over distances the organisms cannot traverse. With the increasing spread of pathogens and reports of die-offs among amphibians and select reptiles worldwide, it is imperative that field biologists, researchers, hobbyists, and anyone interested in recreational herpetology-related field activities employ basic disinfecting procedures to prevent the spread of pathogens.

## BEFORE LEAVING FOR THE FIELD

Although other chemicals are effective (see table), NEPARC recommends a 3% bleach solution to inactivate Bd and most RV's.<sup>3-7</sup> Concentrated bleach is inexpensive and readily available. However, diluted bleach solutions lose their potency if exposed to air, sunlight, or organic material, and should be discarded after 5 days if exposed.<sup>8</sup> To ensure maximum efficacy, prepare only as much solution as you will need for the sampling event.

### Suggested equipment:

- Brushes for scrubbing and/or removing mud and vegetation from equipment.
- Hand sanitizers and antiseptic alcohol wipes.
- Handheld bottles and/or pump sprayers for applying bleach and water. Bring clean rinse water.




- Gloves for handling animals. These should be disinfected or discarded between animals.
- Plastic bags of different sizes: examining animals in bag minimizes contact.
- Prepare additional sets of equipment if sampling at multiple locations.
- Trash bags.

## INSTRUCTIONS FOR LARGE EQUIPMENT

Brush off mud, wash with biodegradable soap, disinfect with bleach and rinse all exterior surfaces of boats, canoes, vehicles or trailers and their tires that may have come in contact with potentially affected water (e.g. stream or wetland).

## AFTER EACH SAMPLING EVENT AND BEFORE MOVING TO THE NEXT SITE

1. Brush off mud and vegetation from field equipment (e.g., nets, buckets, boots). Soil or mud can reduce the effectiveness of the disinfection process.
2. Generously spray or immerse all items in bleach solution.
  - Bleach is highly toxic to aquatic organisms; stand at least 50 m from any natural water source.
  - Lab studies indicate 1 minute contact time to be sufficient to inactivate pathogens but NEPARC recommends 5 minutes in field situations.
3. Rinse bleached items with water to minimize damage to the equipment and to prevent exposing the next wetland to residual bleach.
4. Use alcohol wipes to disinfect calipers, measuring boards, and other sensitive equipment.



## END OF THE DAY

After returning from the field, all equipment should be washed and thoroughly disinfected. If available, set up 2 buckets or large tubs: one with soapy water and one with 3% bleach solution.

- Brush or scrub off any soil or vegetation. Immerse into soap, wash then rinse.
- Immerse in bleach and leave for 5 minutes. Rinse thoroughly with water.
  - Hang equipment and gear, and allow them to air dry completely.

# DISINFECTION OPTIONS FOR RANAVIRUS (RV) AND *BATRACHOCHYTRIUM DENDROBATIDIS* (Bd)

Although these chemicals were not developed specifically for RV or Bd, these recommendations represent the minimum concentration and contact time demonstrated as effective

	<b>Clorox Bleach®</b>	<b>Nolvasan®</b>	<b>Virkon S®</b>	<b>Ethanol</b>
<b>Active Ingredient (AI)</b>	Sodium hypochlorite	Chlorhexidine	Potassium peroxymonosulfate	Ethyl alcohol
<b>Concentration of AI</b>	6.0%	2.0%	20.4%	70.0%
<b>Relative cost</b>	\$4.99/gal	\$65.95/gal	\$76.50/10 lb or \$1.60/gal	\$23.45/L or \$88.83/gal
<b>Min. Contact Time RV<sup>9</sup>/Bd<sup>10</sup></b>	1 min / 30 sec	1 min / not determined	1 min / 20 sec	1 min <sup>11</sup> / 20 sec
<b>Min. Concentration RV<sup>9</sup>/Bd<sup>10</sup></b>	3.0% / 1.0%	0.75% / not determined	1.0% / 1.0%	70% / 70%
<b>Effective dilution ratio for both RV and Bd</b>	1:32 dilution (bleach:water) for 3% solution using 6% concentration of household bleach.	1:127 (Nolvasan®: water) for 0.75% solution (RV only)	1 scoop (1.3 oz) or 1 tablet per gal of water	Effective when applied undiluted (70%)
<b>Toxicity to Humans</b>	<ul style="list-style-type: none"> <li>Vapor may cause severe irritation or damage to eyes and skin</li> <li>Harmful if swallowed</li> </ul>	<ul style="list-style-type: none"> <li>May be fatal if inhaled</li> <li>Avoid breathing spray mist</li> <li>Causes irreversible eye damage</li> <li>Harmful if swallowed</li> </ul>	<ul style="list-style-type: none"> <li>Harmful if swallowed</li> <li>Irritating to respiratory system and skin</li> <li>May cause serious eye damage</li> </ul>	<ul style="list-style-type: none"> <li>May be fatal if swallowed or inhaled</li> <li>Can damage liver, kidneys and nervous system by repeated or prolonged exposure</li> <li>May be absorbed through skin. Repeated or prolonged contact can cause eye irritation or dermatitis<sup>12</sup></li> </ul>
<b>Toxicity to Amphibians</b>	<ul style="list-style-type: none"> <li>Fatal at high concentrations</li> </ul>	<ul style="list-style-type: none"> <li>Safe for short durations<sup>13</sup></li> </ul>	<ul style="list-style-type: none"> <li>Non-toxic<sup>14</sup></li> </ul>	<ul style="list-style-type: none"> <li>May destroy mucus and wax resulting in dehydration and microbial infection<sup>11</sup></li> </ul>
<b>Effects on Equipment</b>	<ul style="list-style-type: none"> <li>Corrodes metals</li> <li>Will fade colors and break down cloth fibers</li> </ul>	<ul style="list-style-type: none"> <li>None reported</li> </ul>	<ul style="list-style-type: none"> <li>Safe on fabric</li> <li>May cause pitting on galvanized or soft metal if not rinsed with water</li> </ul>	<ul style="list-style-type: none"> <li>May damage rubber and plastics</li> <li>May cause deterioration of glues<sup>12</sup></li> </ul>

## Special Instructions:

• Remove debris from equipment prior to treatment.<sup>15</sup> • Wear safety glasses and gloves when handling chemicals. • Water pH can affect chemicals; all information in this table assumes the use of tap or municipal water. • Keep out of lakes, streams, or ponds; stand at least 50 m from any natural water source. • Do not clean equipment or dispose of waste solutions at field sites. • For disposal, follow local, state, and federal guidelines.

**Bleach:** Inactivated by organic material. • Inactivated by sunlight. • If in an opaque container, diluted bleach will last 1 month<sup>16</sup>. If exposed to sunlight or air, it will only last 5 days.

**Nolvasan:** Can be inactivated by organic material.<sup>15</sup> • Store at room temperature in sealed container.<sup>17</sup> • Dilute concentrate with water of pH 5-7.<sup>18</sup> • Remains stable for 1 week if dilute with tap water, and for up to 6 weeks if diluted with deionized water.<sup>17</sup> • Use concentrate within 36 months.<sup>17</sup> • Toxic to fish.<sup>18</sup>

**Virkon-S:** Store at room temperature.<sup>19</sup> • Keep solution away from extreme cold or heat. • Shelf life for tablets is 2 years and for powder is 3 years. • Remains stable for 1 week if diluted with tap water.

**Ethanol:** Highly flammable. • Use and store in a well ventilated area. • Evaporation may diminish effective concentration.<sup>12,18</sup>

# CITATIONS FOR DISINFECTION OF FIELD EQUIPMENT TO MINIMIZE RISK OF SPREAD OF CHYTRIDIOMYCOSIS AND RANAVIRUS

1. This information has been compiled in part from Miller, D. L., and M. J. Gray. 2009. Southeastern Partners in Amphibian and Reptile Conservation, Disease, Pathogens and Parasites Task Team, Information Sheet #10.
2. Converse K.A. and D.E. Green. 2005. Diseases of tadpoles. p 72-88. In: Wildlife Diseases: Landscape Epidemiology, Spatial Distribution and Utilization of Remote Sensing Technology. S.K. Majumdar, J.E. Huffman, F.J. Brenner and A.I. Panah (eds.). Pennsylvania Academy of Science, Easton, PA.
3. Picco, A.M., J.L. Brunner, and J.P. Collins. 2007. Susceptibility of the endangered California tiger salamander, *Ambystoma californiense*, to *Ranavirus* infection. *Journal of Wildlife Diseases* 43:286-290.
4. Picco, A.M. and J.P. Collins. 2008. Amphibian commerce as a likely source of pathogen pollution. *Conservation Biology* 22:1582-1589.
5. St-Amour, V., W.M. Wong, T.W.J. Garner, and D. Lesbarreres. 2008. Anthropogenic influence on prevalence of two amphibian pathogens. *Emerging Infectious Diseases* 14:1175-1176.
6. Bryan L., C.A. Baldwin, M.J. Gray, and D.L. Miller. 2009. Efficacy of select disinfectants at inactivating *Ranavirus*. *Diseases of Aquatic Organisms* 84:89-94.
- 7a. Johnson, M. and R. Speare. 2003. Survival of *Batrachochytrium dendrobatidis* in water: quarantine and control implications. *Emerging Infectious Diseases* 9:922-925.
- 7b. Brem F., J.R. Mendelson III, and K.R. Lips. 2007. Field-Sampling Protocol for *Batrachochytrium dendrobatidis* from Living Amphibians, Using Alcohol Preserved Swabs. Version 1.0. <http://www.amphibianark.org/pdf/>, Accessed 19 March 2014.
8. Green, D.E., M.J. Gray and D.L. Miller. 2009. Disease monitoring and biosecurity. p 481-506. In: *Amphibian Ecology and Conservation: A Handbook of Techniques*. C.K. Dodd (ed.). Oxford University Press, Oxford, United Kingdom.
9. Bryan, L. K., Baldwin, C. A., Gray, M. J., & Miller, D. L. (2009). Efficacy of select disinfectants at inactivating *Ranavirus*. *Diseases of Aquatic Organisms* 84:89-94.
10. Johnson. M., L. Berger, L. Philips, and R. Speare. 2003. Fungicidal effects of chemical disinfectants, UV light, dessication. and heat on the amphibian chytrid, *Batrachochytrium dendrobatidis*. *Diseases of Aquatic Organisms* 57:255-260.
11. Phillott A.D., R. Spear, H.B. Hines, E. Meyer, L.F. Skerratt, K.R. McDonald, S.D. Cashins, D.Mendez, and L. Berger. 2010. Minimising exposure of amphibians to pathogens during field studies. *Diseases of Aquatic Organisms* 92:175-185.
12. Simmons, B., M. Trusler, J. Roccaforte, P. Smith, and R. Scott. 1990. Infection control for home health. *Infection Control and Hospital Epidemiology* 11:362-70.
13. Hadfield, C.A. and B.R. Whitaker. 2005. Amphibian emergency medicine and care. *Seminars in Avian and Exotic Pet Medicine* 14:79-89.
14. Schmidt, B. R., C. Geiser, N. Peyer, N. Keller, and M. von Rutte. 2009. Assessing whether disinfectants against the fungus *Batrachochytrium dendrobatidis* have negative effects on tadpoles and zooplankton. *Amphibia-Reptilia* 30: 313-319.
15. Kennedy, J., J. Bek, and D. Griffin. 2000. Selection and Use of Disinfectants. University of Nebraska Cooperative Extension, G00-1410-A.
16. Rutala, W.A. and J.W. Weber. 1997. Uses of inorganic hypochlorite (bleach) in health care facilities. *Clinical Microbiology Reviews* 10:597-610.

## CITATIONS FOR DISINFECTION OF FIELD EQUIPMENT TO MINIMIZE RISK OF SPREAD OF CHYTRIDIOMYCOSIS AND RANAVIRUS (CONTINUED)

17. Zoetis Veterinary Medical Information and Product Support, inquiry 2014-US-03903, 18 March, 2014.
18. Dvorak, G. 2008. Disinfection 101. Center for Food Security and Public Health. <http://www.cfsph.iastate.edu/Disinfection/Assets/Disinfection101.pdf>, Accessed 19 March 2014.
19. Pharmacal Research Laboratories Inc. <http://www.pharmacal.com/MSDS/US/MSDSVIRKON-S%20Tablet.pdf>, Accessed 19 March 2014.

# Three Steps to Minimize Wildlife Disease Transmission Via Construction Equipment

## STEP 1: CLEAN    STEP 2: DISINFECT    STEP 3: DRY

*Aquatic wildlife can be harmed by viruses, bacteria, fungi, and parasites introduced into wetlands. These infectious pathogens can survive in mud, soil, vegetation, and other debris that collect on the bodies and crevices of drivable equipment. Construction and habitat restoration projects can accidentally transport pathogens from a contaminated aquatic habitat into a healthy one. These three steps can help minimize the spread of pathogens to amphibians, reptiles, and fishes.*

### Step 1 **CLEAN** before entering a worksite or relocating to a worksite near wetlands or waterways.

- Clean on site or at a predetermined wash station.
- Detach parts and accessories (buckets, augers, trailers, chains) as needed to access all surfaces.
- Remove all caked-on mud and foreign materials with shovels, pry bars, or stiff brooms.
- Clean equipment in the following sequence:  
*Exterior surfaces (from top to bottom):* roof → sides → undercarriage → fixed attachments → wheels  
*Interior area:* remove seat covers and floor mats to clean separately
- Clean equipment top-to-bottom and exterior-then-interior.
- Power-wash exterior with  $\geq 90$  pounds per square inch water for sediment removal.



### Step 2 **DISINFECT** using chemical agents when your current worksite may have water or soil with pathogens OR when you move equipment between sites more than a half-mile away.

- Disinfect equipment at a dry location more than 165 feet from any wetland or aquatic habitat.
- Apply one of the following reagents\* with a sprayer, then allow it to sit for at least 5 minutes:
  - ▶ 1% potassium peroxymonosulfate solution per manufacturer's instructions (such as 1.3 ounces of Virkon® Aquatic granulated powder per 1 gallon of water).
  - ▶ An effective bleach mixture. Bleach is sold at different concentrations (see graph on the next page for appropriate ratios of water to bleach).
- Prepare solutions as needed to minimize storage time; solutions weaken within 10 days.
- Rinse chemical disinfectants off equipment with liberal amounts of water.
- Follow the manufacturers' Safety Data Sheets to ensure proper handling and disposal.

*\*Any use of trade, product, or firm names is for descriptive purposes only and does not imply endorsement by the U.S. Government.*

### Step 3 **DRY** outdoors, ideally in direct sunlight, for at least:

- 5 days if the equipment was cleaned but NOT disinfected, or
- 24 hours if the equipment was cleaned AND disinfected.



**NORTHEAST  
PARTNERS  
IN  
PARC**  
AMPHIBIAN AND REPTILE CONSERVATION


**CONTINUED ON BACK**

## CREATING AN EFFECTIVE BLEACH MIXTURE

The appropriate water-to-bleach mixture will depend on the bleach concentration as measured by its %active ingredient (AI) of sodium hypochlorite (NaClO). To make an appropriate mixture (~3% bleach solution):

1. Use the vertical axis to locate the **gallons of water** you're using.
2. Follow that horizontal line to the right until you intersect the diagonal line for the **bleach concentration** being used.
3. Follow the vertical line at this intersection downward to determine the **quarts of bleach solution** to add to your **gallons of water**. If the intersection is between two vertical lines, use the vertical line to the right of the intersection.

**Example:** For 50 gallons of water, use either:  
3 quarts of a 12.00% bleach concentration OR  
4 quarts + 1 cup of a 8.25% bleach OR  
6 quarts of a 6.00% bleach OR  
6 quarts + 3 cups of a 5.25% bleach



### ADDITIONAL SUGGESTIONS FOR MINIMIZING THE SPREAD OF PATHOGENS

**Alternatives for difficult-to-clean materials:** Traditional wooden mats that are used to protect wetland substrates from vehicular traffic are not recommended because they are very difficult to clean before relocating them to a different worksite. As an alternative, a composite matting system is nonporous and is easier to clean, dry, and reuse. Although initially more expensive than wooden mats, its durability, extended life, and ease of cleaning may offset costs.

**Materials with low risk of introducing pathogens:** Native materials obtained *on site*, such as topsoil, logs, wood-chipped vegetation, and streambed rocks, can be used with little risk of introducing new pathogens. The following materials brought into a worksite also have a low risk of containing pathogens:

- Crushed stone for activities requiring roadbeds or temporary stream crossings
- Manufactured sand and rock dust for padding underground pipes and filling sandbags
- Kiln-dried hay or straw bales instead of untreated hay for sediment filtration

Avoid reusing materials between sites with a higher risk of introducing pathogens, such as wooden mats, plywood, and silt fencing.

**Decontaminating hand-held equipment, outerwear, and tools:** If exposed to wetland debris, these items should be cleaned and disinfected daily and, if possible, at the worksite. Porous items that retain water should be cleaned, disinfected, and allowed to air dry. Written instructions on disinfecting these items are found at <http://northeastparc.org/disinfection-protocol/> and a video is available at [https://www.youtube.com/watch?v=\\_SZZiSIWyc](https://www.youtube.com/watch?v=_SZZiSIWyc)

These steps are explained in detail in the article

**Minimizing the Spread of Herpetofaunal Pathogens in Aquatic Habitats by Decontaminating Construction Equipment**  
<http://northeastparc.org/wp-content/uploads/2021/01/Julian-2020-Decontamination-for-Herps-for-large-equipment.pdf>



**From:** [Personeus, Neal \(DEM\)](#)  
**To:** [Lauren Blair](#)  
**Cc:** [Stephen Olson](#)  
**Subject:** RE: [EXTERNAL] : RE: Prudence Island groundwater discharge permit question  
**Date:** Monday, July 25, 2022 10:29:43 AM  
**Attachments:** [image001.png](#)

---

Hi Lauren,

I'm back in the office this week. I did have a chance to meet with someone in the office before I left to discuss this. We can go along with processing a UIC permit application for this discharge provided the RI Department of Health gives it their blessing for the discharge within the well radius. On another note, it may also be worth your looking into designing a surficial sand filter for the discharge rather than going with the UIC. Provided your flow rates and volumes are acceptable, you could design a system based upon the requirements of the RI Stormwater Installation Standards Manual and just make sure it is dedicated for this use only and does not mix with any other flow including stormwater. There would need to be signage indicating such. If this concept is of interest to you let me know and we can discuss it further. This option may provide a way to avoid any permitting and/or registration with the EPA, which would come with a UIC permit.

Neal

---

**From:** Lauren Blair <lab@h2olsonengineering.com>  
**Sent:** Wednesday, July 13, 2022 11:43 AM  
**To:** Personeus, Neal (DEM) <neal.personeus@dem.ri.gov>  
**Cc:** Stephen Olson <sco@h2olsonengineering.com>  
**Subject:** [EXTERNAL] : RE: Prudence Island groundwater discharge permit question

Hello Neal,

I hope you are doing well. I wanted to follow up on these questions again and see if you were able to look over the plans for the site. We would be happy to know any comments or suggestions that you have. We are hoping to get these permit applications finished up this week.

Thank you,

**Lauren Blair | Engineering Intern**  
**H<sub>2</sub>Olson Engineering, Inc.**

10 Riverside Drive, Suite 103

Lakeville, MA 02347

O: 508.375.7007 | C: 941.348.8209

[www.h2olsonengineering.com](http://www.h2olsonengineering.com) [[h2olsonengineering.com](http://h2olsonengineering.com)]



---

**From:** Lauren Blair  
**Sent:** Thursday, June 30, 2022 11:15 AM  
**To:** 'Personeus, Neal (DEM)' <[neal.personeus@dem.ri.gov](mailto:neal.personeus@dem.ri.gov)>  
**Cc:** Stephen Olson <[sco@h2olsonengineering.com](mailto:sco@h2olsonengineering.com)>  
**Subject:** RE: Prudence Island groundwater discharge permit question

Hi Neal,

Thank you for getting back with me. I am attaching the full set of design plans for this project. There are two sites involved – Indian Springs well and Army Camp well. The Army Camp well site has the analyzer line and the plans for the dry well. Sheet C-6 shows the proposed conditions plan for the Army Camp well site and sheet C-8 shows the details of the discharge systems, including the dry well for Army Camp. I am also cc'ing Steve Olson, President of H2Olson Engineering, onto this email. We would be happy to hear your input. I hope you have a great holiday weekend!

All the best,

**Lauren Blair | Engineering Intern**  
**H<sub>2</sub>Olson Engineering, Inc.**

10 Riverside Drive, Suite 103  
Lakeville, MA 02347

O: 508.375.7007 | C: 941.348.8209

[www.h2olsonengineering.com](http://www.h2olsonengineering.com) [[h2olsonengineering.com](http://h2olsonengineering.com)]



---

**From:** Personeus, Neal (DEM) <[neal.personeus@dem.ri.gov](mailto:neal.personeus@dem.ri.gov)>  
**Sent:** Wednesday, June 29, 2022 2:40 PM  
**To:** Lauren Blair <[lab@h2olsonengineering.com](mailto:lab@h2olsonengineering.com)>  
**Cc:** Pena, Traci (DEM) <[traci.pena@dem.ri.gov](mailto:traci.pena@dem.ri.gov)>; Beck, Eric (DEM) <[eric.beck@dem.ri.gov](mailto:eric.beck@dem.ri.gov)>  
**Subject:** Prudence Island groundwater discharge permit question

Hi Lauren,

I was forwarded a request from you regarding a proposed subsurface discharge permit. It sounds as though you are on the right permit track. I would like to see the overall site design, but if what I'm thinking is correct, there may be an easier and less expensive way to deal with the disinfected analyzer line water. I am out of the office until next Tuesday but will be available then if you want to go over it.

Neal Personeus  
Sen. Env. Scientist/Project Mgr.



July 21, 2022

Paul Jordan  
Rhode Island Department of Environmental Management  
235 Promenade Street  
Providence, RI 02908  
401-222-4700 ext. 2774316  
paul.jordan@dem.ri.gov

SUBJECT: Identification of Disturbance to Threatened or Endangered species

PROJECT: Prudence Island Water District, Proposed Water Treatment Facilities

Dear Paul Jordan:

The Prudence Island Water District (PIWD) is under an Administrative Consent Order (ACO) with the Rhode Island Department of Health (RIDOH) to install permanent disinfection facilities for their two water supply sources, including the pre-treatment for the removal of iron and manganese at the Indian Springs well site. PIWD retained the services of H2Olson Engineering, Inc. (10 Riverside Drive, Lakeville, MA 02347) to complete the design and permitting of these facilities in accordance with RIDOH ACO requirements.

One of the requirements of the State Environmental Review Process is to have the relevant agencies review the proposed project and comment on any potential environmental impacts. We are requesting the review of the Rhode Island Department of Environmental Management to determine any impacts of the project to threatened or endangered species. As such, I am attaching the following documents for your use and information:


- A proposed scope of work generally describing the project components.
- A copy of the project overview plan showing the project limits.
- Proposed site location.

Can you please review the attached information and let me know if you have any comments or concerns with the proposed water treatment project on Prudence Island? The project is being propped to improve the water quality and protect the public health for PIWD customers.

Review comments are requested within 30 days of receipt of this letter.

If you have any questions, please feel free to contact us at 508-375-7007 at your convenience.

Very Truly Yours,  
H2Olson Engineering, Inc.



Stephen C. Olson, P.E.  
President



**From:** Jordan, Paul (DEM) <[paul.jordan@dem.ri.gov](mailto:paul.jordan@dem.ri.gov)>  
**Sent:** Thursday, July 21, 2022 2:16 PM  
**To:** Stephen Olson; Lauren Blair  
**Subject:** RE: [EXTERNAL] : Request for Project Review

The two species observations are about 1200 feet west of the parcel boundary. The habitat is essentially the same across the entire area.

---

**From:** Stephen Olson <[sco@h2olsonengineering.com](mailto:sco@h2olsonengineering.com)>  
**Sent:** Thursday, July 21, 2022 2:11 PM  
**To:** Jordan, Paul (DEM) <[paul.jordan@dem.ri.gov](mailto:paul.jordan@dem.ri.gov)>; Lauren Blair <[lab@h2olsonengineering.com](mailto:lab@h2olsonengineering.com)>  
**Subject:** RE: [EXTERNAL] : Request for Project Review

Thank you.

Would it be possible to prepare a map of the Indian Springs site with the habit overlaid?

From your below e-mail my assumption is that our project site does not include any habitat, and the buffer to the closet habitat for endangered species is 2,500 feet. Do I have that correct?

Thank you for your assistance.

~ Steve O



---

**From:** Jordan, Paul (DEM) <[paul.jordan@dem.ri.gov](mailto:paul.jordan@dem.ri.gov)>  
**Sent:** Thursday, July 21, 2022 1:48 PM  
**To:** Stephen Olson <[sco@h2olsonengineering.com](mailto:sco@h2olsonengineering.com)>; Lauren Blair <[lab@h2olsonengineering.com](mailto:lab@h2olsonengineering.com)>  
**Subject:** RE: [EXTERNAL] : Request for Project Review

No, the data points are not shared publicly.  
Paul

---

**From:** Stephen Olson <[sco@h2olsonengineering.com](mailto:sco@h2olsonengineering.com)>  
**Sent:** Thursday, July 21, 2022 1:45 PM  
**To:** Jordan, Paul (DEM) <[paul.jordan@dem.ri.gov](mailto:paul.jordan@dem.ri.gov)>; Lauren Blair <[lab@h2olsonengineering.com](mailto:lab@h2olsonengineering.com)>  
**Subject:** RE: [EXTERNAL] : Request for Project Review

Thanks Paul.

Are the RI Natural Heritage maps located on-line or in a GIS database?

~ Steve O



---

**From:** Jordan, Paul (DEM) <[paul.jordan@dem.ri.gov](mailto:paul.jordan@dem.ri.gov)>  
**Sent:** Thursday, July 21, 2022 1:36 PM  
**To:** Lauren Blair <[lab@h2olsonengineering.com](mailto:lab@h2olsonengineering.com)>; Stephen Olson <[sco@h2olsonengineering.com](mailto:sco@h2olsonengineering.com)>  
**Subject:** RE: [EXTERNAL] : Request for Project Review

Hi Lauren,

These are the RI Natural Heritage records located within 2,500 feet of the Indian Springs site.

#	Family	Genus	Species	COMNAME	SurveyYear	LastSeen	St
1	Insect	Cicindela	formosa generosa	Pine Barrens Tiger Beetle	1996	1996	State Threat
2	Insect	Cicindela	tranquebarica	A Tiger Beetle	1995	1995	State Threat
3	Poaceae	Aristida	purpurascens var. purpurascens	Purple or Arrowfeather Three-awn, Triple-awned Grass	2021	2021	State Threat

There are no records associated with the Army Camp site.

All the best,  
Paul

Paul Jordan  
Data Analyst II / Geographic Information System  
RI Dept. Of Environmental Management  
235 Promenade Street  
Providence, RI 02908  
(401) 222-2776 x277-4315  
[paul.jordan@dem.ri.gov](mailto:paul.jordan@dem.ri.gov)  
<http://www.dem.ri.gov/maps/>

---

**From:** Lauren Blair <[lab@h2olsonengineering.com](mailto:lab@h2olsonengineering.com)>  
**Sent:** Thursday, July 21, 2022 1:03 PM

**To:** Jordan, Paul (DEM) <[paul.jordan@dem.ri.gov](mailto:paul.jordan@dem.ri.gov)>; Stephen Olson <[sco@h2olsonengineering.com](mailto:sco@h2olsonengineering.com)>  
**Subject:** [EXTERNAL] : Request for Project Review

Dear Paul Jordan,

I hope this email finds you well. H2Olson Engineering is seeking review comments from the Rhode Island Department of Environmental Management regarding a proposed water treatment project on Prudence Island, in accordance with the State Environmental Review Process. We were directed to your contact information by David Gregg of the Rhode Island Natural History Survey. The attached documents provide further information on this request and the proposed project. Please let us know if you have any questions or concerns. We look forward to hearing from you.

Best regards,

**Lauren Blair | Engineering Intern**

**H<sub>2</sub>Olson Engineering, Inc.**

10 Riverside Drive, Suite 103

Lakeville, MA 02347

O: 508.375.7007 | C: 941.348.8209

[www.h2olsonengineering.com](http://www.h2olsonengineering.com) [[h2olsonengineering.com](http://h2olsonengineering.com)]









July 18, 2022

Meredith Brady  
Associate Director for Planning  
Rhode Island Statewide Planning Program  
235 Promenade Street, Suite #230  
Providence, RI 02908  
401-222-6496  
meredith.brady@doa.ri.gov

SUBJECT: Intergovernmental Review Comments

PROJECT: Prudence Island Water District, Proposed Water Treatment Facilities

Dear Meredith Brady:

The Prudence Island Water District (PIWD) is under an Administrative Consent Order (ACO) with the Rhode Island Department of Health (RIDOH) to install permanent disinfection facilities for their two water supply sources, including the pre-treatment for the removal of iron and manganese at the Indian Springs well site. PIWD retained the services of H2Olson Engineering, Inc. (10 Riverside Drive, Lakeville, MA 02347) to complete the design and permitting of these facilities in accordance with RIDOH ACO requirements.

One of the requirements of the State Environmental Review Process is to have the Division of Planning review the proposed project and comment on the potential impact that the project might have on any Federal or State Programs, including zoning or land use issues. As such, I am attaching the following documents for your use and information:


- A proposed scope of work generally describing the project components.
- A copy of the project overview plan showing the project limits.
- Proposed site location.

Can you please review the attached information and let me know if you have any comments or concerns with the proposed water treatment project on Prudence Island? The project is being propped to improve the water quality and protect the public health for PIWD customers.

Review comments are requested within 30 days of receipt of this letter.

If you have any questions, please feel free to contact us at 508-375-7007 at your convenience.

Very truly yours,  
H2Olson Engineering, Inc



Stephen C. Olson, P.E.  
President



## Lauren Blair

---

**From:** Hess, Nancy (DOA) <Nancy.Hess@doa.ri.gov>  
**Sent:** Monday, August 22, 2022 8:03 AM  
**To:** RIDWQ, DOH (RIDOH)  
**Cc:** Lauren Blair  
**Subject:** Environmental Review - water treatment project on Prudence Island  
**Attachments:** Review Request RI Statewide Planning.pdf; PIWD - Drawings for Permit Letters.pdf; PIWD - Technical Memorandum for Permit Letters.pdf

Good afternoon.

We received a direct request for comments on the environmental review from Lauren Blair, an engineering intern at H<sub>2</sub>Olson Engineering, Inc. on behalf of Prudence Island water system. We did not see the number of expected people served, although it does give GPD estimates. This project seems to be quite specific in the removal of metals (iron and manganese) from the wells. **We have no comments on the limited scope of this proposal.**

For speedier replies in the future, would you please advise consultants snail mail is no longer necessary as scanned materials can be sent direct to me by email.

Thank you.

### **Nancy Hess**

Interdepartmental Project Manager  
Division of Statewide Planning  
235 Promenade Street, Suite 230  
Providence, RI 02908  
401-222-6480  
[www.planning.ri.gov](http://www.planning.ri.gov)





July 20, 2022

Lea Hitchen  
Portsmouth Town Planner  
2200 E. Main Road  
Portsmouth, RI 0287  
401-643-0332  
lhitchen@portsmouthri.gov

SUBJECT: Identification of Zoning Issues

PROJECT: Prudence Island Water District, Proposed Water Treatment Facilities

Dear Lea Hitchen:

The Prudence Island Water District (PIWD) is under an Administrative Consent Order (ACO) with the Rhode Island Department of Health (RIDOH) to install permanent disinfection facilities for their two water supply sources, including the pre-treatment for the removal of iron and manganese at the Indian Springs well site. PIWD retained the services of H2Olson Engineering, Inc. (10 Riverside Drive, Lakeville, MA 02347) to complete the design and permitting of these facilities in accordance with RIDOH ACO requirements.

One of the requirements of the State Environmental Review Process is to have the Planning Department review the proposed project and comment on any potential zoning conflicts. As such, I am attaching the following documents for your use and information:


- A proposed scope of work generally describing the project components.
- A copy of the project overview plan showing the project limits.
- Proposed site location.

Can you please review the attached information and let me know if you have any comments or concerns with the proposed water treatment project on Prudence Island? The project is being propped to improve the water quality and protect the public health for PIWD customers.

Review comments are requested within 30 days of receipt of this letter.


If you have any questions, please feel free to contact us at 508-375-7007 at your convenience.

Very Truly Yours,  
H2Olson Engineering, Inc.



Stephen C. Olson, P.E.  
President





# TOWN OF PORTSMOUTH

2200 East Main Road / Portsmouth, Rhode Island 02871

(401) 643-0332 / [www.portsmouthri.gov](http://www.portsmouthri.gov)

Lea Hitchen  
Town Planner

[www.portsmouthri.gov](http://www.portsmouthri.gov)  
[lhitchen@portsmouthri.gov](mailto:lhitchen@portsmouthri.gov)

August 2, 2022

Mr. Stephen C. Olson, P.E.  
H2Olson Engineering, Inc.  
10 Riverside Drive, Suite 103  
Lakeville, MA 02347

**RE: Prudence Island Water District, Proposed Water Treatment Facilities (Project No. 19.21.01)**

Dear Mr. Olson,

Thank you for providing me the opportunity to review the designs and plans for the proposed water pre-treatment systems at the "Army Camp" and "Indian Springs" well sites on Prudence Island that have been prepared by your office. I have reviewed the scope of work, project plans and proposed site locations and find there to be no evidence of zoning conflicts with either site.

The "Indian Springs" well site is owned by the Prudence Island Water District (PIWD), being located at 024 Homestead Avenue, Map 76 Plat 5A, consisting of 5.14 acres, and is zoned "Residential-60." The Indian Springs site calls for the construction of a proposed 23'x23' well house building along with four (4) new crushed stone parking spaces which will be located within the building envelope and meet all dimensional requirements per the Zoning Ordinance.

The "Army Camp" well site, being located at on property owned by The Prudence Conservancy, being Map 80 Lot 4, already has an existing 12' x 12' well house on the parcel. Upon review of this site, it does not appear there are any applicable sections of the Zoning Ordinance that are relevant to this portion of the project. The proposed limit of work appears to extend beyond the approximate PIWD easement line; I suggest legal counsel of all parties involved properly evaluate the issue.

In summary I find the project to be consistent with the Comprehensive Community Plan, specifically Element 9, Water Supply, as the plan specifically identifies the drinking water for Prudence Island residents as a critical natural resource as it is sourced from groundwater wells which are threatened. The installation of permanent disinfection facilities for Prudence Island's two water supply sources will satisfactorily address the goals and policies set forth for distributing safe drinking water. Secondly, the proposal is in compliance with the purpose and intent of the Portsmouth Zoning Ordinance, particularly Chapter 405, Article IV, District Intensity Regulations, Section B, Land Space Requirements Table.

Please accept this letter as notice of said zoning concerns. Should you have any questions, please do not hesitate to contact me.

Sincerely,

Lea Hitchen  
Town Planner

cc: Richard Rainer, Town Manager  
Kevin Gavin, Town Solicitor  
Gareth Eames, Building Official  
Robin Weber, PIWD Moderator







July 18, 2022

Elizabeth Totten  
Project Review  
Rhode Island Historic Preservation and Heritage Commission  
150 Benefit Street  
Providence, RI 02903  
401-222-2671  
elizabeth.totten@preservation.ri.gov

SUBJECT: Identification of Historic and/or Archaeological Resources

PROJECT: Prudence Island Water District, Proposed Water Treatment Facilities

Dear Elizabeth Totten:

The Prudence Island Water District (PIWD) is under an Administrative Consent Order (ACO) with the Rhode Island Department of Health (RIDOH) to install permanent disinfection facilities for their two water supply sources, including the pre-treatment for the removal of iron and manganese at the Indian Springs well site. PIWD retained the services of H2Olson Engineering, Inc. (10 Riverside Drive, Lakeville, MA 02347) to complete the design and permitting of these facilities in accordance with RIDOH ACO requirements.

One of the requirements of the State Environmental Review Process is to have the Historic Preservation and Heritage Commission review the proposed project and comment on the potential impact that the project might have on any historic and/or archaeological resources. As such, I am attaching the following documents for your use and information:

- A proposed scope of work generally describing the project components.
- A copy of the project overview plan showing the project limits.
- Proposed site location.

Can you please review the attached information and let me know if you have any comments or concerns with the proposed water treatment project on Prudence Island? The project is being propped to improve the water quality and protect the public health for PIWD customers.

Review comments are requested within 30 days of receipt of this letter.  
If you have any questions, please feel free to contact us at 508-375-7007 at your convenience.

Very Truly Yours,  
H2Olson Engineering, Inc.

Stephen C. Olson, P.E.  
President





STATE OF RHODE ISLAND

HISTORICAL PRESERVATION & HERITAGE COMMISSION

Old State House 150 Benefit Street Providence, RI 02903

Telephone 401-222-2678  
TTY 401-222-3700

Fax 401-222-2968  
[www.preservation.ri.gov](http://www.preservation.ri.gov)

August 19, 2022

Via email: [sco@h2olsonengineering.com](mailto:sco@h2olsonengineering.com)

Stephen C. Olson, P.E.  
President  
H2Olson Engineering, Inc.  
10 Riverside Drive  
Lakeville, MA 02347

Re: RIHPHC Project No. 16772  
Prudence Island Water District  
Portsmouth, Rhode Island

Dear Mr. Olson:

The Rhode Island Historical Preservation and Heritage Commission (RIHPHC) staff has reviewed the information that you provided for the above-referenced project. The Prudence Island Water District is proposing to install permanent disinfection facilities for two water supply sources on Prudence Island at Indians Springs and the Army Camp.

Based on our review of available information, it is the conclusion of the RIHPHC that no historic properties will be affected by the project.

These comments are provided in accordance with the Rhode Island Historic Preservation Act and Rhode Island General Laws. If you have any questions, please contact RIHPHC Project Review Coordinator Elizabeth Totten at 401-222-2671 or [elizabeth.totten@preservation.ri.gov](mailto:elizabeth.totten@preservation.ri.gov).

Sincerely,

Jeffrey Emidy  
Interim Executive Director  
Interim State Historic Preservation Officer





July 18, 2022

John Brown  
Narragansett Tribal Historic Preservation Office  
4425 South County Trail  
Charlestown, RI 02813

**SUBJECT:** Identification of Historic/Archaeological Resources and Land Use Impacts

**PROJECT:** Prudence Island Water District, Proposed Water Treatment Facilities

Dear John Brown:

The Prudence Island Water District (PIWD) is under an Administrative Consent Order (ACO) with the Rhode Island Department of Health (RIDOH) to install permanent disinfection facilities for their two water supply sources, including the pre-treatment for the removal of iron and manganese at the Indian Springs well site. PIWD retained the services of H2Olson Engineering, Inc. (10 Riverside Drive, Lakeville, MA 02347) to complete the design and permitting of these facilities in accordance with RIDOH ACO requirements.

One of the requirements of the State Environmental Review Process is to have the Narragansett Tribal Historic Preservation Office review the proposed project and comment on the potential impact that the project might have on any historical/archaeological resources or lands related to the Narragansett Tribe. As such, I am attaching the following documents for your use and information:

- A proposed scope of work generally describing the project components.
- A copy of the project overview plan showing the project limits.
- Proposed site location.

Can you please review the attached information and let me know if you have any comments or concerns with the proposed water treatment project on Prudence Island? The project is being propped to improve the water quality and protect the public health for PIWD customers.

Review comments are requested within 30 days of receipt of this letter.

If you have any questions, please feel free to contact us at 508-375-7007 at your convenience.

Very Truly Yours,  
H2Olson Engineering, Inc.

Stephen C. Olson, P.E.  
President





July 18, 2022

Aja Szumylo  
Acting Deputy Regional Administrator  
NOAA Fisheries Greater Atlantic Regional Fisheries Office  
55 Great Republic Drive  
Gloucester, MA 01930  
206-526-4746  
aja.szumylo@noaa.gov

**SUBJECT:** Identification of Fisheries Impacts

**PROJECT:** Prudence Island Water District, Proposed Water Treatment Facilities

Dear Aja Szumylo:

The Prudence Island Water District (PIWD) is under an Administrative Consent Order (ACO) with the Rhode Island Department of Health (RIDOH) to install permanent disinfection facilities for their two water supply sources, including the pre-treatment for the removal of iron and manganese at the Indian Springs well site. PIWD retained the services of H2Olson Engineering, Inc. (10 Riverside Drive, Lakeville, MA 02347) to complete the design and permitting of these facilities in accordance with RIDOH ACO requirements.

One of the requirements of the State Environmental Review Process is to have the NOAA Fisheries Greater Atlantic Regional Fisheries Office review the proposed project and comment on the potential impact that the project might have on fisheries in the area. As such, I am attaching the following documents for your use and information:


- A proposed scope of work generally describing the project components.
- A copy of the project overview plan showing the project limits.
- Proposed site location.

Can you please review the attached information and let me know if you have any comments or concerns with the proposed water treatment project on Prudence Island? The project is being propped to improve the water quality and protect the public health for PIWD customers.

Review comments are requested within 30 days of receipt of this letter.

If you have any questions, please feel free to contact us at 508-375-7007 at your convenience.

Very Truly Yours,  
H2Olson Engineering, Inc.



Stephen C. Olson, P.E.  
President





**From:** [Sabrina Pereira - NOAA Federal](#)  
**To:** [Lauren Blair](#)  
**Subject:** Re: Request for Project Review  
**Date:** Thursday, August 11, 2022 11:44:20 AM  
**Attachments:** [image001.png](#)

---

Hi Lauren,

Thank you for reaching out and sending these materials. We agree that some of the construction activities associated with the installation of water disinfection facilities for the Prudence Island water district may adversely affect Essential Fish Habitat. However the avoidance and minimization measures, like sedimentation controls outlined in the project drawings, adequately minimize adverse effects, and we have no conservation recommendations to provide.

Thank you, and please let me know if you have any questions.

Best regards,

**Sabrina Pereira**

Marine Resources Management Specialist  
Habitat and Ecosystem Services Division  
NOAA/ National Marine Fisheries Service  
Gloucester, MA

Pronouns: she/her/hers

(978)-675-2178

[Sabrina.pereira@noaa.gov](mailto:Sabrina.pereira@noaa.gov)

On Fri, Jul 22, 2022 at 11:38 AM Christopher Boelke - NOAA Federal  
<[christopher.boelke@noaa.gov](mailto:christopher.boelke@noaa.gov)> wrote:

At this point, I do not think we have any action to take under the state process, so just FYI

----- Forwarded message -----

From: **Lou Chiarella - NOAA Federal** <[lou.chiarella@noaa.gov](mailto:lou.chiarella@noaa.gov)>

Date: Fri, Jul 22, 2022 at 10:52 AM

Subject: Fwd: Request for Project Review

To: Chris Boelke <[Christopher.Boelke@noaa.gov](mailto:Christopher.Boelke@noaa.gov)>

Chris,

I don't know how you want to handle this.

Lou Chiarella  
Assistant Regional Administrator  
for Habitat and Ecosystem Services  
NOAA/National Marine Fisheries Service  
Greater Atlantic Regional Fisheries Office  
55 Great Republic Drive  
Gloucester, MA 01930

978-281-9277

----- Forwarded message -----

From: **Aja Szumylo - NOAA Federal** <[aja.szumylo@noaa.gov](mailto:aja.szumylo@noaa.gov)>

Date: Fri, Jul 22, 2022 at 5:04 AM

Subject: Fwd: Request for Project Review

To: Lou Chiarella - NOAA Federal <[lou.chiarella@noaa.gov](mailto:lou.chiarella@noaa.gov)>, Jennifer Anderson - NOAA Federal <[jennifer.anderson@noaa.gov](mailto:jennifer.anderson@noaa.gov)>, Julie Crocker - NOAA Federal <[julie.crocker@noaa.gov](mailto:julie.crocker@noaa.gov)>

Hi Lou and Julie-

Forwarding to your groups for review. How do these typically come in to you?

Aja

----- Forwarded message -----

From: **Lauren Blair** <[lab@h2olsonengineering.com](mailto:lab@h2olsonengineering.com)>

Date: Wed, Jul 20, 2022 at 10:59 AM

Subject: Request for Project Review

To: [aja.szumylo@noaa.gov](mailto:aja.szumylo@noaa.gov) <[aja.szumylo@noaa.gov](mailto:aja.szumylo@noaa.gov)>

Dear Aja Szumylo,

I hope this email finds you well. H2Olson Engineering is seeking review comments from the NOAA Greater Atlantic Regional Fisheries Office regarding a proposed water treatment project on Prudence Island, in accordance with the Rhode Island State Environmental Review Process. The attached documents provide further information on this request and the proposed project. A copy of these items will be sent by mail as well. Please let us know if you have any questions or concerns. We look forward to hearing from you.

Best regards,

**Lauren Blair | Engineering Intern**

**H<sub>2</sub>Olson Engineering, Inc.**

10 Riverside Drive, Suite 103